LOAN TO BRITAIN

. . . Investment in World Economic Unity

CONGRESS should give swift and confident approval to the proposed loan to Great Britain.

Few other issues of foreign policy in the present troubled world lend themselves to such clear appraisal of where our National interest lies.

In simplest terms, the question is whether we should extend to Great Britain a credit of $3¾ billions (plus $650 millions in payment for lend-lease balances) in return for her promise to repay principal with interest over a fifty year period starting at the end of 1951, and her pledge to give the fullest possible support to the kind of world trading system which it is the declared policy of both the United States and the United Nations Organization to promote.

We Can Afford to Make It

The sum we hazard is not inconsiderable, but financial risks have meaning only when related to resources. The line of credit provided by the loan will amount, at most, to a claim on 2/5 of 1 per cent of our gross output for the five to six year period over which it may be used. The interest rate charged, while moderate, is higher than our Treasury is paying upon current borrowings. The risk entailed is well within our resources as a creditor. In the considered judgment of the American and British technical experts who thrashed through the intricate accounting for three painful months, the amount and terms offered will suffice to allow Britain, under rigid austerity, to relax her system of foreign trade restrictions, and to expand exports sufficiently to pay her debt commitments.

Against the considered risks of extending the loan, there must be weighed the certain costs of refusing it. Without the loan, Britain has no recourse but to maintain and extend the system of bloc trading which she adopted under stress of world depression and world war. If that is the route Britain follows, she will carry with her a large part of the sterling area countries — all British Commonwealth and Empire countries (except Newfoundland and Canada) plus Egypt, Iraq, and Iceland—and many of the nations with which the United Kingdom has payment agreements (Argentina, Bolivia, Brazil, Chile, Paraguay, Peru, Uruguay, Belgium, Czechoslovakia, Denmark, Finland, France, Netherlands, Norway, Portugal, Spain, Sweden, and Turkey).

Altogether, the United Kingdom's orbit accounts for more than half of the world's imports and exports combined. It likewise is crucial to the trade of the United States. In the years immediately preceding the war, the sterling area and payment-agreement countries provided just under one-half of both the import and export trade of this country.

Russia, of course, will continue to conduct her foreign commerce exclusively upon a state-trading basis. Before the war, the Soviet Union transacted only a little more than 1 per cent of foreign trade business, but its future sphere of influence will be large—conceivably embracing as much as 30 per cent of total international trade.

We Cannot Afford to Refuse It

If the weight of British influence in foreign trade is thrown toward the Russian pattern rather than toward ours, it is apparent that bloc trading, with all of is supporting devices—bilateral deals, exchange controls, import and export quotas, subsidies, currency manipulations and the like —will be the prevailing pattern for foreign transactions.

In self-protection, the United States would have no alternative but to conform to the dominant pattern. We should be forced to form our own bloc, and to enter into active economic warfare in bidding for trade concessions against the offers of our rivals. How well we would do this is problematical. To the game we would bring the largest economic potential in the world. But our handicaps would be equally impressive.

First, under a system in which political and economic motivations are inextricably fused, a democratic nation, and particularly one with a tradition of freedom in its domestic enterprise, would operate at a great disadvantage. We should inevitably be driven toward more and more government control of our entire economy.

Second, with a pattern of foreign trade in which our exports habitually are greater than our imports, our bargaining position in international trade is much weaker than our over-all economic strength would suggest. Under state-controlled trading we should still find it difficult to compete successfully without resort to loans, and under these conditions our loans would be supporting a system alien to our choice and interest.

Third, under a regimented system which made economic decisions subservient to political considerations, it is virtually certain that the volume of world trade would shrink. That was the clear experience of the nineteen-thirties. Thus, the

standard of living in the United States would suffer in common with all others, and we would be forced into a particularly drastic curtailment of certain war-expanded segments of our economy, at the very time when a large portion of the world is most in need of the products they can produce.

Weighing the Alternative Costs

In the years immediately ahead it is certain that from two-thirds to three-quarters of all international trade will be transacted either in pounds or dollars. If both circuits are linked in a determined effort to restore competitive world markets, to which buyers and sellers alike have access without discrimination, that will be the dominant system of foreign trade. If the sterling group with its satellites organizes a closed grid, our exclusive effort cannot preserve the trade pattern that we believe offers most to us and to the world.

No one can accurately measure the costs to the United States of refusing the loan and accepting the consequences. But unquestionably they would dwarf to insignificance the sum risked in the proposed credit. We would lose through the shrinkage of our trade, through the wrench of violent readjustments in our production patterns, and eventually through the curtailment of our over-all output below what it would be under an open rather than a closed system. We would lose heavily in economic liberty under a procedure that can be followed with success only by a close regimentation of production as well as trade.

Most of all, we would lose in prestige, through demonstrating that we are still unprepared to exercise a world leadership to which our giant stature as the possessor of almost half of the world's economic capacity entitles us. Once again we would be exhibiting to the world political feet of clay supporting an economic frame of heroic proportions.

It Is Far from a "Soft" Bargain

There has been some disposition in this country to regard the loan to Britain as a somewhat "soft" and generally unprecedented transaction that smacks of charity. This is the sheerest nonsense.

In the first place, the kind of economic system we want has never functioned and cannot operate now without a lender. For many decades prior to World War I Great Britain filled the creditor role. In 1913 her foreign investments totaled $19 billions, and she not only made such transactions pay, but they proved her salvation through two grim wars. Her credits helped in the industrial development of a large segment of the world, including the United States. Of all the nations in the world, only the United States can assume now the mantle which Britain no longer can support.

In the second place, the terms of our proposed loan to the United Kingdom are far from easy. Britain put a substantially greater proportion of her relatively meager resources into the war than we did, and dissipated a large share of her foreign holdings in the process while accumulating an outside debt of crushing magnitude. On a per capita basis her internal debt is greater than ours. Many Britons feel that our proposed loan is too small, and its terms too rigorous. If the amount proves to be inadequate, we shall have to consider supplemental aid at a later date. But the majority believe that the present offer gives a fighting chance to restore the system of world trade that we and they both want, and upon which the World Bank, the Monetary Fund, and the International Trade Organization under United Nations aegis are based. It is certain that without our loan all of this will go by the board.

In the third place, our proposed loan is far from being without precedent. Canada, which is linked by far closer economic ties to us than to the Empire, already has provided for a loan to Britain of $1,200,000,000. This amounts to almost a third of what we propose to lend, although Canada's population is less than 10 per cent, and her income is little more than 5 per cent of ours.

Shall the United States Lead or Follow?

The way to exercise leadership is to lead. Nothing could be more futile than to go half way toward establishing the economic order for which we stand, and then withhold the crucial measure that will make it work. Failure to approve the loan to Britain will be a clear default of leadership. Failure to approve it promptly will dissipate its effectiveness.

It has been officially stated that the British loan is a unique case that will establish no precedents for further credits to other nations. It is exceptional in its importance to our aim. But if the United States expects to make its economic program the dominant one for world trade, it must continue to exercise the creditor function without which that program cannot persist.

The most that we should ask is that future loan transactions be scrutinized as was this one to see that they offer comparable security and comparable return in support of the program for which we stand.

For the loan to Britain, it can be said that never before has one nation had an opportunity to gain so much at so little risk as has the United States in this uniquely decisive case.



President, McGraw-Hill Publishing Co., Inc.

THIS IS THE 46TH OF A SERIES

CROSS TALK

►**LORAN . . .** Arrival in New York Harbor of MS Gripsholm, the well-known Swedish-American luxury liner, with the first commercial installation of loran brightens the hope that this and other wartime developments will soon find their way into peacetime applications. As our readers know, loran is an electronic—and elegant—method of finding one's location on the face of the earth by determining accurately the time required for signals to reach the particular spot from two or more sets of transmitters whose position is accurately known.

This new aid to navigation does not measure the direction of arrival of the signals as do ordinary direction-finding systems. Like radar it does its important job by measuring the small but finite time nature requires for transmitting radio energy through space.

Without doubt passenger ships will carry loran and radar. The latter enables the ship master to see where he is in the dark or in fog, particularly with respect to nearby objects. The combination of loran for long-range and radar for short-range position-finding should prove to be marvelous steps toward complete safety at sea.

Whether cargo vessels will carry loran or radar may turn out to be another story. Insurance rates on ships at sea take into account aids to safety, and if there are no other charges than the purchase and ordinary maintenance of the equipment, the decreased insurance will pay for the new equipment. On the other hand, if an operator is required, then the additional navigation aids represented by loran or radar will add considerable overhead to the cost of running the ship.

In a highly competitive business like cargo shipping, fixed charges must be kept low. Wide adoption of radar or loran by cargo vessels—unless ordered by government—will hinge on the matter of whether extra operating personnel will be required. If the equipment can be operated by deck officers, or by an existing radio operator, and if no additional help is needed, then these new aids to navigation will find their place in ships at sea as they have in ships of the sky.

►**RESEARCH . . .** Recently a very large American manufacturer found that 10,000 stockholders expressed interest in company research while only 95 wanted to know more about company finances. Such a circumstance can only be a result of the war.

This is all to the good. Only by continuing research can standards of living in peace and success in war be sure. The disturbing factor, however, is the constant stream of researchers who pass through this editorial office who say "my company is cutting down on research—where can I find a job?"

What's the matter with the electronics industry? Is it losing its nerve?

►**FIRE . . .** So far the horizon shows no electronic device, except radio, which can be sold to the average American home. All such gimmicks proposed to date are either too expensive, are not necessary or are just plain silly.

The Christmastime Hartford fire in which aged inmates of a hospital lost their lives, the daily radio and newspaper reports of disastrous fires in which lives and farmer's stock are lost, indicate that some device, electronic or not, which would accurately and cheaply and surely give an alarm within one's own precincts of the approach of fire could be sold in untold millions to American home owners.

►**CROSSROADS . . .** At the request of the Navy Department, Donald G. Fink, Executive Editor of ELECTRONICS, has been granted a leave of absence for the period of the atom bomb tests in the Pacific to be associated with Captain Christian L. Engelman, Electronics Coordinating Officer of the project. Mr. Fink will leave some time around the first of April for Bikini Atoll, returning to his desk early in the Fall.

RADAR ECHOES

Dr. Harold D. Webb (right) adjusts the auxiliary tuning crystal in the lunar receiver while E. K. Stodola looks on. Behind Stodola is the nine-inch type-A indicator which records the echoes

Lt. Colonel John H. DeWitt, Jr., in charge of the project, at the power supply controls of the transmitter, a modified version of the SCR-271 early-warning radar used at Pearl Harbor. DeWitt is former chief engineer of WSM

The author, Jack Mofenson, adjusts the position of the waveform-monitoring stub. Over this transmission line traveled the 3-kw transmitted pulse and the millionth of a billionth of a watt echo



THE RECENT EXPERIMENTS performed by the Signal Corps Engineering Laboratories in receiving radar echoes from the moon have aroused much comment from engineers, astronomers and others engaged in technical pursuits. Although the scientific aspects of sending radio-frequency signals through the ionosphere are certainly of importance, the work done on the project is better classified as an engineering achievement. As yet, no long-term systematic observations have been made. This article is confined, therefore, to a discussion of the technical characteristics and general description of the equipment employed.

Briefly, the experiment consisted of transmitting quarter-second pulses of radio-frequency energy at 111.5 mc every four seconds in the direction of the moon, and detecting echo signals approximately 2.5 seconds after transmission. Display of the detected signals was audible as well as visible. Technically, the experiment utilized well-established radar techniques, but with radically different constants throughout the system. Considerations of pulse width, receiver bandwidth, transmitter power and the precise frequency of the returned signal due to Doppler effect, were such that careful attention had to be given to the design of the overall equipment.

After preliminary calculations were made concerning transmitter power, the reflectivity coefficient of the target, and receiver noise figure, it was apparent that receiving radar echoes from the moon was technically possible. Under the direction of Lt. Col. John H. DeWitt, a project called "project Diana" was set up in September 1945 to develop a radar system capable of transmitting r-f pulses to the moon, and detecting echoes more than 2 seconds later. Prior to entering the Signal Corps, Colonel DeWitt, who at that time was chief engineer of Radio Station WSM in Nashville, Tenn., designed and constructed transmitting and receiving equipment for the purpose of receiving echoes from the moon. This equipment employed substantially similar transmitter power and frequency to that used by the Signal Corps, but the attempt was a failure due to insufficient sensitivity in the receiver. Colonel DeWitt's appreciation of the problem and personal supervision were the driving forces that made the present experiment successful. Assisting Lt. Colonel DeWitt were: E. K. Stodola, Dr. Harold D. Webb, Herbert P. Kauffman and the writer, all of Evans Signal Laboratory. Credit is also due the members of the Antenna and Mechanical Design Group, Research Section, Theoretical Studies Group and others.

The practical implications of radar contact with the moon are numerous. During the war the Germans used the V2 Rocket which climbed some 70 miles above the earth, and the future holds the unhappy prospect of missiles going far higher than this. The matter of transmission of radio signals to great distances above the earth for detection and control of such weapons becomes a problem of military importance. Further, the use of a reflector far beyond the earth for radio waves makes possible direct measurement of the ability of radio waves to penetrate the ionosphere. A more complete investigation in this direction is indicated. The possibility of using the moon as the reflector for a part-time long-distance point-to-point

electronics WAR REPORT

By JACK MOFENSON
Evans Signal Laboratory
Belmar, N. J.

FROM THE MOON

Detailed description of the techniques underlying the first recorded radio transmission through outer space. Calculations show that the maximum range of Signal Corps radar on lunar target exceeds one million miles



FIG. 1—Block diagram showing the essential elements of the system. Transmitter and receiver are controlled by the same crystal, permitting stable tuning of the narrow-band receiver relative to transmitter frequency

communication system is also being considered, as well as using the moon as a target to measure field-strength patterns.

Determination of Requirements

Several of the constants which determine the maximum distance at which a radar set can detect targets are peak transmitter power, radio-frequency of the transmitted signal, duration of the signal, receiver noise figure, and target echoing area. These constants, among others, are concisely summarized in what has been called the free-space radar equation.

$$r = \sqrt[4]{\frac{P_t A_o G_o \sigma}{P_r (4\pi)^2}} \qquad (1)$$

This equation has already been derived in ELECTRONICS[1]. In this equation, r is the radar range at which a signal may be detected, P_t is the transmitter power during the pulse,

Herbert Kaufman adjusts the bias on the high-level multiplying stages of the transmitter. Kaufman and the four others shown were the personnel of "project Diana"

G_s the transmitting antenna power gain, A_s the absorption area of the receiving antenna, σ the effective echoing area of the target, and P_r the power of a barely discernible signal, on the same basis as P_t. The power gain due to ground reflections (not considered in the free-space equation) at maximum effectiveness increases the range of the system by a factor of 2. This is equivalent to a power gain of 12 db.

In the case of a target as large as the moon (2160 miles diameter), calculations showed that in order to receive an echo from the whole hemisphere of the moon at once a pulse width greater than 0.02 seconds was required. This set a lower limit on the transmitter pulse width which corresponds to an optimum bandwidth of 50 cps for the receiver. These requirements eliminate, for the present, the use of the microwave frequencies, because of considerations of pulse length.

Propagation studies indicated that electromagnetic waves at a frequency of 110 mc were capable of penetrating the ionosphere, and because of availability of equipment, a radar set operating at 111.5 mc was chosen for the experiment. The peak power available in this transmitter was equivalent to 3000 watts for P_t using a 0.25-second pulse. The transmitter had the added advantage of being crystal controlled, deriving its final radio frequency after a series of frequency multiplications from a 516.2-kc crystal oscillator. The receiver associated with the transmitter was of the multi-mixer type (quadruple superheterodyne) capable of beating down radio-frequency signals to a final intermediate frequency of 180 cycles per second. Such an arrangement permitted use of an extremely narrow pass band, 57 cps, thus making the receiver highly selective and limiting the noise to a very low value. The extremely narrow-band receiver was an advantage, also, because it permitted tuning the receiver to the exact radio frequency of the returned echo. The importance of this can best be realized by considering the fact that due to the relative velocities of the earth and the moon, the returned signal may differ from the transmitted signal by as much as 300 cycles, due to the Doppler frequency shift. In using a highly selective receiver whose final mixer is tuned to receive the precalculated frequency of an echo return from the moon, the receiver rejects any signal returned at any other frequency.

To reduce the noise contribution of the receiver, a high-gain, low-noise-figure pre-amplifier was connected between the antenna and the receiver proper. The minimum perceptible received power was P_r readily calculated from the formula for noise figure.

$$\overline{NF} = \frac{E^2/4R}{KTB} \qquad (2)$$

In this formula $E^2/4R$ is the maximum available signal power at the receiver input terminals in watts, where E is the signal voltage at the antenna terminals, and R is the effective impedance in ohms. KTB is the maximum available noise power at the receiver input, where K is Boltzman's constant, 1.37×10^{-23} joules per degree Kelvin, T is the temperature in degrees Kelvin, chosen at 300 degrees, and B is the noise bandwidth of the receiver in cycles per second. For this receiver B is 57. For a one-to-one ratio Eq. 3 gives signal-power to noise-power of

$$P_r = \frac{E^2}{4R} = \overline{NF}\,KTB \qquad (3)$$

1.48×10^{-18} watts, taking the effective noise figure of the receiver as 7 db.

The best antenna available at this frequency was a 32-dipole array utilized by the SCR-271 early-warning radar. Two of these arrays were secured side by side and mounted on a 100-foot tower. Calculations show that the array had a power gain of 152 times that of a single halfwave dipole antenna. Since the effective gain of a single dipole is 1.64 times that of an isotropic radiator, the value of G_s is given as 1.64×152 or 250.

The absorption area A_s of the re-



FIG. 2—Block diagram of the transmitter proper. This arrangement is a part of equipment designed for another purpose by E. H. Armstrong, adapted by the Signal Corps for the lunar studies

ceiving antenna is calculated from

$$A_e = \frac{G_e \lambda^2}{4\pi} \qquad (4)$$

Substituting the value of G_e previously given, $A_e = 522.1 \times 10^{-7}$ square miles.

The remaining constant to be determined before solving Eq. 1 is σ the effective echoing area of the target. Calculations of the reflectivity coefficient made by Walter McAfee of the Theoretical Studies Group, assuming zero conductivity and a dielectric constant of six for the moon, resulted in the figure 0.1766. The effective echoing area is this figure multiplied by the projected area of the moon, $\pi d^2/4$ where d is the lunar diameter. This gave an effective echoing area of 0.1766 (2160)^2 (3.1416)/4 or 647,000 square miles.

Substitution of these values in the free-space radar equation gave a maximum range of 573,500 miles and indicated that the effective range of the equipment chosen was more than twice that needed to receive echoes from the moon. By adding the power gain due to ground reflection, a further excess of power of 12 db or a range of 1,140,000 miles was indicated, which meant that according to calculations, the received signal should be about 20 db above thermal noise. This calculation of the signal strength of the returned echo checked closely with observations, and indicated that no appreciable attenuation occurs in free space.



FIG. 3—The radiator consists of two standard SCR-271 "mattresses" mounted side by side, 64 dipoles in all. This 40-foot-square array is supported on a 100-foot tower, can look at the moon only at moonrise and moonset

Transmitter

Once the determination of constants was completed, the choice of available radar sets was made. Since no attempt was made to design major components specifically for this experiment, the selection of receiver and transmitter was made from equipment on hand. A crystal-controlled radar transmitter and receiver designed by Major E. H. Armstrong for another purpose were selected since they met the requirements of power and bandwidth. A block diagram of the complete transmitting, receiving and indicating system is shown in Fig. 1.

The transmitter is crystal controlled, deriving its final radio frequency of 111.5 mc after a series of frequency multiplications from a fundamental crystal oscillator frequency of 516.2 kc. Keying is accomplished by causing a low-level multiplier stage to conduct by driving its cathode negative for the duration of the transmitted pulse. In the initial setup, keying was performed mechanically by a relay, but this has since been replaced by an electronic keyer with the pulse width controllable between 0.02 to 0.2 seconds. A block diagram of the transmitter is shown in Fig. 2.

From the diagram it is apparent that the transmitter is of a conventional type. The output is fed over a 250-ohm open-wire transmission line to the antenna array. The antenna contains 64 dipoles horizontally polarized. The effective power gain of the array is 250, or 24 db.

The antenna, shown in Fig. 3, is mounted on a steel tower 100 feet high and is controllable in azimuth only. No provision has been made to incline the antenna in elevation. Because of this restriction, the times of observation using the present equipment were necessarily limited to moonrise and moonset. That this condition of observation is the worst possible (due to the long path through the atmosphere and the consequent possibility of trapped radiation) has been recognized. But it was impractical to procure an array of the equatorial type. Aside from propagation deficiencies, a far more serious limitation was the fact that observations were limited to two short periods daily.

The beam width of the array is approximately 15 deg at the half-power points, with the first three lobes spaced approximately 3 deg in elevation. Since the diameter of the moon subtends roughly one half degree of arc, most of the power transmitted does not illuminate the target, which constitutes a serious waste of power. The rate of rise of the moon along its ecliptic is 1 degree of arc every



FIG. 4—Block diagram of receiver, a quadruple superheterodyne. Four mixers, controlled from transmitter crystal, keep receiver in tune, beat signal down to 180-cps i-f frequency. Visual as well as aural indications are provided

4 minutes, which allowed roughly 40 minutes of observation as the moon intercepted the first three lobes of the antenna. Bending effects due to long transmission path through the ionosphere undoubtedly exist, but no precise measurement of this effect has yet been made.

Receiving System

The receiving system is sufficiently different from conventional design to warrant a more complete description. A block diagram is shown in Fig. 4. The entire receiver is frequency controlled, and contains four mixer stages which heterodyne the radio-frequency signal to a final intermediate frequency of 180 cps. Since the first three injection frequency voltages as well as the final radio frequency are derived from multiples of a common crystal oscillator, a high degree of frequency stability is achieved in the system. This high degree of stability is essential to permit tuning the highly selective receiver to the frequency of the echo signal. This tuning is accomplished in the final heterodyne stage.

In tuning it is necessary to take account of the change in frequency of the returned signal which results from variations in the relative velocity of the moon with respect to the earth. The frequency of the returning echo may differ from the transmitted frequency by as much as 300 cycles per second, since the relative velocities of the earth and moon vary from about +900 mph at moonrise to −900 mph at moonset. At the frequency of the transmitter, a relative velocity of 3 miles per hour between antenna and target causes a shift of approximately 1 cycle per second in the received signal. This frequency shift, due to relative velocities of the transmitting antenna and target, is present in all radar echoes from moving targets, but is undetected in conventional receivers because the bandwidth of the normal receiver is many times greater than the frequency shift. In the Diana receiver, a bandwidth of 57 cps is achieved in the final i-f stages. It is therefore necessary to predetermine the Doppler frequency shift for the particular observation being made, and to select the proper crystal for the final heterodyne mixer. To achieve the high degree of accuracy required in the final mixer, provision is made to modify the frequency of the crystal-controlled oscillator by means of a screwdriver control which varies the air gap above the crystal. Final adjustment of the oscillator is made by beating the crystal oscillator output against a secondary frequency standard source, and observing the output on a monitoring oscilloscope.

The output of the final heterodyne mixer is fed into two channels, one audio, the other video. The audio channel is simply a power amplifier stage with the output connected to a loud speaker. The video output channel is fed into a second detector to recover the envelope of the 180 cps intermediate-frequency signal, and then is amplified by a high-gain video amplifier and connected directly to the vertical deflecting plates of a nine-inch cathode-ray tube. The horizontal deflection is a linear 4-second type-A sweep. The visible output is the characteristic low-frequency noise pattern representing a 57-cycle bandwidth centered at 180 cycles. A sudden upward departure from the base line occurs when an echo signal is received from the moon. This is shown clearly in Fig. 5. The audible signal is random noise of 57-cycle bandwidth, superimposed on a fixed-frequency note, at the intermediate frequency of 180 cycles, when the echo is received.

As stated previously, tuning of the receiver is accomplished in the final mixer. The injection signal frequency must be calculated for each observation to take into account the

relative velocity of target and antenna due to both the rotational velocity of the earth and the orbital velocity of the moon. These data, together with azimuth angle and time, are calculated daily from information given by the Nautical Almanac and Ephemeris. The detection of the frequency due to Doppler shift is made with a high degree of accuracy by the selective receiver. This in itself is corroboration that the echo signal is from the moon. Also, the echo interval of 2.4 seconds admits of no other explanation.



FIG. 5—Most widely published cathode-ray trace in history, this type-A presentation shows amplitude of moon echo about three times peak noise. Taken at moonrise, January 22, 1946. The relative velocity of moon and earth was 682 miles per hour, requiring a 227-cps shift in tuning to allow for Doppler effect. Signal-to-noise ratios as high as 20 db have been recorded

The pre-amplifier of the receiver consists of a three-stage tuned r-f amplifier employing two grounded-grid stages (6J4) followed by a 6SH7 tuned amplifier at the transmitter frequency. The overall gain of the pre-amplifier alone is 30 db with an overall noise figure of 3.5 db and a bandwidth of 1 mc. The electrical design of the first two stages was suggested by a development of Dr. F. B. Llewellyn. A simplified schematic of the first two stages is shown in Fig. 6. The use of concentric tubing inductances for the tuned circuits provides automatic r-f filtering on the direct-current and filament leads. The pre-amplifier was designed originally as an improvement kit for the SCR-271 radar, and like the transmitter and receiver, was chosen for the Diana experiment because it satisfied one of the requirements, that of a very low noise figure receiver. A tuned impedance-matching transformer is used between the receiver and transmission line to convert the 250-ohm balanced input to the 50-ohm unbalanced input of the pre-amplifier.

The transmit-receive switching system (t/r box) employed in the original experiment was a set of two



FIG. 6—Secret of success was low-noise pre-amplifier, a grounded-grid circuit based on a design by F. B. Llewellyn. Coaxial leads inside coils exclude r-f from d-c circuits

mechanically-operated shorting bars on the transmission line, operating from a multivibrator-controlled relay during the transmitted pulse interval of 0.25 sec. One of the shorting bars serves to short out the receiver input during transmission, and the other shorts out the transmitter during reception.

Keyer and Indicator

The visual indicator used is a nine-inch electrostatic cathode-ray tube, 9EP7, with a long-persistence screen. The electron beam is caused to scan the width of the tube, synchronously with the transmitted pulse, in 4 seconds, forming a linear time base. The persistence of the tube is long enough to retain the pattern for at least two sweeps. The circuit employed to generate this sweep is a direct-coupled transitron sawtooth oscillator, described below. A pulse equivalent in time to the keying pulse is also generated by this circuit and is applied to the cathode of a low-level multiplier stage of the transmitter, causing it to conduct for the pulse duration and to drive the subsequent multipliers.

The time-base generator consists essentially of a high-gain pentode amplifier with capacitance coupling between plate and grid. The schematic is shown in Fig. 7. The capacitance coupled path includes a cathode follower stage, the left hand section of V_2. For the duration of the conduction cycle, the anode voltage of the pentode V_1 drops and capacitor C_1 begins to discharge through the tube. As the voltage on the plate drops the current flow in C_1 drives the grid negative, tending to cut off the plate current. A condition of dynamic equilibrium then exists with the plate voltage dropping at a linear rate determined by R_1 and C_1 and the grid being maintained at a constant voltage, since each decrement in plate voltage causes a corresponding drop on the grid which keeps the grid signal and hence the output of the tube substantially constant. The time constant of R_1 C_1 is chosen to cause C_1 to become fully discharged during the cycle.

When the plate voltage drops to the point where electrons from the cathode can no longer flow to it, an increase in screen current occurs which rapidly decreases the screen



FIG. 7—Linear deflection circuit of type-A indicator, which sweeps spot across screen in up to ten seconds. Basic circuit is transitron oscillator. Sweep and keyer are controlled by the cathode-coupled flip-flop circuit at bottom of diagram

voltage and correspondingly decreases the suppressor voltage. This action, which is cumulative, has the effect of suddenly cutting off the anode current. This causes the cathode current to be retarded by the suppressor grid and made to flow to the screen. A negative pulse appears at the screen, and C_1 begins to charge through the cathode follower until a point is reached where the plate begins to draw current and the oscillator is recycled. The screen returns to its original voltage, and the plate voltage begins to fall. By suitable choice of R_1 and C_1 a range of from about 0.1 to 3 cps is obtained.

Keying-voltage signals are derived from the differentiated output of the negative pulse appearing on the screen of the oscillator. This is used to trigger a multivibrator whose time constant is controllable by a variable 5 meg resistor, varying the output pulse width from 0.02 to 0.25 seconds.

The addition of the cathode follower stage V_2 was made to shorten the charge time of C_1 by causing it to charge through the grid cathode space of the cathode follower. This reduces the return trace time. Tube V_3 serves as a degenerative phase-inverting amplifier to secure push-pull sweep voltage.

The keyer multivibrator is a conventional cathode-coupled flip-flop circuit with the initiating trigger applied as a positive pulse on the grid of the normally non-conducting section. A positive pulse varying in width from 0.02 to 0.25 seconds is obtained at the plate of the other section. This signal is applied to a normally cut off pentode whose load impedance is the cathode of the 12.388 mc amplifier stage in the transmitter. For the duration of this applied signal, the plate of the amplifier is driven negative, taking the cathode of the keying tube down with it, thus causing it to conduct.

The first echoes from the moon were received at moonrise on January 10, 1946. The indication was of the audible type in the form of a 180-cycle beat note occurring 2.5 seconds after transmission.

Although numerous observations have been made, both at moonrise and moonset, echo returns do not occur after every transmission. Further measurements are needed before precise scientific conclusions can be drawn.

Reference

(1) The Radar Equation, Electronics, p. 92, April 1945.



USS R-4 submarine, with arrow pointing to JP hydrophone installed topside (U. S. Navy photo)

SONAR FOR SUBMARINES

Technical details of sonar equipment used on submarines for underwater listening, including description of supersonic converter circuit, construction of highly directive line-type magnetostriction hydrophone, and analysis of transmission characteristics of sea water

By R. S. LANIER
New York, N. Y.
and
C. R. SAWYER
Western Electric Co., New York; formerly Columbia University, Division of War Research

WITH the declassification by the Navy of JP sonar equipment, it is possible for the first time to describe a complete underwater sound system, including the advanced form of magnetostriction hydrophone that became the standard transducer in submarine listening devices. The JP sonar was developed in cooperation with the Navy by Columbia University, Division of War Research, under NDRC Section 6 at the U. S. Navy Underwater Sound Laboratory at New London, Connecticut.

The success of underwater sound devices became increasingly important to the American war effort with the launching of the German submarine campaign against our coastal shipping in 1942. While playing an important role in the defeat of the U boat, American sonic gear also performed outstandingly against the Japanese. The JP sonar carried a large share of the burden of underwater listening during the war, and constituted a major advance in the development of American underwater sound gear.

Much of the developmental work in the field of underwater sound went into sonic ranging devices which project a signal into the water and obtain information of various kinds from the echo. Such ranging devices are of fundamental importance, but a listening device has a complementary importance and a number of advantages as a warning instrument. It gives warning of the presence of a surface vessel at greater ranges than from an echo ranging device, which suffers from the doubled distance the signal must travel and the far from efficient reflection by the target.

The operator of a listening device gets information about the outside world by identification of sounds which is lacking when echo ranging is employed. Furthermore, the tactical and psychological advantages of actually being able to hear the enemy were found early in the war to be of great importance to the commander of a submerged submarine.

electronics WAR REPORT

Underwater Listening Problems

The most important sound produced in the water by a moving vessel, either on the surface or submerged, is usually the result of cavitation at the propeller. The resulting underwater sound wave is highly complex and has frequency components throughout the sonic and into the supersonic spectrum. The acoustic pressure produced in the water at 1,000 yards by the propeller of a typical ship moving at medium speed is plotted in Fig. 1 for frequencies between 100 and 10,000 cycles.

Other noises produced in the water by a vessel include the vibration of the engines or other machinery and impact-type noises such as the banging of chains or other gear. Speed-reducing gears and pumps are especially noisy. Some types of bearings may have a periodic squeak, and the hull of the ship may cause cavitation

in the water at high speeds. These types of noises will in general be carried through the water as waves of complex frequency distribution, with both sonic and supersonic components.

Although exact analysis of the transmission characteristics of sea water is difficult, there are two main effects that influence the range of a sound in sea water. The first is the expected inverse-square-law reduction in energy caused by the spreading of the wave; the other is an absorption effect due to the mechanical resistance of the water. The latter effect, for signals below about 5 kc, adds approximately 2 db of attenuation per 1,000 yards to that due to spreading. Above 5 kc, the attenuation from absorption increases rapidly. At 100 kc, the absorption amounts to approximately 20 db per 1,000 yards. This transmission characteristic makes it certain that at relatively long ranges an underwater sound will consist predominantly of low-frequency energy.

Ambient water noise is a never-absent factor that vitally affects the range and effectiveness of underwater listening devices. The noise level varies with different states of sea agitation and with other factors, but under most representative conditions has an energy distribution that falls off rapidly in the higher frequencies. The falling characteristic of the noise with frequency usually gives high signal frequencies a better signal-to-noise ratio at close ranges, but at long ranges the attenuation of the signal at high frequencies tends to cancel this advantage. The frequency at which the signal first becomes recognizable when closing range may be anywhere in the spectrum, but is most often in the 500 to 2,000-cps range.

Equipment Requirements

It will be seen from the above that a searching device must be capable of responding to signal frequencies anywhere in the sonic and well into the supersonic range. Rugged electromechanical transducers for such a range are essential. The transducers must operate under water, at static pressures as high as 250 lb per square inch, and in addition are subject to dynamic pressures arising from depth charges and the motion of the submarine through the water. The problem of matching the transducer impedance to that of the water is of an unfamiliar order of dimensions, as the mechanical impedance of water is many times that of air.

Additional design factors arise from the combination of the listening and tracking functions with searching in the JP sonar. For the listening function it is desirable that the operator be able to hear the signal through a system having controllable characteristics over the audible band. If the aural character of the signal is emphasized by filtering, experienced operators can identify different types of vessels by their sound. Many operators became so experienced in the interpretation of sonic signals that they could in some cases tell whether a ship was loaded or unloaded, when it made a sharp turn in the water, etc.

For the tracking function, the system should, of course, be as directive in its response as possible.



FIG. 1—Acoustic pressure in water due to propeller of freighter 1,000 yards away



FIG. 2—Drawing of JP sonar listening equipment



FIG. 3—Cross-section view of line-type magnetostriction hydrophone



FIG. 4—Magnetostriction hydrophone, disassembled at left and assembled at right for topside mounting on a submarine

The JP equipments met the above requirements through the development of the line type of magnetostriction hydrophone and specialized electronic equipment to function with it. The complete equipment, shown in block form in Fig. 2, consists of the hydrophone mounted at the top of a training shaft which extends through the topside of the submarine, the training gear for revolving the hydrophone and indicating its tracking position to the operator, the listening amplifier for raising the signal level and bringing it under the operator's control, and the supersonic converter for heterodyning signals in the supersonic spectrum down to audibility.

To search or track in the sonic range, or to listen directly to a signal for the aural character, the hydrophone is fed directly into the listening amplifier, with the supersonic converter cut out of the system. When searching for supersonic signals or tracking on the higher components of any signal, the converter is cut into the system between the hydrophone and the listening amplifier.



FIG. 5—Frequency response of hydrophone



FIG. 6—Circuit for remagnetizing nickel tube of magnetostriction hydrophone



FIG. 7—Directivity pattern of hydrophone at three different frequencies

Earlier types of hydrophones were of piston construction, using a multiplicity of magnetized nickel tubes placed parallel to each other and fastened perpendicularly to a diaphragm in contact with the water. This performs well in certain applications, but when greatly increased directivity is demanded of the system, the physical dimensions of the piston hydrophone make it unwieldy. Interference between successive wave fronts at close bearing angles, which is the basis of the directivity of a typical underwater sound transducer, cannot be achieved in the sonic range with a circular diaphragm of practical dimensions.

Magnetostriction Hydrophone Design

The line type of hydrophone overcame this difficulty by using a single magnetized element, a nickel tube 3 feet long and 2 inches in diameter. The tube itself acts as a diaphragm to receive energy from the water. The coil is wound on a soft wood and silicon steel core and is entirely enclosed in the tube, as shown in the cross-sectional view of Fig. 3. In back of the tube and supporting it in the horizontal position is the baffle, a bronze casting of streamlined cross-section which is covered with a rubber blanket to absorb sound reaching the hydrophone from the rear. The hydrophone tube, the baffle, the rubber blanket, and various fittings disassembled are shown in Fig. 4 along with the complete assembly as mounted at the top of the training shaft.

Hydrophone Characteristics

The nickel tube is magnetized before use and the instrument operates on the residual magnetism. Deformation of the tube by acoustic energy in the water produces a corresponding variation in the magnetic field, which is carried through the coil by the transverse steel core.

Figure 5 shows the sensitivity and frequency response of the JP hydrophone, in decibels below one volt at the open-circuit terminals, with a constant acoustic pressure of one dyne per square centimeter. The rising character of the response between 100 and 10,000 cycles is desirable to equalize the reverse characteristic of underwater signals at long ranges. The response in the supersonic range is necessary to make the system completely flexible as a tracking and searching device.

The residual magnetism in the tube gradually falls off in use, and may be materially reduced by the shock of depth-charge explosions or other underwater disturbances. The remagnetizing circuit shown in Fig. 6 is therefore provided in the amplifier for remagnetizing the tube. The 500-microfarad capacitor is maintained in a charged condition across the 110-volt d-c power line, and a pushbutton switch allows the capacitor to be discharged through the hydrophone coil.

The directivity pattern of the JP hydrophone is shown in Fig. 7 for single frequencies of 1, 5 and 10 kc. At 1 kc, with a wavelength of nearly five feet, there is no useful directive effect, while at 10 kc the response falls off nearly to zero at about 5 degrees either side of zero bearing. The first secondary lobe in the pattern is about 13 db below the zero-bearing



FIG. 8—Block diagram of JP sonic listening gear



FIG. 9—Circuit diagram of a-f amplifier for models JP-2 and JP-3 sonar equipment



FIG. 10—Response of a-f amplifier at the five filter-switch settings

response. As the signal frequency rises into the supersonic spectrum the directive pattern shows even sharper peaks, which indicates the reason for the emphasis on the high frequencies in the tracking function.

Actual listening employs a band of frequencies which minimizes the prominence of the secondary lobes of the directivity pattern.

The line hydrophone has a solid directive pattern of the pancake type, as opposed to the bowling-pin pattern of the piston hydrophone. The difference can be visualized by revolving the 10-kc pattern of Fig. 7 first around the horizontal reference line as an axis to form the pancake pattern, and then around the vertical center-line to form the bowling-pin pattern. The pancake pattern is considered superior for searching purposes because it gives equal response to signals in a plane normal to the hydrophone axis, no matter what the vertical angle of elevation. This ignores the effect of the baffle, which reduces the response from the rear and thus allows the operator to place the signal in the forward arc of the pancake pattern.

Amplifier Circuit

The hydrophone output is brought down through the training shaft to the listening amplifier. A block diagram of the amplifier is shown in Fig. 8 and the complete schematic in Fig. 9. It is in the main a resistance-coupled five-stage arrangement of conventional design, using pentodes throughout. Two separate feedback loops are used to stabilize gain and reduce noise, one over the first two stages and one over the last two.

The electrical sensitivity of the system, measured from the output of the hydrophone, is approximately 10^{-8} volt. With a hydrophone of the JP type and overall amplifier sensitivity of the order of 0.01 microvolt, the system has a sensitivity margin of about 20 db over that required to raise the water noise to audibility under average conditions. Further increases in sensitivity have not been found of value in listening systems of the JP type, as the water noise is at present the limiting factor on the range of the system.

Testing of large groups of operators has shown that for a signal to be recognized through the noise, the signal level must be about equal to the noise level over a band of frequencies somewhere in the audible spectrum. The width of such a band which will just make the signal discernible, known as the critical bandwidth, varies somewhat with the position of the band in the spectrum. With strongly periodic signals, experienced operators can sometimes pick out a signal as much as 10 db below the noise level.

To reduce the noise level and make the system most effective at the point in the spectrum where the signal-to-noise ratio happens to be most favorable, the amplifier incorporates a variable equalizer between the second and third stages. The characteristic response for each of the five filter positions is shown in Fig. 10. The bass-boost or No. 1 position aids in identifying noises with a predominant low-frequency character, such as banging chains, machinery vibration, etc, and is useful at long ranges. The unequalized position is No. 2, and No. 3, 4 and 5 cut in high-pass filters with progressively higher cut-off points. The latter positions are most useful at relatively close ranges, when the falling characteristic of the noise with frequency can be used to advantage.

Limiting the response to the 3,000 or 6,000-cycle-and-up range will often eliminate the major part of the noise energy, which lies in the lower fre-

quencies, and will permit the operator to pick out signals that would otherwise be completely masked. Naturally, reducing the bandwidth also reduces the noise level by some factor independent of differential frequency effects.

Normal listening was with high-quality headphones so sounds would be as near the original as possible.

The indicator channel, with an amplifier stage and a high-pass filter cutting off at 5,500 cycles, is used to give the operator a sharp visual indication of zero bearing on the target. Restriction of the response of the tuning eye tube to signals above 5,500 cycles is necessary to obtain a sharply directional response.

The output stage includes a diode which can be thrown in with a switch to shunt the grid circuit, with the plate of the diode connected directly to the grid and the cathode of the diode connected to ground. The resulting clipping action on positive signal peaks provides a strong band of harmonics which will often make a periodic signal stand out clearly from the noise. This simple distortion-supplying device is most often used to get a clear count on the propeller beat of another vessel, hence the name turn-count detector.

Supersonic Converter

The supersonic converter is shown in block form in Fig. 11 and the complete schematic in Fig. 12. It contains five 6SJ7 pentodes, one as an amplifier and two each as oscillators and mixers. The first conversion uses a local oscillator frequency tunable over the range of 102 to 154 kc, so that any signal in the 8 to 65 kc input range of the instrument will produce a difference frequency between 89 and 94 kc. The second local oscillator is tuned to 94 kc, so that the final difference frequency will be in the audible band below 5 kc. The various filters restrict the response of the system to the desired range.

The oscillator voltages from the electron-coupled oscillators are injected at the suppressor grids of the mixers. A three-step volume control at the grid of the first mixer provides a long, short, and medium range, with 20 db of attenuation between each step. The audio output of the converter is — 4 db over the range of 500 to 5,000 cycles. The converter gives the system as a whole 18 db more gain at supersonic frequencies than the listening amplifier alone has at 1,000 cycles.

With the hydrophone output fed into the supersonic converter and the converter output connected into the listening amplifier at the grid of the third stage, the operator can search for signals in the supersonic range, or use the higher components of any signal for greater tracking accuracy. Switching is provided so that the converter can be instantly connected into the listening system. An operator experienced in the use of the converter can determine the bearing of a signal, under favorable conditions, with an accuracy of better than 1.5 degrees.

The flexibility of the JP sonar and its ability to bring the actual sound of the signal into the submarine, together with its range and high accuracy of tracking, made it a major contribution to the success of American submarines during the war.

Important contributions to the success of the JP sonic apparatus were made by H. C. Williams, J. W. Horton, T. E. Shea, F. P. Herrnfeld, W. B. Snow, D. P. Loye, R. Chapman, R. H. Griffin, M. T. Rodger, and the late A. L. Thuras.



FIG. 11—Block diagram of supersonic converter used to heterodyne supersonic signals in the range from 8 to 65 kc down to the audible band below 5,000 cycles

FIG. 12 (below)—Circuit diagram of supersonic converter



Printed

By CLEDO BRUNETTI
Principal Physicist
National Bureau of Standards
Washington, D. C.

and

A. S. KHOURI
Engineer
Centralab Division, Globe Union Inc.
Milwaukee, Wisconsin



FIG. 1—Comparison of tiniest mortar VT fuze with standard 6L6G radio tube, and cross-section of fuze. Arrow points to printed ceramic electronic control circuit

THE development of the tiny generator-powered radio proximity fuze for the U. S. Army's mortar shells resulted in several new processes and techniques which promise to do much in reducing size and improving efficiency of many types of electronic devices. Outstanding among these is perfection of a method of printing wiring and certain components on a ceramic surface.

The diminutive size of the mortar fuze may be realized from Fig. 1, in which it is shown alongside a 6L6G radio tube. The cross-section view shows a portion of an electronic control circuit constructed according to the new principle. Completely self-contained with radio transmitter-receiver, control circuits, safety devices and a turbo-generator power supply, the fuze was designed to withstand a set-back force of 10,000 times that of gravity. The limited space requirements for the control circuit, coupled with the necessity of rugged-

FIG. 2—Top and bottom views of two-stage amplifier constructed according to present practice and (below) by new printed ceramic technique developed for use with subminiature tubes



Electronic Circuits

First details of new technique for printing wiring directly on a steatite chassis block with silver solution by a silk screen process, then spraying on resistors through masks. This method makes possible the mass production of ultracompact amplifiers and radio sets

ness in design, led to the adoption of the printed ceramic method.

With the resumption of peacetime activity, the new circuit wiring process promises to have wide use in such applications as pocket radios, personal telephones, miniature hearing aids, meteorological instruments, and miscellaneous electronic control circuits. A typical example of its use is seen in Fig. 2, in which a two-stage audio amplifier constructed on this principle is compared with one made according to present table-model radio practice.

Essentially the process consists of the following four techniques: (1) Printing or stencilling the circuit wiring (using silver paint) onto a suitable chassis or base material, such as a plate of steatite; (2) Spraying the resistors in the form of a carbon and resin mixture, onto the plate through positioning masks that locate them between appropriate silvered end tabs; (3) Attaching small disc-type capacitors, consisting of a high-dielectric-constant ceramic with both faces silvered, directly to the silvered wiring on the plate; (4) Soldering other components such as tubes into appropriately located and silvered holes in the ceramic. Used with the newly developed subminiature tubes, the electronic circuit assembly made possible by this process is extremely compact.

Figure 3 shows the circuit and the



FIG. 3—Circuit and response characteristics of two-stage audio amplifier used as example illustrating the advantages of the printed ceramic technique





Silk screen (above) mounted ready for use, and jig (right) for holding screen and steatite plate during printing. Design has just been printed on the plate by forcing silver solution through the screen with a neoprene bar, and the printed plate has been lowered out of contact with the screen

gain-frequency characteristic for the printed amplifier of Fig. 2. The response is identical to that of ordinary circuits. This is to be expected, as basically the components of this circuit are resistors, capacitors, and tubes just as in the standard circuits.

Although an audio circuit is described, the method is adaptable to high as well as low frequencies. In fact, the reduced size of the components and assembly allows very efficient ultrahigh-frequency circuits to be constructed in a limited amount of space. At very high and ultrahigh-frequencies small circular or rectangular spiraled coils may be printed flat on the ceramic surface in the same fashion as the wiring leads, using silver paint. It is possible to obtain Q values of 150 to 200 and even higher if desired.

The method is adaptable also to attenuators, filters, corrective networks and, in general, any low-power electric circuit. In circuits requiring the use of tubes, subminiature tubes now on the market are ideal. These inch-size tubes, which played a principal part in the development of proximity fuzes, are not only small but rugged and efficient. Filament drain is exceedingly low. Typical characteristics of Raytheon subminiature tubes as used in printed electronic circuits are shown in Table I.

Soldering of subminiature tube leads to a printed ceramic chassis. Ceramic capacitor discs in foreground are also soldered to the steatite

Although the compactness of the method was the most important factor in its application to the VT fuse, other equally important and desirable characteristics are the uniformity of finished assemblies both in appearance and performance, high production speed, and ease of circuit checking. Uniformity is obtained since each circuit is an exact reproduction of the master pattern. High production speed is obtained by the screening and spraying operations, which combine in a few fast mechanical operations the former operations of cutting wires to length and soldering wires and resistors into place.

Because of its two-dimensional nature and the open method of construction, circuits constructed by this new process lend themselves to rapid circuit tracing and repair. Faulty components such as resistors and capacitors which are on the chassis can be repaired, if desired, by soldering a conventional component of equivalent value across each faulty part and opening the circuit leading to the fault.

Details of Construction

Six stages in the evolution of the printed ceramic circuit are portrayed in Fig. 4. The base material most commonly used is steatite, a hard, dense, porcelain-like ceramic material. Like porcelain, steatite is



FIG. 4—Evolution of a printed electronic circuit, showing the amount of powder needed to press one steatite plate, the pressed but unfired plate, the fired plate (showing shrinkage), circuit wiring applied through silk screen and fired on, resistors sprayed on, and the final assembled unit

formed by various methods of extruding, pressing, or casting to a predetermined larger size and then dried and fired at almost white-heat temperatures to shrink and vitrify it to its final form.

Preparatory to fabricating to shape, the carefully selected and ground talc is thoroughly mixed with small percentages of clays, fluxes, and organic binders in large muller mixers. Water is added and the batch is worked to a uniformly plastic condition.

The pieces are pressed to the desired form by either a dry or wet press process. The dry press method, which lends itself to more rapid and automatic pressing, is used whenever possible. However, the more complex pieces are of necessity wet-pressed to obtain satisfactory flow of materials to the various parts of the mold. Material is prepared for pressing by disintegrating a wet batch into small granular particles by use of high-speed hammer mills. For wet pressing it is used in this form and pressed in molds at pressures of one-half to two tons per square inch. For dry pressing, the granulated material is dried and screened for use and pressed in molds at pressures between five and ten tons per sq in.



FIG. 5—Front and back patterns for wiring of printed amplifier

TABLE I. Typical Characteristics of Subminiature Tubes Used in Printed Electronic Circuits

Electrical Characteristics	CK-505AX Pentode Voltage Amplifier Type	CK-503AX Pentode Output Type	2E 31 2E 32 Pentode Shielded R-F Type	2E 41 2E 42 Diode-Pentode	2G 21† 2G 22† Triode-Heptode	CK-509AX Triode Voltage Amplifier Type
Filament voltage in d-c volts	0.625	1.25	1.25	1.25	1.25	0.625
Filament current in ma	30	45	50	30	50	30
Plate voltage in volts	30	45	22.5	22.5	22.5	45
Screen voltage in volts	30	45	22.5	22.5	22.5	—
Control grid voltage* in volts	0	−4.5	0	0	0	0
Peak a-f grid voltage in volts	—	4.5	—	—	—	—
Transconductance in μmhos	175	500	500	400	60 (Gc)	160
Plate resistance in megohms	1	0.12	0.35	0.25	0.5**	0.15
Plate current in ma	0.15	1.25	0.35	0.4	0.2	0.15
Screen current in ma	0.05	0.4	0.3	0.15	0.3	—
Load resistance in megohms	1	0.03	—	—	—	1
Screen resistance in megohms	3	0	—	—	—	—
Power output in milliwatts	—	25	—	—	—	—
Voltage gain	35	—	—	—	—	16
Distortion, percent	—	10	—	—	—	—
Max. grid-plate capacitance in μμf	—	—	0.018	0.10	0.065***	—
Oscillator plate voltage in volts	—	—	—	—	22.5	—
Oscillator plate current in ma	—	—	—	—	1.0	—

*With 5-meg grid res. connected to F. grid to mixer plate capacitance. **Approx. conversion plate res. ***Signal

The pieces thus formed are sprayed or dipped with glass-forming materials on any surface which is to be glazed, and fired through continuous tunnel kilns to temperatures approximating 2400 degrees F. After this treatment they are no longer soft and easily machinable, but have a hardness approaching that of sapphire. In certain instances where more exacting dimensional requirements have to be met than can be held by careful control of the fabrication processes, those dimensions are wet ground to exact size on large carborundum discs or diamond wheels.

Application of Silver Wiring

The leads between components are applied by a process in which the silver is intimately bonded to the ceramic. The silver is in the form of a paint or paste. Very finely divided metallic silver or silver oxide is uniformly dispersed in a suitable vehicle, and the consistency is adjusted with solvents to meet requirements for the specific type of application. The degree of bonding or adherence of the fired silver to the ceramic surface is largely dependent on the surface condition of the ceramic before application of the silver paint or paste. Therefore, the ceramic surface must be free of dust, dirt, grease, or other contaminants.

The method most commonly used for circuit reproduction is a screening process in which the silver paint is dispersed through the open mesh of a silk or metal screen arranged as a mask to define the circuit. This makes it possible to print circuits of any degree of complexity. Complicated designs can be held to very close tolerances. The deposited or printed film thickness is very uniform and little silver paint is wasted.

For best results a genuine Swiss silk is used for the screen. The mesh size of the silk is dependent on the fineness of design desired and the characteristics of the paint vehicle. The silk is stretched tightly on a wooden frame and coated with a material, such as gelatin or polyvinyl alcohol, which is capable of becoming photosensitive when sensitized with potassium dichromate. A photographic positive is held tightly against the sensitized silk screen and

exposed to light. The portions of the sensitized coating exposed to light become insoluble in water. Those portions which are not exposed to light are water soluble and wash out. The parts that wash out form the design of the pattern to be printed. Front and back patterns for the wiring of the amplifier of Fig. 2 are shown in Fig. 5.

The next step is to place the paste on one end of the top surface of the screen. The ceramic to be painted is brought into contact with the opposite or bottom surface of the screen. A neoprene bar is moved across the top surface of the silk, forcing the silver paint ahead and through the open mesh of the screen pattern. The paint forced through the open mesh is deposited on the ceramic plate in a design which conforms identically to that of the screen pattern.

After applying the silver to the ceramic, the parts are placed in a furnace and heated to a temperature between 1300 and 1500 F. This temperature removes the vehicle and solvents, and intimately bonds the silver to the ceramic. Properly fired silver has the dull metallic appearance of typical silver color and will adhere to the ceramic surface with a tensile strength of approximately 3000 pounds per square inch.

Resistoring

The process of resistoring involves the application of an accurately controlled amount of resistance paint to the ceramic surface. The paint consists of a conducting material, a filler or inert material, and a vehicle or binder. By varying the quantities of these ingredients, paints covering a resistance range from 3 ohms to 200 megohms may be obtained. Other desired electrical and physical characteristics, including good adhesion to the ceramic surface, are also obtained by the proper formulation of the three components.

The paint is applied by a spray process. The size and position of the resistors are governed by suitable masks which have good adhesion to the ceramic surface. After air drying, the masks are removed and the paint is cured in an oven at 300° F for several hours to produce stable resistors. A special resin coating is applied to the resistors to protect them against humidity and other effects.



FIG. 6—Effect of temperature on sprayed resistors



FIG. 7—Effect of temperature on ceramic disc capacitors employing titanates as dielectrics

Resistance stability with time, under load or under extreme humidity conditions, is good. When exposed for 100 hours in 95 percent relative humidity at 110 F, the average resistance change was minus 10 percent for values in the range of 5 ohms to 10 megohms. This was not a permanent change, as the original values were obtained on suitable drying.

Ceramic Disc Capacitors

The ceramic disc capacitors are molded from high-dielectric-constant mixtures of titanates. Capacitance is controlled by the mix, the thickness of the disc, and the area of the silvering on the faces. Dielectric constants of 40, 100, 1000, and 2000 are used for capacitors ranging in value from 6.5 to 2000 $\mu\mu$f. These capacitors are from $\frac{1}{8}$ inch to $\frac{3}{8}$ inch in diameter and 20 to 40 mils thick. Higher dielectric constant materials than described have been used, but these are still in the experimental stage.

Soldering to Metallized Ceramic

External leads, such as tube leads or leads from separate resistor or capacitor components, may be soldered to the silver wiring on the plate, providing a solder having about 2 percent silver, to saturate against further absorption of silver, is used. The ceramic disc capacitors are soldered to the plate with a low-temperature bismuth solder. The low-temperature solder minimizes the possibility of fracturing the ceramic during soldering.

Effects of Temperature

Variations in resistance and capacitance values with temperature for several common values of components are shown in Fig. 6 and 7. The performance is comparable to that of standard components. Improvements in techniques to be expected with wide use of the process make probable even superior performance to that obtainable with ordinary type components.

Conclusions

In addition to the advantages delineated above, other features of this method of manufacture are apparent. Amplifier, filter, or other control circuit assemblies may be printed on small ceramic blocks and plugged into a main chassis. Replacements can then be made in the same manner as a tube is now changed. Furthermore, any tampering with a circuit by inexperienced personnel is immediately apparent. Although ordinary resistors or capacitors may be soldered across the printed components, the change is clearly visible.

This article is based on work carried out jointly by the Centralab Division of Globe Union Inc. and the Ordnance Development Division of the National Bureau of Standards under the direction of Harry Diamond. The work was accomplished under development contracts with Division 4, N.D.R.C. under Dr. Alexander Ellett, leading to production contracts by the Army Ordnance Department.

COLOR TELEVISION
On Ultra High Frequencies

Color images broadcast on 490 mc in recent CBS demonstrations show great improvement over 1940 tests. New system uses 10-mc video band to carry 525-line signal, transmits sound by f-m bursts interspersed with the video information

AFTER an interlude of five years occasioned by the war, the Columbia Broadcasting System has resumed development of the color television system last demonstrated to the press in September 1940. Several radical departures have been introduced in the latest version of the system, aimed primarily at improving the detail of the images, and secondarily at improving the color quality. The method of introducing the color to the signal remains the same. A mechanically-driven color wheel, composed of trichromatic filter segments, rotates before the camera and a similar wheel rotates synchronously in front of the picture tube in the receiver. This method of transmission was reported[1, 2] in ELECTRONICS and elsewhere in 1940 and 1942.

The color images in the present system are scanned in 525 lines, interlaced 2-to-1, and the interlaced fields are scanned at a rate of 120 per second. Each field is scanned and reproduced in succession through a different primary color in the filter wheel. The three colors are thus presented to the viewer in 1/40th of a second. The persistence of vision extends for a longer period than this, so the three colors fuse in the mind of the observer and a multicolored reproduction results.

The principal shortcomings of the images in 1940 were low definition, 343 lines compared with 525 lines in the standard black-and-white images, and occasional difficulties in the rendition of certain colors, particularly the dark shades. Both definition and color have been considerably improved in the equipment recently demonstrated to the press. Details of the new equipment were described before the IRE Winter convention



Rear view of the modulator. Video stages occupy second and third racks from top. Remaining racks are power supplies

Front view of transmitter. The large size is required to provide sufficient r-f and video stages to reach 1-kw peak output modulated over 10-mc band



by Messrs. Goldmark, Reeves, Schlesinger, Serrell, and Lyman of the CBS Engineering Staff.

Changes to Improve Definition

To improve the definition of the images, Dr. Goldmark and his staff elected to increase the number of lines to 525, the value now used in black-and-white systems. Since twice as many pictures are transmitted per second in the color system as in the monochrome system, the bandwidth required is twice as great for the same number of lines. The maximum video frequency in the black-and-white system is about 4 mc, so the corresponding figure for color would be 8 mc. The figure adopted for the CBS system is 10 mc, an increase which improves the resolution in the horizontal dimension relative to the standard black-and-white picture.

When 10 mc is adopted as the maximum video frequency, space cannot be found for r-f sidebands in the vhf television band (54 to 216 mc). For this reason, among others, CBS decided to enter the uhf experimental television band (480 to 920 mc). The channel proposed for use, shown in Fig. 1, is similar in form to the vhf standard, i.e. vestigial sideband transmission and reception. The transmitter carrier is set at 485 mc, and the sidebands extend from 480 to 496 mc, or 16 mc overall. The receiver i-f bandpass characteristic attenuates the transmitter carrier by 50 percent and thus restores equal amplitude to all video frequencies at the output of the receiver second detector. All this is identical to present black-and-white practice except that the radio frequencies are roughly



FIG. 1—Proposed uhf channel, employing vestigial sideband transmission over a 16-mc band. Sight and sound signals are transmitted on the same carrier



FIG. 2—Block diagram of the transmitter, showing frequency and power transformations and voltage gains in the modulator. The 6C22 r-f tube is a water-cooled disk-seal type

2 to 10 times higher and the bandwidth is 2 to 3 times wider.

The sideband filter required to remove the lower sideband has not yet been completed by CBS, so double sideband operation was used during the demonstrations. To keep within the band, the carrier was set at 490 mc and the sidebands extended 10 mc either side. The additional sideband energy radiated in the lower sideband, relative to the characteristic in Fig. 1, has no effect on the receiver operation which remains as shown, with the 50 percent level shifted to 490 mc.

To design a transmitter capable of radiating substantial power at this frequency, while being modulated over a 10-mc bandwidth was a task of large magnitude. The transmitter was designed and built by the Federal Telephone and Radio Corp., using as its essential component a water-cooled disk-seal triode, type 6C22. The transmitter meets the specification with a power output of 1 kilowatt peak or 600 watts average. The block diagram is shown in Fig. 2. The r-f chain consists of eight stages, a crystal tritet, two triplers and two doublers with three linear amplifiers, interspersed as shown. The last four stages, including the final grid modulated amplifier use the new tube. The frequency and power transformations of each stage are shown.

The video modulating chain uses five stages, each conductively coupled so that all frequencies from d-c to 10 mc are passed with constant amplitude and time delay. The voltage gains attainable over this band are not large, ranging from 3 to 7 times depending on the tube type used. The video couplings are of the compensated filter type, both four-terminal and two-terminal networks being used. A 2-volt peak to peak input video signal is capable of modulating the final amplifier to its peak output of one kilowatt.

Synchronization monitor for keeping tabs on complex waveforms throughout video system. Thirty-two pushbuttons permit rapid selection of various signals





FIG. 3—Video waveform used in the CBS system. The sound is transmitted by an 8-mc subcarrier radiated during the horizontal retrace time. Color pulses are inserted to synchronize the color wheel

The power output of the transmitter is multiplied 20 times by the radiator. The radiation pattern is highly directional in the vertical plane, produced by a slotted waveguide structure which compresses the radiated signal into a vertical angle of 6 degrees, while delivering a signal of substantially constant magnitude over the 360 degrees of the horizon. To compress the beam to 6 degrees requires a radiator surface about 10 wave-lengths long. Fortunately this is not impractical at 490 mc. The antenna consists of two waveguide panels, each 18.5 feet high and 2 feet wide. These panels are mounted on the north and south faces of the Chrysler Building in New York and the beam is so oriented in elevation that the field strength at ground level is theoretically constant at all points out to the horizon. The horizontal pattern of each antenna panel extends theoretically over 180 degrees. The actual horizontal coverage has not yet been investigated, but it is expected that only a slight loss in gain is experienced in the east and west directions. Each panel has a power gain of 40, the transmitter power being split between the two, resulting in an effective radiated power of 20 kilowatts.

Sight and Sound on Same Carrier

The numerical constants employed in scanning make possible the transmission of the sound signal and the picture signal on the same carrier. Since the 525-line picture is completely scanned (two fields) in 1/60th of a second, the line scanning frequency is 525 × 60 = 31,500 cps. It has been appreciated for some time that the inactive time during the re-



FIG. 4—R-f and video signal components of the receiver. A crystal mixer and six i-f stages (at left of center) are used, and 8-microvolt sensitivity is achieved



Exploded view of the coaxial final amplifier of the transmitter. Type 6C22 amplifier tube is at top left

trace of the scanning line might be used for transmitting the sound on the picture carrier. But the maximum audio frequency which can be transmitted without serious distortion in such a system is limited to not more than one half the line-scanning frequency. In practice, distortionless transmission can be achieved up to a value of about one-third the scanning frequency, or in this case 31,500/3 = 10,500 cps. This is high enough to permit faithful sound transmission, but is not as high as the 15-kc limit specified for black-and-white sound.

The video waveform, showing the relative position of sound, video and synchronization signals, is shown in Fig. 3. This diagram is not unlike the standard video waveform of the vhf black-and-white system, except for the numerical constants and the insertion of the sound. Negative transmission is employed, that is, upward modulation produces black. In the region above the black level standard horizontal synchronization pulses are sent to synchronize each line. At the conclusion of each field, the vertical sync pulse is transmitted. This differs from the black-and-white standard in that no preparatory pulses are used, but the serrated form used in black-and-white (interspersed long pulses and double-frequency line pulses) is retained.

Below the black level, the camera signal is sent in the normal manner. Immediately following each horizontal sync pulse, while the scanning spot is retracing, a burst of 7.8-mc sine-wave signal is inserted, extended over the full amplitude of the black-to-white region, and lasting for eight percent of the horizontal scanning time. The 7.8-mc bursts constitute a discontinuous subcarrier which is frequency modulated by the sound signal. At the receiver the subcarrier bursts are selected from the video wave in a 7.8-mc tuned circuit and passed through an f-m discriminator which recovers the audio frequencies. The audio signal contains distortion products, due to the discontinuous nature of the carrier, extending from 15,000 cps upward. These are eliminated by a low-pass filter in the receiver which removes all audio signals above 10 kc. The extension of the audio subcarrier into the picture signal region would brighten the cathode-ray beam during the retrace time, unless means are provided to prevent it. Local blanking signals are generated in the receiver to depress the cathode-ray beam during the retrace time.



FIG. 5—The direct-viewing receiver demonstrated to the press. The screen of the 10-inch tube is magnified to 12-inch size. The shock-mounted color-wheel drive makes virtually no noise

The two basic advantages of the sound-on-sight system are: (1) one transmitter is required and (2) the receiver tuning is not critical. The receiver also is simpler in that no separate sound i-f amplifier is required, but this advantage is offset by the necessity of providing a low pass audio filter and local blanking circuits to remove the sound bursts from the picture.

The video waveform (Fig. 3) shows the color pulses which are used to synchronize the color wheel of the receiver. These consist of three additional horizontal sync pulses inserted during each of three successive fields (shown as c-d and e-f in the diagram).

The Receivers

Two receivers were demonstrated to the press, a direct-viewing type employing a 10-inch picture tube and magnifier, and a projection set using a Schmitt optical system to produce a 17 by 22-inch picture. The radio and video-frequency components, identical in the two sets, are shown in Fig. 4. The head end of the receiver is a silicon crystal mixer (no preamplification is used), which is continuously tunable over the band from 480 to 920 mc. The tuning element is an extensible transmission line of unusual design. Ganged to the tuning control is a tunable r-f filter which rejects images and reduces the noise spectrum. The local oscillator is a 6F4 acorn triode. The i-f amplifier consists of six stages, type 6AK5, operated at 105 mc and coupled by single-tuned circuits, tuned to three staggered frequencies. The sensitivity is such that the noise level (about 8 microvolts) is reached at full gain. This is an extremely low noise figure, considering that the overall i-f bandwidth is 12 mc. Two video frequency amplifiers are used, terminating in a 6AG7 tetrode.

In the direct-viewing set, Fig. 5, a 22-inch color wheel covers the face of the 10-inch tube. The filter seg-

ments have substantially the same shape as those used in 1940,[1, 2] but the filter materials themselves are somewhat different. Standardized color distributions, designated as Wratten numbers 61 (green) 47 (blue) and 26 (red) are used. One form of filter developed by Kodak is produced on an acetate base, coated with the colored gelatine and protected by lacquer. Segments of this material are riveted to a wheel made of transparent plastic. Another filter is a true plastic, developed by Monsanto, the color extending throughout the material. Sheets of this substance are inserted between two transparent discs, in the form of a sandwich.

One cause of occasional flicker in the 1940 images has been eliminated by rigid standardization of the optical transmission of the filter elements. The wheel consists of six segments, two of each color. If the two segments in a given color (particularly green, since this color contributes directly to the luminosity of the image) do not have the same transmission within a few percent, a 20-cycle flicker may be visible in areas having the same color as the filter segment. The manufacturers of the filter materials are able to meet the close tolerances required. The phosphor (of neutral white color) used in the cathode-ray tube has also been standardized by two manufacturers (Sylvania and General Electric). The phosphor is of the aluminum-backed type which increases the brightness and contrast of the image. The direct viewing receiver employs a magnifying lens to increase the apparent size of the image from 10 inches to 12 inches. Since this is a moderate degree of magnification, the angle over which the image is visible extends to about 30 degrees each side of the magnifier axis.

The filter wheel displays an average transmission of about 14 percent. Since 86 percent of the light is absorbed, the phosphor image must be very bright. An accelerating voltage of 8000 is used, obtained from a "flyback" power supply which employs the high voltage generated across the scanning coils during the horizontal retrace periods.

The color-wheel is driven by a 1750-rpm induction motor, synchronized by a type 6SN7 synchronization



FIG. 8—Front view of projection receiver, which produces a 17 by 22-inch picture through a Schmitt optical system

FIG. 7—Rear view of projection set. The cup-shaped color wheel is shown at right of projection tube, above the spherical mirror





FIG. 8—The receiving antenna consists of a dipole and a 6-by-2 foot parabolic reflector which can be steered by remote control. The fifteen-degree beam width eliminates ghosts from reflected signals

stage which compares the incoming pulses with locally generated ones and thereby controls the speed and phase of the disc. A phase compensation circuit is used to maintain the instantaneous position of the wheel within a few degrees of the correct value as it rotates. This permits full utilization of the area of the filter segments. Since the color wheel synchronization is obtained from the video waveform, the phasing of the color segments is automatically selected (that is, a given color automatically appears before the receiver tube when that color is present before the camera at the transmitter).

Since the fundamental color recurrence rate of the system is 120 per second, which is twice that of the power frequency of 60 cps, precautions must be taken to shield the picture tube from a-c fields, and to avoid power supply ripple in certain critical circuits, particularly the scanning generator output tubes. Such filtering is not required in all scanning tubes, however, and its cost is moderate. The picture tube shield is of the permalloy type.

The projection receiver, Fig. 6 and 7, employs a 5-inch projection tube which faces downward toward the spherical mirror of the Schmitt optical system, where the image is reflected through a molded cast-plastic correction lens. The color sequence is introduced by a modified wheel in the form of a cup, mounted to the side of the picture tube. The filter segments rotate directly under the face of the projection tube. To conserve light, the blue filter used has twice the optical transmission of the filter used in the direct-viewing receiver, and as a consequence the color gamut is somewhat reduced in the projection set. The projection color wheel rotates at 600 rpm and contains 12 segments, four of each color.

In a high definition picture ghost images must be minimized, and this is particularly important when color is transmitted. To avoid ghosts from reflected signals (which may also affect the quality of the f-m burst sound transmission) a directive receiver aerial is considered essential for use in built-up city districts.

Receiving Antenna

The antenna used in the demonstrations is a single dipole, Fig. 8, mounted at the focus of a parabolic reflector of perforated metal, 6 feet wide and 2 feet high. The beam width is about 15 degrees in azimuth. The structure is motor driven in azimuth. Direction can be shown on a chart by a remote control through a selsyn indicator system. Excellent ghost-free reception was obtained on direct line to the transmitter as well as by reflected signals from the Empire State building and other tall buildings in the vicinity. No difficulty was experienced in avoiding reflections, although ghosts were visible when the beam was turned so that it faced the wall of the CBS building.

Camera and Pick-up Equipment

At present the CBS equipment is limited to pickup from 16-mm color



FIG. 9—Camera pick-up equipment for 16-mm film and 35-mm slides. The continuous-motion projector and color wheel are at the left, selector lens disc at center, image dissector in cylindrical housing at right

film and 35-mm color slides. Work is in progress on a direct pickup camera which is expected to be ready for demonstration in May. The film camera tube is an image dissector, a tube ideally suited because it has no storage and hence does not carry over stored charge on the unscanned interlaced lines from one color segment to the next. The tube has low sensitivity, however, and requires correspondingly great illumination—too great to permit direct pickup. The direct equipment will employ an orthicon storage-type tube. The film images are scanned in a continuous-motion projector by passage through five stationary lens elements. A selector disc permitting light to pass through one lens at a time, Fig. 9, introduces a shift in the optical axis to counterbalance the motion of the film.

A block diagram of the pickup and associated sync equipment is shown in Fig. 10. The signal output from the dissector, after passage through the video preamplifier, is passed to a video amplifier and gamma control. The latter is a non-linear amplifier which compensates for the curvature in the dynamic transfer characteristic of the remainder of the system, including the receiver picture tube. After passage through this gamma control amplifier, the signal has such a form that the light output in the receiver picture tube is a linear function of the light input to the dissector tube, that is, the gamma is unity. This is a new departure which has greatly improved the ability of the system to render dark shades, as well as to maintain color balance over a wide range of illumination. The gamma control has the property of maintaining a fixed output amplitude regardless of changes in the curvature introduced. The gamma control is applied simultaneously to all three colors. A separate gamma characteristic for each color, introduced in sequence, has theoretical advantages but has not proved necessary in practice.

After emerging from the gamma control the camera signal is mixed with the other portions of the video waveform (sync and sound f-m bursts in accordance with Fig. 3. Monitoring facilities are provided at the outputs of the sync generator (waveforms viewed), the gamma control (image viewed in black and white), and the mixer amplifier (image viewed in color). The relative amplitudes of the camera signals produced in the three colors are varied by the color mixer. This is an improved version of the color mixing equipment used in 1940. The 1940 mixer employed 20 tubes and occupied three chassis of equipment. The new mixer is purely mechanical in operation and occupies less space than a 6-inch cube. The image pickup, synchronization and sound-on-sight equipment is now being produced, following CBS designs, by the Westinghouse Electric Corp.

The system just described transmits excellent color pictures. The intrinsic definition of the pictures is better than the 525-line black-and-white pictures by virtue of the more than proportionally wide band used and, of course, the apparent definition is greatly enhanced by the color contrasts present in the image. From this standpoint the images are perhaps the best television pictures yet produced. Further work, to investigate the coverage properties of the uhf signal and to develop direct pickup equipment of equally high quality, has been undertaken by the CBS group and will be reported in these pages as soon as the results are available.—D. G. F.

References

(1) Color Television Demonstrated by CBS Engineers, ELECTRONICS, p 32, Oct. 1940.

(2) Goldmark, Dyer, Piore and Hollywood, Color Television, Part I, Proc. IRE p 162, Apr. 1942.



FIG. 10—Block diagram of pickup, sync and sound-on-sight equipment

ULTRASONIC

Design of r-f generator and quartz crystal radiator providing ultrasonic mechanical energy for disintegration of bacterial cells and other unique physical and chemical effects. The frequencies involved range as high as 500 megacycles

By FREDERICK W. SMITH, Jr. and PAUL K. STUMPF

Department of Medicine
College of Physicians and Surgeons
Columbia University, New York



FIG. 1—Chart giving percent reflection (K × 100) at interface of two media having different acoustic resistances

THE term "ultrasonics" is applied to super audible sound waves which can be generated in liquids and solids over a frequency range of 30 kc to as high as 500 mc. The unique physical and chemical effects produced by intense sound fields at these frequencies are finding wide applications in many fields of investigation. As an example, in the field of biochemistry ultrasonic energy has been successfully employed by the authors in the disintegration of bacterial cells, permitting a detailed study of their enzyme system.[1, 2] This paper presents a consideration of the problems encountered in the design and construction of ultrasonic laboratory equipment.

Height of fountain of liquid thrown up from surface of medium during ultrasonic exposure is criterion of ultrasonic intensity

The basic element of the piezo type ultrasonic generator consists of an X-cut quartz plate vibrating in the longitudinal or thickness mode, acoustically loaded by immersion in a liquid media and excited at mechanical resonance in order to achieve an appreciable ultrasonic output. The circular plate usually employed has diameters as large as 10 cm, the thickness of course being determined by the resonant frequency desired.

Ultrasonic intensities generated will vary directly with the acoustic resistance of the surrounding medium and with the square of the applied voltage and operating frequency. However, the latter two factors cannot be increased indefinitely to achieve greater outputs. The maximum voltage that can be applied is determined by the breakdown point of the crystal and its associated supports. Furthermore, vibration does not occur uniformly over the surface of the quartz plate, and if excited too vigorously the elastic limits of certain sections of it may be exceeded even though other areas are relatively motionless. Crystal fragility and liability to voltage breakdown increase at higher frequencies due to diminishing thickness, and hence operation at high intensities is usually confined to frequencies below one megacycle.

Efficiency Criteria

These limitations on the exciting power make it essential that the efficiency of the acoustical system be as high as possible. The four criteria for such a system are as follows:

(1) Damping of the quartz radiator due to its support must be avoided. This is accomplished by securing the crystal at points of low

GENERATOR



Radio-frequency generator connected to quartz radiator immersed in oil in glass container on table. Cooling system for oil is on shelf under table. Microscope stand is being used as rack and pinion for adjusting height of fluid-filled flask in oil. Output power is over 500 watts in operating range of from 150 to 1000 kc. At right is a rear view of the ultrasonic generator

motion either about its periphery or in the middle of the thickness dimension, the nodal point for an X-cut crystal.

(2) Reflections between objects to be immersed in the sound field and the conducting medium should be minimized. These will occur when the sound crosses a junction of two media having unequal acoustic resistances.[3] From the approximate acoustic resistances given on the reflection chart in Fig. 1 it may be seen that the reflection loss for a glass container immersed in an oil medium would be about 70 percent (K = 0.7 for an acoustic resistance ratio of 11), and between any medium and air close to 100 percent. Thin sections of material interposed in the sound path will cause a minimum of attenuation if they are an integral number of wavelengths thick.

(3) The acoustic loading on the radiator should be concentrated on one surface only. This requires that the other be coupled to a medium of very high or low acoustic resistance to provide a maximum of reflection. In practice, one surface is coupled to the liquid medium and the other is exposed to air, concentrating the radiation in one direction.

(4) In order to obtain large intensities coupled with a minimum of reflections, a medium having the highest acoustic resistance consistent with good dielectric properties is selected. A transformer oil, such as Wemco C produced by the Westinghouse Electric Corp., has proven to be one of the most suitable.

Fortunately, dispersion of the radiated energy does not introduce much loss since the radiation from a circular plane source is confined to a highly directional beam when the radio of radiator radius to the wavelength is large. Further concentration may be obtained by using a spherically curved plate of large curvature which develops very high intensities at its focal point. In addition, recent investigation has shown that slightly curved crystals, while not producing a marked focussing effect, provide intensities at all distances from the radiator which are superior to those obtainable from either a flat or focussed radiator.[4]

Design of Crystal Holder

With these requirements in mind, the crystal holder sketched in Fig. 2 was developed. It consists of a quartz crystal sandwiched between two brass rings that are held together by



FIG. 2—Construction of quartz radiator designed for immersion in oil

This work was supported by a grant from the John and Mary R. Markle Foundation, administered by Dr. D. E. Green of the Department of Medicine, College of Physicians and Surgeons, Columbia University.



FIG. 3—Coupling circuits suitable for matching the output of an r-f generator to a quartz radiator

a Lucite press device which permits changes in contact pressure of the brass electrodes on the quartz surfaces. Although it leads to some damping, this arrangement has the advantage that breakdown of the insulating medium is eliminated completely. With other types of holders which were constructed and tested, voltage breakdown of the transformer oil resulted in immediate and irreparable damage to the surfaces of the quartz crystal.

The surface of the quartz crystal is silver-plated routinely every six months by Brashear's method. It was found that a silver-plated surface is superior to a surface of aluminum or silver foil cemented or spattered onto the quartz surfaces. To increase the voltage breakdown path, the upper and lower plating is not carried out to the extreme edge of the crystal. Lucite is used exclusively in the mounting and in the oil chamber as insulation against high voltage.

The crystal holder is completely immersed in transformer oil which serves at once as insulation medium, conducting medium for ultrasound, and circulating fluid for the cooling system. The oil is circulated continuously by a centrifugal pump from the ultrasound apparatus through a copper coil surrounded by an ice-water mixture. Much heat is formed during operation and efficient cooling is necessary to prevent the temperature from rising above 30 C in the bacterial suspension.

When the crystal holder is immersed in the oil bath, the lower brass ring electrode automatically forms an air pocket, which almost completely reflects the sound waves at the lower side of the quartz plate. The reflected waves come automatically into the right phase with those radiated upwards and increase their energy, hence the total damping of the crystal becomes less, owing to the decrease in the radiation decrement.

In the design of the radio-frequency sources used to excite ultrasonic generators, it has heretofore been the trend to increase the power output capabilities of the equipment in order to increase ultrasonic outputs. The futility of this is evident when it is realized that only an increase in applied voltage is necessary to accomplish this. The actual power consumption of any crystal radiator will rarely exceed 250 watts and will usually be much less.

Ultrasonic Power Output

The input impedance at resonance of a quartz radiator is mainly resistive and is the equivalent of a load of 10,000 to 250,000 ohms shunted by a capacitance of as much as 100 $\mu\mu$f. Developing large voltages across such an impedance is simply a problem in impedance matching. The resistive load which the usual class-C amplifier must see across its tank circuit ranges from 500 to 10,000 ohms depending on its operating conditions, and these values will determine the matching ratios to be used in the network coupling the r-f generator to the crystal.

It is interesting to note that any reflection of sound back to the quartz radiator alters the electrical impedance of the radiator in a manner similar to that in which the impedance of a discontinuous transmission line varies with length. The input impedance is therefore a minimum when the reflection path is an odd number of quarter wavelengths long. Total reflection may also cause a shift in the quartz resonant frequency by as much as 20 percent and consequently is to be avoided.[6]

Coupling Circuits

In Fig. 3 are shown various coupling circuits suitable for matching purposes.

In Fig. 3A the crystal is connected directly across the tank circuit of the r-f generator and the excitation is limited to the peak voltage developed across the tank. In Fig. 3B, an inductive coupling circuit is shown but it has proven to be relatively inefficient and subject to breakdowns.

In Fig. 3C and 3D, a tapped tank circuit is utilized, the final amplifier being connected across only a portion of either branch. A further extension of this idea is the parallel resonant impedance transformer in Fig. 3E, where L is equal to $(R_s R_L)^{\frac{1}{2}}/\omega$. If the circuit Q is greater than 10, a small load R_s will be presented to a generator looking into either branch of the circuit when a large load R_L is shunted across it. This action is identical to that of the L matching network in Fig. 3F.

Probably the best arrangement is the use of a pi network as shown in Fig. 3G, which will provide the most exact impedance match and will obviate the use of a tank circuit.

Voltages developed across matching components will increase as the square root of the impedance level,

and hence special care must be taken in insulating these components. Sharp edges and corners will cause undue concentrations of electrostatic flux which are likely to result in corona and frequent breakdowns. The design of inductive elements should take into consideration not only the potential gradients existing across the windings and forms but also the amount of dissipation the coil forms must accommodate.

R-F Generator Circuit

The requirements of the r-f generator used to excite these radiators are similar to those of the usual radio transmitter, except that provisions for the use of both a crystal-controlled and a stabilized, calibrated variable-frequency exciter should be included. Operating frequencies may cover a wider range than usual but continuous frequency coverage is not absolutely essential. Additional refinements might also include a variable power output control and an automatic timing device to facilitate accurate ultrasonic time exposures.

The circuit of a generator designed and constructed to excite a quartz radiator is shown in Fig. 4. It employs beam-power tetrodes to eliminate neutralization, and the final amplifier consists of type 813 tubes operating in push-pull parallel. The generator has an operating range of from 150 to 1000 kc, obtained by switching plate circuit inductors. When fully loaded, it will deliver over 500 watts output. In operation, all metallic objects associated with the equipment are grounded to prevent accidental burning of the operator by induced potentials.

Simple oscillator circuits may also be employed as generators. A suitable oscillator circuit for this purpose, similar to those used as high-voltage supplies for cathode-ray tubes, is shown in Fig. 5.[6] The secondary, L_2, is tuned to the operating frequency by the distributed capacitance shunting it, and for low power loss is of very high impedance. To obtain a stable tuning characteristic, feedback for the grid circuit is obtained solely from L_2. To improve the generator regulation, the coupling between L_1 and L_2 is made at least twenty times greater than is critical.

For those tempted to experiment, it should be noted that the high damping of the quartz plate used as a radiator makes it impossible to employ this plate to establish the frequency of the generator.



FIG. 5—Self-excited oscillator circuit suitable for driving a quartz radiator

Typical Application

One application of the ultrasonic generator to the problems of enzymology will be described briefly. A thin suspension of bacteria is placed in a flask and immersed in the medium by a rack and pinion device. The flask is then adjusted to a critical distance from the radiator determined by the peak in the height of the cone of fluid thrown up within the flask by the radiation pressure of the ultrasound. After a ten-minute exposure to ensure satisfactory disintegration, the material is spun down in the high-speed head of a refrigerated International Centrifuge at 20,000 rpm. In five minutes all cellular debris as well as intact cells will have been centrifuged down, and the supernatant fluid, usually turbid and light amber in appearance, is carefully decanted into a chilled container for analysis.

References

(1) Stumpf, P. K., and Green, D. E., *J. Biol. Chem.*, 153, p. 387, 1944.
(2) Stumpf, P. K., *J. Biol. Chem.*, 159, p. 529, 1945.
(3) Bergmann, "Ultrasonics", Ch. 2, J. Wiley & Sons, New York.
(4) Labaw, L. W., Curved Quartz Crystals as Supersonic Generators, *J. Acous. Soc. Amer.*, 16, p. 231, Apr. 1945.
(5) Fox and Rock, A Quartz Plate with Coupled Liquid Column as a Variable Resonator, *Proc. IRE*, Jan. 1943.
(6) Schade, O. H., R. F. Operated High Voltage Supplies, *Proc. IRE*, Apr. 1943.



FIG. 4—Circuit of r-f generator used to excite an ultrasonic quartz radiator

AFC for R-F HEATING

Automatic correction of frequency shift under varying load is accomplished by an electric motor that tunes the heating oscillator back to the desired frequency. Discriminator and search circuits actuate relays to control motor rotation

By S. IVAN RAMBO

Design Engineer
Industrial Electronics Division
Westinghouse Electric Corporation
Baltimore, Md.

IN PROCESSING MATERIAL by means of radio-frequency energy, it is desirable to accurately control the heating oscillator frequency. Most oscillators used for induction and dielectric heating have poor frequency stability as compared to oscillators used for communication purposes. This is because they are much more heavily loaded, and the characteristics of the load change considerably during the heating cycle.

Some manufacturers have made an attempt to shield their oscillators to eliminate interference to communication services. However, with conditions met in field installations, excessive radiation can easily occur at the work-handling point, even though the oscillator itself has been properly shielded, unless extreme precautions are taken in shielding the work circuit as well.[1]

The Federal Communications Commission, to reduce interference to other services by industrial electronic equipment, has assigned definite frequency bands for use by industry. The tentative proposed frequency stability requirement is ±0.05 percent.[2] Obviously, it will not be practicable to maintain such stability with a self-excited type of generator without some means of frequency correction.

Amplifiers for Low Power

One possible solution to the problem is to employ broadcast transmitter design methods utilizing a crystal or small stabilized oscillator with amplifiers following it until the necessary power required to drive the final amplifier is obtained. In the case of generators of low output (1 to 10 kw), this method would be relatively inexpensive, although the added size and cost would be considerably greater than that of present heating oscillators. For higher-powered generators (10 to 200 kw), this method would add many complications and increase the cost tremendously over that of a simple oscillator of corresponding power output.

With the rapid development of frequency-modulation technique in the past few years, many automatic frequency control devices have been developed to maintain accurate oscillator frequency. Extremely accurate frequency control has been obtained by the use of reactance tubes or similar devices connected across the oscillator tank circuit.[3] Unfortunately, it is not very practical to utilize such correction means for high-power oscillators because of the large power requirements of the reactance tube and associated circuits. In addition, it is difficult to correct for the large frequency variations encountered in induction and dielectric heating oscillators because of the limited range of reactance variation obtainable with such devices.

It is possible to obtain heating oscillator frequency stability in the order of ±0.05 percent by mechanical means. If a portion of the oscillator circuit inductance, capacitance, or transmission line length, can be varied by means of a motor, a system such as that shown in block diagram form in Fig. 1 may be used.



FIG. 1—Essential stages of the afc system for an electronic heating generator. A frequency stability on the order of ± 0.05 percent is obtained

Tuning Correction

The output from a crystal oscillator which may operate at a desired heating oscillator frequency[4] or at some fixed frequency above or below the desired heating oscillator frequency[5] is fed into a mixer stage along with some voltage picked up from the heating oscillator. The output circuit of the mixer stage is designed to pass the difference frequency between the two oscillators. After suitable amplification, this voltage is applied to a diode discriminator which may be of the Seeley or Crosby type. If the crystal oscillator frequency is made the desired

Automatic frequency control is employed on this 100-kw Westinghouse oscillator for electronic heating

heating oscillator frequency, the *RC* or audio-frequency transformer type of frequency discrimination may be used.

The discriminator output is used to control electromagnetic relays, thyratrons or vacuum tubes which in turn control the motor attached to the variable element of the heating oscillator tank circuit.

Motor Tuning Control

If the heating oscillator is on frequency, the resultant discriminator output voltage will be zero so that the control circuit will permit the motor to be at rest. If the heating oscillator frequency drifts higher or lower than mean frequency, the discriminator resultant output will assume a polarity such as to drive the motor in the proper direction to return the oscillator to its proper frequency.

No detailed circuit for the conversion of difference frequency between heating oscillator and desired frequency to direct current is shown because the form which such a circuit takes depends upon the point in the frequency spectrum where the master oscillator operates and the accuracy of correction desired. However, the conversion of the discriminator output to mechanical motion of the variable element of the heating oscillator tank circuit is relatively independent of the oscillator frequency. One possible control system for this purpose is shown.

Figure 2 is a simplified diagram of a method for motor control which will function properly with certain limitations. The d-c voltage output from the discriminator is connected to the control grids of V_1 and V_2. In the plate circuits of these tubes polarized relay coils are connected in such a manner that if the plate current of V_1 exceeds that of V_2 by a certain amount, contact K_1A will close. If the plate current of V_2 exceeds that of V_1 by the same amount, contact K_1A' will close. Then if the discriminator is arranged so that point 1 is negative with respect to ground and point 2 is positive for a heating-oscillator frequency greater than the desired frequency, V_2 will draw more plate current than V_1, causing relay contact K_1A' to close. When K_1A' closes, it shorts out the coil of relay coil K_2 so that its contact K_2A opens and K_2B closes. This completes the circuit through the motor armature, causing current to flow from point B to point A.

The motor will rotate to vary the heating-oscillator tank circuit in the proper direction to lower its frequency until the proper frequency is reached when the voltage between points 1 and 2 are equal, at which time K_1A' opens, stopping the motor. Obviously, for a heating-oscillator frequency less than the proper frequency, the tank circuit will be varied in the opposite direction to make the necessary correction. The limitations of the circuit are imposed by the bandwidth of the discriminator employed and the sensitivity of the polarized relay.

Limitations of Discriminator

Figure 3 shows a typical plate current characteristic for V_1 and V_2. If the discriminator characteristic is so shaped as to cause the polarized relay to operate at points 1 and 2, then it will again center at points 3 and 4 where the difference currents



FIG. 2—Control circuit for converting the discriminator output into mechanical motion of the tuning element of the heating oscillator



FIG. 3—Plate current characteristics of tubes V_1 and V_2 of Fig. 2. Points 1 and 2 determine the correction accuracy and points 3 and 4 indicate the effective bandwidth of the discriminator

FIG. 4—Search circuit for maintaining the frequency within the desired limits at the start of a new heating cycle



are the same as at points 1 and 2. Unfortunately, the closer the points 1 and 2 are brought together by steepening the slope of the plate current crossover curves to get better accuracy of frequency correction the more rapidly do the plate currents approach one another off resonance.

Search Circuit Operation

With the relatively large frequency change encountered in radio-frequency generators during heat treatment of materials, the oscillator frequency may be outside the limits of points 3 or 4 at the start of a new heating cycle, so that no correction can take place. In order to make certain that this condition cannot occur, a further refinement of the circuit shown in Fig. 2 is usually necessary. A search circuit such as is shown in Fig. 4 can be made to cause the variable element in the heating-oscillator tank circuit to rotate, even though the frequency is outside the limits of points 3 and 4, until it is brought within these limits. The discriminator will then take over to center the frequency.

Some r-f voltage from the heating oscillator is coupled to an *LC* circuit tuned to the proper oscillator frequency. This circuit is connected to the grid of a pentode used as a detector, with the search relay K_4 connected in its plate circuit. The Q of this circuit and the bias voltage *E* are so adjusted that K_4 will close just before point 1 is reached for one direction of frequency connection and just before point 2 is reached in the opposite direction of frequency correction.

The adjustments will also cause K_4 to open just before points 3 and 4 are reached when the frequency departs from the mean frequency. Contacts K_4A and K_4B, along with limit switch *LS*, will then cause the motor to operate even though the frequency of the heating oscillator is outside the discriminator effective range until the frequency is brought within this range. When that occurs, they will relinquish control to the polarized relay K_1, which will perform the same function as before.

Other Methods

The frequency of the heating oscillator may be outside the desired limits of correction for an appreciable time at the beginning of a heat cycle. It may therefore be desirable to automatically return the variable portion of the tank circuit to the proper starting point after the completion of a heat cycle for applications where the heating procedure is not a continuous process. This can be done automatically by additional relay contact arrangements.

There are many other possible arrangements of relays, thyratrons and vacuum tubes which have been devised for other applications[6] and can be used to accomplish motor control for frequency correction. In any of these systems the problem of hunting arises, and may be overcome by the same methods employed for other motor control devices. In general, the higher the sensitivity desired the more difficult it becomes to overcome hunting unless the electrical and mechanical inertia of the system can be kept low.

Unfortunately, for large power oscillators the variable element will be bulky with inherent high inertia. For such cases, braking or motor-plugging schemes[7] may be employed to prevent motor overshoot. Such schemes apply reverse current to the motor armature momentarily of such magnitude as to overcome all inertia at the instant when it is desired to stop the motor. Many feedback systems[8] and motor-braking systems developed for other applications may also be helpful here.

Systems of the type discussed above for frequency correction can be made employing small receiving-type tubes and components whose overall size and cost will be much less than the oscillator-amplifier type of design. For small oscillators from 1 to 10 kw output it may be more economical to employ broadcast transmitter design technique for accurate frequency control. For larger units, the above system is much more economical in both space and cost.

References

(1) Klingaman, G. W., & Williams, G. H., Shielding of Dielectric Heating Installations, ELECTRONICS, p 106, May 1945.
(2) FCC Allocation Plan, ELECTRONICS, p 92, Mar. 1945.
(3) Hund, August, Reactance Tubes in F-M Applications, ELECTRONICS, p 68, Oct. 1942. Bard, Jr., H. B., Remote Tuning with Reactance Tubes, ELECTRONICS, p 100, Aug. 1945.
(4) Sheaffer, C. F., The Zero-Beat Method of Frequency Discrimination, *Proc. IRE*, Aug. 1942.
(5) Crosby, M. G., Reactance Tube Frequency Modulators, *RCA Rev.* 5, July 1940.
(6) Hale, H, Erwin, The K8 Computing Gunsight, ELECTRONICS, p 94, Jan. 1945. Bond, Donald S., Visual Direction Finders, ELECTRONICS, p 144, Jan. 1944. Gille, Willis H., & Sparrow, H. T., Electronic Autopilot Circuits, ELECTRONICS, p 110, Oct. 1944. Moyer, E. E., Electronic Control of D.C. Motors, ELECTRONICS, May, June, July, Sept., Oct., 1943.
(7) Harrell, F. E., & Hough, W. R., D.C. Braking of Induction Motors, *AIEE*, May, 1935.
(8) Garman, G. W., Thyratron Control of D.C. Motors, *AIEE Transactions*, p 337-342, 57, June, 1938.



Rotating sector and photo unit arrangement, as used in a grating spectrograph, shown with the electrostatic shield removed

By J. R. COSBY*
Department of Physics
Virginia Polytechnic Institute
Blacksburg, Va.

SPECTROGRAPH EXPOSURE CONTROL

Semi-automatic device employing a phototube and a grid-glow tube permits duplicate exposures to be made on photographic plates despite variations in the arc source. Other applications are indicated

IN RECENT YEARS the spectrograph has evolved from a small optical instrument with little dispersive power to a massive structure having dispersive powers of the order of 1.0 angstrom per millimeter or less.

The necessity for some device whereby duplicate exposures on photographic plates may be obtained naturally arises, especially in quantitative spectrographic analysis. A need for such a device is readily grasped when one observes the image of the arc or spark source on the slit of the spectrograph wandering from side to side, changing in intensity and even failing.

The types of spectrographs in use are generally of the grating or quartz-prism types and both can be adapted for use with a semi-automatic integrating exposure control developed by the author. In particular, the grating spectrograph lends itself readily to an integrating method of recording the light energy developed. The apparatus described herein was designed to operate with a grating spectrograph having a dispersive power of 2.6 angstroms per millimeter, employing a grating of 30,000 lines per inch and having a radius of curvature of 21 feet. Using a simple photocell, it automatically determines the end point of photographic exposures and further application of such a device to other measurements, such as solar radiation,



FIG. 1—Simplified diagram of a grating spectrograph equipped with an exposure-control photo unit

* Now with the Friez Instrument Div., Bendix Aviation Corp., Baltimore, Md.



FIG. 2—Complete circuit diagram of the spectrograph exposure control device

visible and invisible, will be apparent. The use of the device to measure the intensity of spectral lines in spectroscopy is also possible.

The Apparatus

Figure 1 shows the relative locations of the various parts of a grating spectrograph. The phototube unit is located near the slit of the spectrograph, within the spectrograph enclosure. Light from the arc source passes through the slit to the mirror and then to the grating, forming spectrum lines on the plate holder and giving a central image.

In this particular application the incident light received by the phototube is reflected from the surface of a polished aluminum rotating sector located between the slit and the mirror within the spectrograph enclosure. The sector is adjustable for long or short exposures, dependent upon the nature of the analysis. Thus the light received by the phototube will be actually only a cross section of that exposing the photographic plate. If the sector is rotated at a reasonable speed (about 900 rpm) the light received by the phototube will be representative of that received by the spectrograph plate.

As shown in Figure 2, the photo unit consists of two tubes VT_1 and VT_2, a phototube and a cold-cathode grid-glow tube. The grid-glow tube operates as an integrating-device actuator.

Details of Operation

In operation, the phototube converts the incident light into electrical energy and charges a capacitor, C_B, at a rate proportional to the intensity of the incident radiation, at the same time discharging C_A. Capacitors C_A and C_B are the partial capacitances of VT_1 and VT_2. At a particular grid potential predetermined by the voltage on the plate of VT_2, the grid-glow tube fires, registering one integrated interval, and reestablishes the system to its initial conditions. This process is repeated many times for a complete exposure, thus giving an integrated result. The accuracy is dependent partially upon the size of the increments. The dial setting determines the number of these increments. A ratchet wheel having many teeth is employed to position the dial, sums up the increments and thus becomes the integrator.

The overall unit contains a rectifier to supply the necessary d-c voltages for the phototube and the grid-glow tube. The sample to be analyzed is placed in the cavity of the lower arc electrode (pure carbon) and an arc is established between the two electrodes. This causes relay RL_1 to operate, completing the circuit to the grid-glow tube. Relay RL_1 insures inoperation of the indicator should the arc fail. Reestablishment of the arc restores operation. This provision also permits the exposure to be interrupted if desired without appreciable error due to slight leakages that may exist.

After each successive charge-up of capacitance C_B, VT_2 fires, causing the relay RL_2 to operate, actuating sole-



Front panel of power supply, relay and ratchet unit, showing the indicator dial

noid RL_3 which ratches the dial one increment and resets the grid-glow tube by opening its plate circuit for an instant by means of the switch located near the solenoid arm. After many such cycles of operation are completed a cam-switch opens and releases the arc cutoff relay RL_4, thus interrupting the arc circuit. This arc cutoff relay extinguishes the arc when the desired exposure or end point is obtained. The desired length of exposure is determined by the position of the cam switch, which is preset by moving the indicator arm about the indicator scale. Once the arc is established for any setting of the dial, the operation is automatic.

Certain precautions must be taken to eliminate as far as possible any leakage paths present across the phototube leads. Removal of the base from the phototube and the grid-glow tube is recommended. The photounit must be mounted on a base of good dielectric material. If mounted compactly, surrounded by some form of electrostatic shielding and properly grounded, a portable arrangement will be obtained with only three interconnecting leads to the recording unit. In humid climates, operation of the phototube unit under a desiccator might be required.

Performance

It is reasonable to expect some variation in the sensitivity of the phototube cathode surface to the wavelength of incident light and to area of surface. However, for any given analysis, especially in samples having the unknown material in percentages of the order ½ to 5 percent, the energy distribution is rather constant. Furthermore the cathode surface exposed for different spectrograms is practically constant. Losses due to absorption in the air are likewise similar for each sample. These errors, although they represent inaccuracies so far as quantitative measure of the incident light is concerned, do not represent errors in obtaining duplication of results for any complete analysis.

Figure 3 is an exposed spectrograph plate showing five successive copper spectrograms. Each of these exposures was made by the integrating exposure control from unweighed electrodes of copper. There was an actual variation in exposure time of over three to one when taking the five spectrograms. This large variation in exposure time was due to deliberate motion of the arc, causing the image of the arc to wander on and off the slit. Examination of this plate shows the uniformity of results obtained by this equipment.

Further sensitivity can be obtained by employing a C7022B electron-multiplier phototube. Some preliminary data has been obtained using this tube at the central image, thus eliminating lens systems and reflections from a rotating sector. The results indicate that a sensitivity of at least ten times that obtained with the apparatus described can be obtained. Certain difficulties were encountered, the greatest of these being variation of the sensitivity of the portion of the phototube surface employed.

The author acknowledges the assistance of H. D. Ussery, Dr. F. B. Haynes, and other members of the Physics Department of the Virginia Polytechnic Institute, whose cooperation made possible this development.

Bibliography

James, H., and Salzberg, B., *Proc. IRE* 23, Jan., 1935.
Allen, J. S., *Physical Review*, 55, p 966–971, 1939.
Allen, J. S., *Proc. IRE*, 27, p 558–566, 1939.
Zworykin, V. K., *Proc. IRE*, 24, p. 351, 1936.
Bedell, F., and Reich, H. J., Rev. of Scient. Inst., 2, p 532, 1931.
Hoag, J. Barton, "Electron and Nuclear Physics," Van Nostrand Co., New York, 1938.
Hughes, A. L., and DuBridge, L. A., "Photoelectric Phenomena," McGraw-Hill Book Co., New York, 1932.
Farnsworth, P. T., *Jour. Franklin Institute*, 218, p 411, 1934.
Radio Corporation of America Application Sheets, 917, p 6, 1939.
Radio Corporation of America Application Sheets, C7004.
Westinghouse Electric Company, Bulletin TD81.



Spectrograph exposure control power supply, relay and ratchet unit, seen from the back



FIG. 3—Exposed plate showing, from top to bottom, five successive exposures under the varying arc and time conditions indicated at the left

Vibration and MOBILE



FIG. 1—The solid lines show the usual method of mounting electronic equipment to isolate vibration and reduce shock. The vertical dashed lines show the location of wires used in the experimental determination of radius of gyration



FIG. 2—Resonance diagram for use in applying shock and vibration mounts with horizontal stiffness equal to one-quarter the vertical stiffness. R = radius of gyration $\cong$ 1/5 (case height and case width), H = vertical distance-mounts to center of gravity, L = mount spacing

VIBRATION FATIGUE TESTS of commercial and military aircraft radios are standard practice in the industry, and the accepted requirements have been covered by government specifications. However, improved types of vibration isolators[1] are now commercially available for aircraft and new applications of radio equipment are presenting shock and vibration conditions of an entirely different nature. Proper application of the new vibration isolators and tests of equipment for services other than aircraft require the application of some theory not previously used, as well as a few additional methods of using vibration test equipment.

The tests indicate such things as possible interference due to relative movements of parts under vibration; their points of resonance; the swinging of connecting wires; crystallization of or weakness at soldered terminals; fasteners that loosen; strength of brackets, especially at bends; welded joints subject to shock and vibration; and mount problems.

We use two types of vibration tests in conjunction with design. The first test is a check of the mechanical design of the unit itself. The complete unshockmounted unit is subjected to vibration over the expected or specified frequency range, and carefully observed with a Strobotac for any resonant vibratory motion of components, panels, etc. The vibration is applied successively in three mutually perpendicular directions by a machine made by L. A. B. Corporation of Summit, N. J.

Vibratory displacements of 0.005 inch are sufficient to produce easily observable motion in any members resonant in the usually specified test range of 600 to 3600 cycles per minute. If there is vibration in service at the resonant frequency of any member, even amplitudes so small that they can barely be felt are sufficient to cause fatigue failure of unmounted equipment resonant at an exciting frequency. If vibration-isolating mounts are used, component resonance must be well above (3 or more times) mount resonance.

Two Tests

The structural strength of radio chassis and brackets is usually empirically determined by the designer, who is normally primarily influenced by such considerations as weight, electrical performance and ease of servicing. Increased competitive emphasis on these factors requires more highly stressed structural members and increases the probability of resonance at frequencies present in service. No readily usable design data on resonance of structural members is available, and "beefing up" of members found by test to be resonant is the usual procedure. An example of this first test is illustrated by a flightweight receiver designed for use in light personal planes where absolute minimum weight is essential.

Communications equipment designed for services which subject the equipment to shock or vibration is almost invariably shockmounted.

Whether the mounts are primarily intended to absorb shock, or are both to absorb shock and to isolate vibration, there is the same design problem. This is because the usual form of shockmount is essentially a rubber spring and if only its shock-absorbing qualities are considered by the designer the mount in many actual cases will amplify barely noticeable vibration up to destructive amplitudes. Tube failure complaints from the field are a good indication of vibration amplification in service, if

Shock Testing of EQUIPMENT

Proper application of newly developed vibration isolators to mobile communications equipment requires techniques not previously employed. Methods of testing shockmounts in three mutually perpendicular directions are given, along with data on resonant conditions

By JOHN H. BEST

Engineering Department, Radio Division
Bendix Aviation Corporation
Baltimore, Maryland



Personal aircraft receiver and radio compass mounted for mechanical resonance test

it is known that shock conditions are not the probable cause. The second vibration test is to secure data on the vibration isolation efficiency of the shockmount.

Directions of Resonant Frequencies

In most applications, the greatest shock forces are in a vertical direction, and in the past it was customary to apply the test vibration only in this direction. The current practice, however, is to test in three mutually perpendicular directions, since the direction of vibration in service is dependent on the nature of the equipments support and the structure between the cause of vibration and the equipment. The usual result in field tests is to find some components vibrating in all directions. Since most communications equipment is for general application, it must be assumed for test purposes that all directions of vibration are equally important.

The widely distributed formulas for calculation of isolation efficiency of mounts assume that the equipment will only have a lineal vibratory motion and no tendency to rotate. This is true only so long as the unit is on mounts loaded to equal deflections and located in a plane passing through the center of gravity of the unit. For obvious reasons, however, the most widely used layout places all the mounts between the unit and the supporting surface, and the equipment is free to tip as well as to move lineally. In such cases the mounted unit has one vertical resonant frequency, two resonant frequencies about a fore and aft horizontal axis, and two about a sidewise horizontal axis. These occur one above and one below the single horizontal resonant frequency which would be secured if the unit did not tip.

With many of the mount designs applied in the past to usual radio designs this higher resonant frequency is at or near the speed of internal combustion engines, and is very undesirable. There is a sixth resonant frequency—torsional about a vertical axis—but this has no significance in most applications.

A formula useful for computing these torsional modes of resonance is given below. Its derivation is similar to that of the formula for use without tipping and is based on the classic equation $F = MA$. Equal mounts, equally loaded and symmetrically placed with respect to the center of gravity, are assumed, but for practical purposes negligible error is introduced by using the average of four slightly different static deflections such as are usual in an actual design. The vertical resonant fre-

quency in cps is computed by the usual formula $f_r = 3.1\sqrt{1\Delta_r}$.

resonant frequencies (cps)

$$= 2.21\sqrt{B \pm \sqrt{B^2 - 4C}}$$

$$\text{where } B = \frac{S\,L/2\,(2 + H^2 + R^2)}{\Delta_r\,SR^2}$$

$$\text{and } C = \frac{L^2/2}{\Delta_r^2\,SR^2}$$

L = Distance between mounts
H = Height of equipment's center of gravity above plane of mounts
R = Radius of gyration of the equipment
Δ_r = Static deflection of mounts
S = Horizontal to vertical softness ratio of mounts

These relations are illustrated in Fig. 1 which shows a schematic drawing of the usual method of mounting electronic equipment. It also shows the location of supports used in experimentally determining radius of gyration as referred to below.

Radius of Gyration

If any accuracy is to be secured with this formula—or any other formula—the static deflection and softness ratio must be secured under the actual load conditions. Most mount load deflection curves are nonlineal and the slopes at the point of actual loading must be used, rather than total measured deflections. Radius of gyration can be rather laboriously computed by handbook formulas, or can be approximated ($\frac{1}{3}$ of $A + B$ in the sketch is an average value from measurements on a number of aircraft radios), but is best actually measured by use of a bifilar pendulum. For the latter, the formula is as follows (T is the period in seconds; other dimensions show in the sketch and are expressed in inches.)

$$R = 3.14\,T\sqrt{CD/L}$$

In applying the resonance formula, the designer usually finds the height and radius of gyration fixed by other considerations. Mounts with suitable static deflection and horizontal softness ratio can be selected, however. Deflection of $\frac{1}{16}$ to $\frac{1}{8}$ inch and softness ratios of 3 to 5 are about the values required for general aircraft application (no resonance above 15 cps) and approximately these values are now commercially available. Graphs similar to that shown in Fig. 2 (for a mount in use by Bendix) can then eliminate the need of successive approximations in finding the greatest spacing which will not exceed the maximum allowable frequency. (The maximum permissible spacing should be used to minimize shock forces on the mounts.)

The improvement in performance which can be secured from use of mounts with suitable horizontal softness is illustrated by the photographs of Fig. 3 and the performance curves of Fig. 4. The unit shown conforms to standard $\frac{1}{2}$ ATR case dimensions. Mounts of the same type and rating were used in both cases, but a simple adapter was added in one case to increase horizontal softness.

Vertical isolation at 1500 and 2100 cpm with the standard mounts is not as great as would theoretically be expected, but is typical of many installations. Unequal loading of the mounts results in slight torsional impulses which have an appreciable effect at the torsional resonance frequency. The performance in the operating range of the horizontally soft mounts under vertical vibration is improved by the elimination of these slight peaks, even though the load is no more evenly distributed.

Shock Fatigue Tests

The vibration test table may also be used for shock fatigue testing if such a test is warranted by the requirements of the application. For such an application electronic equipment is normally shock-mounted on rubber. The mounts effectively isolate against large impact shock forces caused by rapid small displacements, such as are caused by metal-to-metal contact or by the vibration of structural members induced by impact forces. No effective isolation, however, can be secured from accelerative forces without exceeding reasonable space limitations, and if these forces are large and numerous in service, fatigue failure should be investigated. This requires test forces equal to or greater than those which may be expected in service, at frequencies near the resonant frequency of the mounted equipment. This frequency is dictated by the fact that accelerative forces in service will cause rapidly decaying vibration of the unit at its resonant frequency, regardless of the speed with which the force is applied.

In service, large accelerative shock forces normally will deflect mounts past their lineal range. In test, to secure large forces at low frequencies, the displacements must also be large enough to cause deflection past the lineal range. It is then no longer possible to treat the mount as a simple spring with one resonant frequency, such as is generally assumed for vibration isolation calculations.

FIG. 3—Bendix interphone amplifiers whose geometrical proportions (½ ATR, CAA designation) present the most difficult vibration isolation problem of the standard equipment cases. The unit on the left is mounted on conventional vertical shear-type mountings and the unit at right is mounted on identical rubber elements with an additional rubber part to produce isolation of horizontal vibration. The test table in both cases is vibrating at a speed of 2100 rpm, with a total excursion of 1/64 inch in the left-right direction. The photographic definition of the equipment shown at the right illustrates the improvement



FIG. 4—Overall vibration performance at various engine speeds and in three mutually perpendicular directions is shown on these graphs for the two units of Fig. 3. In the graph on the right, effective isolation is secured in the normal operating range of aircraft engines. The graph on the left shows that conventional mounts actually magnify vibration at these speeds

A load mounted on a spring whose modulus is constant for small deflections but which increases with increasing large deflections has a range of resonant frequencies, rather than a single resonant frequency. If the frequency of an adequate disturbing force is increased past the resonant frequency of the lineal deflection, the spring deflects further into the nonlineal range of the spring. The greater force speeds up the motion and resonant motion of the load continues at frequencies above the lineal resonant frequency.

This motion continues as frequency is increased until the friction loss in the mount equals the energy input of the disturbing force, when the motion subsides to movements in the lineal range whose magnitude can be computed by the simple spring formula.

Such resonance carry-over is of course highly undesirable in service, but can easily be—and always is—avoided by making the linear deflection range of the spring materially greater than the vibratory displacements which will be encountered in service. The phenomenon is important, however, when testing at large amplitudes and low frequencies. Knowing the stress-strain relation of the mount, it is possible to compute the approximate deflection for resonance at frequencies above linear resonance. A method for doing this is given in Den Hartog's "Mechanical Vibration," but the method is laborious and the results inaccurate because of the comparatively large effect of internal friction in such cases. For most purposes it is sufficient merely to be familiar with this type of resonance, and frequency displacement curves at various exciting displacements for a case of this type are shown in Fig. 5.



FIG. 5—Vibration isolation and magnification of an effectively lineal vibration isolator and a nonlineal shock absorbing bumper. At amplitudes of vibrations such as would be reasonably encountered in service, there is a single resonant frequency. At larger amplitudes, there is a range of frequencies above this at which resonance continues due to the combined effect of lineal and nonlineal characteristics

Other Equipment

To use resonance carry-over for test purposes it is also necessary to measure the forces. Since the movement is not simple harmonic motion, the usual G meters reading rms voltage are not suitable. A pressure-sensitive pickup from such a device feeding a recorder of suitable frequency response must be used so that the peak voltage generated by the pickup can be measured rather than the rms value.

With such a device, forces of large definite magnitudes near linear resonance frequency can be obtained with practically any type of mount. Curves showing the forces generated by the simple harmonic motion of a test table, and the forces in a unit vibrating resonantly with a complex harmonic motion are shown.

The equipment from which the curves were secured is the Bendix railroad model MRT-1 communications transmitter-receiver. The test subjects the unit to forces of the magnitude of those encountered in severe service conditions such as are encountered in switch-engine installations and freight service in mountainous regions.

Reference

(1) Vibration Control for Electronic Products, ELECTRONICS, p 134, September 1945.

F-M Radar Altimeter

Frequency-modulated signals from the APN-1 equipment are directed earthward from an aircraft, and the beat note between transmitted and received signals is measured to obtain an indication of altitude, accurate to a few feet above the earth

IN 1938 United Airlines demonstrated to the press a radio altimeter which had been developed by the Bell Telephone Laboratories, and which revealed the height of an aircraft above the terrain by timing a reflected radio wave. The word radar had not then been invented, and the principle employed by the altimeter was different from that of the pulse-type radars which were then being developed in great secrecy.. No technical information was revealed at the time, but the general principle of operation was described in several publications[1, 2]. Shortly thereafter censorship was imposed on further information.

A detailed description of an f-m radar altimeter may now be given, following the recent declassification of the model AN/APN-1 altimeter. This altimeter was installed on over 100,000 Army and Navy aircraft during the war. The APN-1, operating on the same principles as the equipment demonstrated before the war, was designed for production by the RCA group at Camden. The altimeter is one of two widely used in wartime aviation (the other uses the reflected pulse principle). It is expected to be installed on commercial aircraft following recent type approval by the Civil Aeronautics Authority.



Type AVQ-6 f-m radar altimeter, version of the APN-1 equipment approved by CAA for commercial use

Principle of F-M Radar

Frequency-modulation radar determines the distance to a reflecting surface (in this case the ground beneath the plane) by measuring the frequency shift between transmitted and reflected waves. While the wave is traveling to the surface and back, the transmitter frequency is changing under the influence of the frequency modulation. When the reflected wave arrives back at the transmitter, its frequency is slightly different from that then being transmitted. The transmitted and reflected signals are combined in a detector and the frequency difference between them developed as a beat note.. This frequency difference becomes larger as the distance to the reflecting surface becomes greater. The altitude is indicated by converting the beat frequency into a distance indication.

The advantage of this method lies in its ability to measure very short distances, down to a few feet. The minimum detection distance in the pulse method is limited by the length of the pulse. Even if a pulse as short as 0.2 microsecond is used, the minimum range is one hundred feet. Pulse radar thus cannot indicate altitude during landings when the height of the aircraft above ground must be accurately indicated from a few hundred feet down to zero. For indicating higher altitudes, the pulse method is useful and has in fact been employed in a high-altitude instrument.



Lubber-line installation of radar altimeter dipoles below the fuselage of a Navy Consolidated Privateer (PB4Y-2). The radomes house antennas for radar countermeasures

One disadvantage of the f-m principle is the fact that an altimeter designed for low-altitude indication cannot indicate very high altitudes without lowering the deviation of the frequency modulation. Hence, two scales are required to cover all operational altitudes and in early equipments there was a chance of human error in reading the correct scale. Later versions of the equipment provided against this type of error.

The quantitative relationships which govern the design of an f-m radar altimeter may be derived from Fig. 1. At the top of the figure, the frequencies of the transmitted and received waves are plotted as functions of time. The solid line represents the transmitted frequency, which is modulated by the linear triangular waveform. The total deviation of the frequency modulation (the peak-to-peak value of the modulation envelope) is indicated as ΔC megacycles. In the APN-1 equipment, the center frequency is 440 mc, and the deviation is plus or minus 20 mc ($\Delta C = 40$ mc) on the low-altitude range.

The dashed line in Fig. 1 represents the received signal. This signal is, of course, frequency-modulated by the same envelope since the signal preserves its form during reflection, but the received signal is displaced in time by the reflected interval, which is equal to $2h/c$ where h is the height of the aircraft above the terrain in feet and c is the velocity of radio wave propagation in feet per second. As a consequence of this time displacement, a corresponding frequency displacement occurs, indicated by the vertical separation Δf between the solid and dashed lines.

The relationship between the altitude h and the frequency difference Δf, can be found by comparing similar triangles in the figure. The height of the triangular waveform is ΔC and half its base is $1/(2f_m)$, where f_m is the frequency of the modulation envelope. The ratio of the height to half the base is $2\Delta Cf_m$ and this is equal to the frequency difference divided by the time difference:

$$2\Delta Cf_m = \frac{\Delta f}{2h/c} \qquad (1)$$

where ΔC, f_m, and Δf are all measured in cps. The relationship between frequency difference and height is then found by rearranging Eq. 1

$$\frac{\Delta f}{h} = \frac{4\Delta Cf_m}{c} \qquad (2)$$

It will be noted that the sensitivity of the indication, in cps frequency difference per foot, can be increased by employing a wide frequency deviation or a high modulation frequency, or both. In the APN-1 equipment, ΔC is 40 mc, f_m is 120 cps, and c is 984×10^6 feet per second, and hence $\Delta f/h$ is 19 cps per foot of altitude.

It thus appears that audio frequencies up to 7,600 cps are developed in the beat note between transmitted and received signals, provided that heights not greater than 400 feet are encountered. For higher altitudes, up to 4,000 feet, a lower frequency deviation $\Delta C = 4$ mc is introduced and the beat frequency is thereby reduced to 1.9 cps per foot. The maximum beat frequency developed is then the same ($4000 \times 1.9 = 7{,}600$ cps).

A minor aberration occurs during the period between reversal of the

electronics WAR REPORT



FIG. 1—Time and frequency relationships when a triangular modulation envelope is employed in an f-m radar system. Transmitted and received signals combine to give a-f beat note



FIG. 2—Time and frequency relationships when the modulation envelope is sinusoidal. The average beat note corresponds to the constant beat of the triangular case (Fig. 1)

transmitted frequency deviation and the corresponding reversal in the received wave, as shown in Fig. 1. The transmitted frequency, at the center of this period, falls to a value equal to the received signal, which is then still increasing. At this instant, therefore, the beat note is zero. During this crossover interval the beat frequency is variable, dropping to zero at the center. However, the duration of the crossover interval is only 20 microseconds, at the maximum altitude of 4,000 feet, compared with 42,500 microseconds, the half period of the modulation envelope. Consequently the crossover effect is negligible.

In practice it is not convenient to modulate the frequency with a triangular envelope, and a sinusoidal envelope is substituted. The situation is then that shown in Fig. 2. The frequency difference is no longer a constant between crossovers, but varies in the manner shown, from zero at the crossover to a maximum which occurs when the transmitted frequency is passing through its center value. By circuits described later, the average beat frequency is measured and this value corresponds with that produced by triangular modulation. Equation 2 may be used to predict the average beat frequency Δf when sinusoidal modulation is used.

In installing the equipment in an aircraft, care must be taken to equalize residual delays between the transmitting and receiving inputs to the beat-note detector. The distance between the inputs is not zero when the wheels of the aircraft are on the ground, but is equal to the sum of the cable lengths between detector and the two radiators, plus the physical reflection distance (amounting to a few feet) between radiators and the ground midway between them. This residual altitude error is removed in calibrating the instrument.

A final error may appear when the aircraft is flying over very smooth terrain such as a runway or smooth water. Under these conditions, the indicated beat frequency shifts back and forth by an amount equivalent to about six feet when the actual altitude changes by six inches (one quarter wavelength at 440 mc). When the terrain contains a rough surface (projections higher than six inches) the shift is averaged out and the indicated altitude is the correct value. The shifting altitude (known as fixed error) may be quickly recognized, and the correct altitude is the intermediate value between the limits of the shift.

General Layout of APN-1 Equipment

A block diagram of the essential elements of the APN-1 altimeter is shown in Fig. 3. A transformer-coupled audio oscillator operating at 120 cps drives the modulator unit. This is a mechanical modulator resembling the voice-coil assembly of a dynamic loudspeaker. The moving element of the modulator drives one plate of a balanced capacitor in the transmitter tank circuit, thus producing a frequency-modulated output. Two amplitudes of drive are available, one for 40 mc total deviation (low-altitude scale), the other for the reduced deviation of 4 mc (high-altitude scale).

The transmitter itself is a line-controlled push-pull oscillator employing two types 955 acorn triodes. The transmitter produces a power output of about 100 milliwatts at a center frequency of 440 mc. Part of the transmitted signal is passed to a dipole transmitting antenna, mounted under one wing of the aircraft. Another portion of the signal is injected



FIG. 3—Block diagram of the APN-1 altimeter. The beat note is clipped and its average frequency measured in the counter circuits



FIG. 4—Balanced diode detector. The circuit arrangement is insensitive to amplitude modulation which may arise due to passage of the f-m signal through the resonances of the circuit elements

directly into the receiver detector.

The head end of the receiver is a balanced push-pull detector employing two type 9004 acorn diodes. The balanced detector mixes the received and transmitted signals. These signals are applied respectively in push-push and push-pull, an arrangement which avoids mutual coupling between the two signals. The push-push connection is a rod centrally located between two conductors of the detector tuned circuit, and the push-pull connection is a coupling loop. The detector circuit is balanced against amplitude-modulated signals and hence discriminates against amplitude variations introduced by the passage of the f-m signals through the resonant regions of the tuned circuits and antennas. The details of the detector are shown in Fig. 4.

The audio-frequency output (beat note) of the detector is passed to a three-stage audio amplifier which has the frequency response characteristic shown in Fig. 5. The low-fre-quency components are attenuated, since the amplitude modulation due to resonant effects is at a maximum at the modulation frequency (120 cps) and its lower harmonics. The gain characteristic also equalizes the amplitude of the beat note as a function of height, since the received signal is strongest when the aircraft is near the ground and the beat note has its lowest values. The a-f gain continues to increase above 7,600 cps, the maximum beat-note frequency. The high amplifier output drives the altitude indicator off scale when the altitude exceeds 400 and 4,000 feet, respectively, on the low and high altitude scale. The frequency charactertistic shown is obtained by the use of degenerative feedback. The amplifier is shock-mounted and is shielded against stray r-f pickup from other equipment.

The audio-frequency output of the amplifier is converted into a corresponding direct-current signal for altitude indication. This signal also actuates limit relays to indicate deviations from an assigned altitude or to control the automatic pilot. The conversion process begins in a limiter stage which converts the sinusoidal beat output (varying in frequency in accordance with Fig. 2) into a rectangular wave of about 135 volts peak-to-peak amplitude. The purpose of this limiter is to remove

FIG. 5—Frequency characteristic of the three-stage audio amplifier which discriminates against low-frequency components



FIG. 6—Double-diode counter circuit, which develops a positive d-c voltage proportional to the beat note frequency



amplitude variations which may persist and to provide sharp leading edges which may be counted in determining the average frequency of the beat note. The limiter stage, an over-driven amplifier, limits the positive peaks by grid current and the negative peaks by grid voltage cutoff.

The output of the limiter stage is passed to two counter stages, which determine the average frequency of the beat note by counting the rectangular waves. The first counter operates the altitude indicator. This circuit, Fig. 6, consists of a double diode. One section of the diode passes the positive half-cycles of the limiter output, charging a capacitor and load resistor in shunt. The resistance and capacitance values are so chosen that the charge on the capacitor leaks off through the resistor at a rate approximating the conduction of charge through the diode. Hence when the positive rectangular waves arrive at a more rapid rate (higher beat note), the direct voltage across the capacitor tends to increase, and vice versa. This voltage is passed through a low-pass *RC* filter which averages the direct voltage and applies it to the grid of the output amplifier tube. A milliammeter in the cathode of the latter tube registers, over a range of 5 milliamperes, the average value of the direct voltage on the grid. This meter is calibrated directly in feet, 0 to 400 and 400 to 4,000. The scale shown is switched synchronously with the switch which controls the total deviation of the transmitted signal, so it is not possible to misread the scale.

A part of the voltage across the cathode resistance is fed back to the other section of the diode in the counter circuit. This diode passes the negative halves of the limiter output to ground, and this discharges the coupling capacitor, leaving it ready to receive the ensuing positive half. The feedback from the output amplifier biases the diode and improves the linearity of the indication.

A similar counter circuit is employed to actuate the limit relays. In this case, however, the polarity of the diodes is reversed, and a negative voltage is developed across the load. The amplitude of this voltage is substantially proportional to the frequency of the limiter output and hence to the altitude.

The counter voltage is passed to



FIG. 7—Circuit diagram of the APN-1 altimeter (details of limit switch and range switch omitted)

the grid of a self-biased pentode stage. Relays in the plate circuit of this tube are actuated when the plate current exceeds certain limits. These limits are set by the operator, who adjusts a potentiometer which applies bias to the amplifier stage. This potentiometer is marked in feet and is set at the altitude at which it is desired to fly. The relays remain in their normal positions if the plane remains within 10 feet of the selected altitude. If the altitude deviates further than this, the counter circuit depresses or elevates the bias by an amount sufficient to operate the corresponding relay. Three lamps are controlled by these relays. One, white in color, lights when the relays are in normal position (altitude within 10 feet of the preset value). A red lamp lights when the altitude falls below the lower limit, and a green lamp when the altitude exceeds the upper limit. Corresponding voltage impulses are available to control the automatic pilot so as to correct altitude changes.

Physical Appearance

Three indicating units appear on the instrument panel of the aircraft, or at some other convenient point in the pilot's compartment. They are the altitude limit control, the indicating lamps, and the indicator dial. The on-off switch and range switch are provided directly on the face of the indicator. The total weight of the equipment is about 25 pounds, installed, and it consumes about 2.5 amperes at 27.5 volts d-c.

The accuracy is better than plus or minus five percent of the indicated altitude above terrain, plus or minus the six-foot uncertainty previously mentioned. On the high range, the fixed error is plus or minus 60 feet.

The two dipole antennas are installed so that the direct transfer of energy from one to the other is minimized. Usually the antennas are placed under the wings on either side of the metal fuselage. The antenna pattern, when the reflecting surface of the aircraft is taken into account, is a broad cardioid which illuminates the terrain below over a wide area. The f-m altimeter cannot be relied upon to detect obstacles dead ahead, although it will indicate rising ground and thus give advance warning of high ground ahead.

The power supply includes a dynamotor for plate and screen voltages, regulated by a gaseous regulator (type VR 150-30). The filaments of the tubes are connected in series parallel across the 27-volt supply. The complete circuit of the APN-1 altimeter is given in Fig. 7.

A model of the APN-1 has been approved by the Civil Aeronautics Authority for use in commercial aircraft. This equipment incorporates an automatic frequency response control in the audio amplifier. At low altitudes when no high frequencies are present except those due to noise, it is advantageous to reduce the high-frequency gain. Conversely, at high altitudes, high-frequency gain is required to amplify the weak beat note.

The editors wish to express thanks to Russell Newhouse of the Bell Telephone Laboratories and H. J. Markley of the RCA Service Company, for information on which this article is based.—D.G.F.

References

(1) Aircraft Radio, 1939, ELECTRONICS, Jan. 1939, p. 10.

(2) Matsuo, Sadahiro, a Direct Reading Radio-Wave-Reflecting-Type Absolute Altimeter for Aeronautics, *Proc. IRE*, p. 848, July 1938.

High Speed Oscillograph

Oscillograph for transient measurements has rapid writing speeds, in excess of 50 centimeters per microsecond. Simultaneous viewing of cathode-ray tube screen by recording camera and operator facilitates positioning and focusing the trace between measurements

By N. ROHATS

General Engineering and Consulting Lab.
General Electric Company
Schenectady, N. Y.

HIGH WRITING SPEED oscillography capable of recording transient voltage or current wave shapes has become an indispensable tool of high-voltage engineering. That section of high-voltage engineering which deals with the behavior of circuits or apparatus under transient conditions requires laboratory equipment capable of producing and recording surge voltages and currents measured in kilovolts and kiloamperes, with time scales measured in microseconds. The transients to be studied are generally produced by the discharge of a number of capacitors in series and the recording is done by some form of cathode-ray oscillograph.

Oscillograph Features

Based on experience gained in operating several types of oscillographs in which the film was inserted in the vacuum chamber of the cold cathode, cathode-ray tube and the compartment vacuum pumped after each loading, an oscillograph was designed around a hot cathode, sealed off, cathode-ray tube (see Kuehni, H. P. and Ramo, Simon, A New High Speed Cathode Ray Oscillograph, *Electrical Engineering*, June 1937, p. 721, disc. 1401). Changes were made in this oscillograph as experience and special requirements suggested.

The features of the resulting oscillograph suit it to rapid recording of high-speed transients. The single, sealed off, cathode-ray tube eliminates delays of releasing and repumping the vacuum and the problems associated with the pumps. A small camera for photographically recording the transients portrayed on the screen and giving records about 20 to 25 percent of screen size is mounted in front of the tube. New rolls of film can be quickly inserted.

Other oscillographs have been built containing two or three cathode-ray tubes with rotating or moving film cameras, and with cameras taking full-size pictures. Optical systems can be designed to have separate cameras for the multi-tube types or, by means of mirrors, three tubes may be covered by one camera.

The cathode-ray tube is mounted horizontally in a magnetic shield



Cabinet houses magnetically shielded cathode-ray tube, sweep generator, and high-voltage power supply. Voltage regulator at bottom prevents interference from power line fluctuation. Operator can view screen during tests from a standing or sitting position



FIG. 1—Sweep generator can either trigger or be triggered by transient under observation

near the top at a level most convenient for visual observation. The camera holder has two eyepieces, one above the camera for observation from a standing position, and one below for operation from a sitting position. Image focusing and continuous visual checking of performance can thus be made without delay or interruption. The size of the steel cabinet, two feet square and five and a third feet high, permits building a desk or table around it for more convenient operation. Power and deflection terminals are on the right side. A door at the back gives easy access to all parts.

At the top right is the timing wave oscillator, giving frequencies of 10, 50, 500, and 5,000 kc at several hundred volts. At the upper left is the d-c, deflection calibration circuit having a single-wave rectifier and a range of 0–1,000 volts. Below the cathode-ray tube are the sweep and beam control circuits shown in Fig. 1. Rectifier and bias arrangements have been omitted for simplicity. The balanced, thyratron-operated time axis generator gives sweeps ranging from one to 2000 microseconds duration. In the bottom is the 15-kv voltage doubler cathode d-c supply, a resistance divider for obtaining potentials for other tube elements, and a constant voltage transformer to insure accuracy despite fluctuating line voltage.

Figure 2 shows a series of oscillograms taken for plotting the volt-time breakdown curve of a 20-inch rod gap. Time axis and deflection calibrations are also given. This figure illustrates the sort of surge test records which can be obtained. The oscillograms were taken about as fast as the surge generator adjustments were made. The fastest writing speed shown in these records is some 20 centimeters per microsecond. For inclusion in reports these records can be enlarged to suitable size. For tabulating test data and measuring voltage and time values it is most convenient to project the negatives on ruled graph paper.

Oscillograms

Figure 3 shows a record of the flashover of a transformer bushing on the front of the wave. The oscillation after breakdown required a writing speed of about 50 centimeters per microsecond. However, this writing speed is by no means the available maximum. This record was taken with a one to one $f/3$ lens and those in Fig. 2 with an $f/2$ lens. In the course of our laboratory work, writing speeds of several meters per microsecond have been required and easily obtained with an $f/1.5$ lens. Such performance is not unusual and does not require additional skill on the part of the operator.

Sweep Tripping

In the above application the tripping of the surge generator was controlled by the sweep circuit of the oscillograph. Another problem frequently encountered is that of recording a surge whose time of occurrence cannot be controlled. The same sweep circuit used for surge generator work may be used in this connection because it can be tripped and the beam established on the screen with a loss of only 0.2 to 0.3 microseconds. This tripping may be repeated as often as sixty times a second if repeated surges are required. In most cases the loss of 0.2 microsecond is unimportant. Where necessary, this loss can be regained by connecting a delay cable between the surge point and the deflection plates.

The repeating characteristic of the sweep circuit makes possible studies



FIG. 2—Series of test oscillograms

of such varied phenomenon as high-frequency vibrations, lightning or switching surges, and ignition circuit transients. In the latter case the deflection plates may be connected to one spark plug and every spark wave shape observed on the screen. Then the effect of various operating conditions can be quickly determined. Records are taken either by snapshot exposure of the stationary film camera or by using a moving film camera.

An application which has lately become important is the measurement of short time intervals either on a single or repeating basis. A deflection voltage of 100 volts is ample for indicating a point along the time axis, and therefore microsecond intervals between phenomenon in one or more circuits can be conveniently measured.

Typical Application

In Fig. 1 is a diagram of the oscillograph as used with a surge generator. The operation is as follows: pushing the button fires the positive sweep thyratron T_1, raising its cathode from about −1500 volts to +3000 volts. This change of voltage has four functions: (1) it immediately trips the negative sweep tube T_2 through coupling capacitor C_1; (2) it provides half the sweep voltage by charging C_2 through R_1, the other negative half being provided by C_2 charging through R_2; (3) it establishes the cathode-ray beam by reducing the negative bias on the cathode-ray tube control grid through the circuit C_4, R_3, R_4; (4) it fires the time-delay thyratron T_3 at some time later depending on resistance R_5 and capacitance C_5.

The firing of thyratron T_3 immediately causes the large thyratron T_4 to fire, thereby tripping the small surge generator. The small surge generator has an output of about 70 kv which is enough for tripping the control gap of the main surge generator. The complete tripping is accomplished with such precision that no variation is visually noticeable in the position of the surge on the screen even on the one-microsecond sweep. For such precision the gaps of both the tripping and the main generator have to be preionized either with ultraviolet light or with corona.

With the sweep already established and in motion, the surge is applied to the vertical plates where it can be observed and simultaneously recorded photographically. Several hundred such records may easily be obtained in an eight-hour day, assuming normal time to prepare each test point.



FIG. 3—Record of high-voltage transformer flashover

Grounded-Grid Power

Radio-frequency power amplifiers using grounded-grid circuits operate at higher frequencies and can handle wider bandwidths than capacitance-neutralized grounded-cathode circuits. These advantages suit the grounded-grid circuit to television, f-m, and industrial uses

By E. E. SPITZER

Engineering Department, RCA Victor Division
Radio Corporation of America
Lancaster, Pa.

POWER AMPLIFICATION at high frequencies has always been a difficult technical problem. As the frequency is increased, the problems become more difficult. A number of these problems can be alleviated by a novel circuit which, undoubtedly, is destined to be used widely in the high-frequency field. This circuit is often called the grounded-grid circuit, and while it is not new it has not until recently received the attention it deserves. The purpose of this article is to call attention to this circuit, point out its advantages and characteristics, and show how such a circuit is designed.

There are three practical ways of utilizing a triode as an amplifier. The most common way is to apply the input signal between grid and filament terminals and take output from plate and filament. A second way is to apply input to grid and plate and take output from filament and plate. This type of amplifier is known as a cathode follower. The third way is to apply input to grid and filament and take output from plate and grid. There is no generally accepted name for this type of amplifier. It has been variously called grounded-grid amplifier, inverted amplifier, and common grid circuit because the grid is common to the input and output circuits. According to this terminology, the normal amplifier would be called a common cathode circuit, and the cathode follower would be a common plate circuit. In this article, the designation grounded-grid will be employed since it has been used fairly widely.



FIG. 1—Circuit and parameters of grounded-grid r-f power amplifier

Problems of Tube Design

Consider a normal triode circuit with input applied between grid and filament and a tuned output circuit between plate and filament. The filament is grounded. It is well known that such an amplifier will oscillate by itself at some undesired frequency because of feedback through the grid-plate capacitance of the tube. The cure for this difficulty is neutralization. However, as the frequency is increased, neutralization becomes increasingly difficult to handle. Because feedback is caused by capacitance between grid and plate and because any external neutralizing circuit is isolated from the internal capacitance by the inductances of grid and plate leads, the frequency band over which the tube can be neutralized becomes narrower and narrower with increasing frequency and finally vanishes altogether. Another undesirable effect is that capacitance neutralization serves to increase the input and output capacitances of the amplifier. For example a push-pull cross-neutralized amplifier has an output capacitance per tube equal to the plate-filament capacitance of the tube plus twice the grid-plate capacitance. This resultant high capacitance narrows the r-f bandwidth that can be handled or it may reduce the efficiency of the amplifier because of excessive circulating kilovoltamperes.

Tetrodes and pentodes were developed to overcome the foregoing

Amplifiers



FIG. 2—Cut-away view showing method of extending grid cylinder to complete the shielding between filament and plate circuits in a triode especially designed for grounded-grid circuits

difficulties. In these types of tubes, the screen and suppressor shield the control grid from the plate so that the feedback capacitance is low enough to make neutralization unnecessary. However, as the frequency is increased, self-oscillation may occur if the screen and suppressor leads have appreciable inductance. Then, these grids cannot be held effectively at r-f ground potential and, as a result, feed-through may occur. Twin tubes such as the RCA-829B were designed to overcome this difficulty. In a twin tube designed for push-pull operation, screen grids and cathodes can be intimately connected within the tube so that practically no inductance is present between these electrodes. Tubes of this design give excellent performance. The only difficulty is that tube cost for a twin-pentode tends to be high compared to the cost of triodes or triodes for equivalent power output capability.

Circuit Characteristics

The grounded-grid circuit is a way of using a triode which reduces the possibility of self-oscillation without the need for neutralization. Figure 1 shows a grounded-grid amplifier circuit, in which the control grid acts as shield between plate and cathode to reduce feedback capacitance C_{rr}. Thus, the control grid performs one function of a screen grid in a tetrode.

A second characteristic of the grounded-grid circuit is that the driver tube and output tube act in series to supply the load. In Fig. 1, the driver produces an r-f voltage E_g across the input terminals of the output tube. The latter has an r-f voltage E_p across its plate and cathode. These voltages are 180 degrees out of phase with respect to the cathode so that the r-f voltage from plate to grid and also across the output circuit is $E_p + E_g$. If I_p is the fundamental component of plate current 180 degrees out of phase with E_p, and I_g is the fundamental component of grid current in phase with E_g, the following relations then hold

Power delivered to load circuit = $(E_p + E_g)I_p$

Power delivered by output tube = E_pI_p

Driver power transferred to load circuit = E_gI_p

Power delivered by driver circuit = $E_g(I_p + I_g)$

Power absorbed by output tube = E_gI_g

It is apparent from these relationships that driver tube and output tube act in series to supply the load circuit. Power output, therefore, is higher than would be expected and the conventional efficiency, based on the input to the output tube, is unusually high.

The foregoing discussion brings out a third characteristic. The driving power of a grounded-grid amplifier is higher than when the same tube is used in a normal triode circuit and may be three to ten times greater. However, this increased power is not lost; it is merely transferred to the plate circuit and appears as output, as explained above.

Tubes for Grounded-Grid Circuits

A fourth characteristic is lower output capacitance. In a grounded-grid circuit, output capacitance is approximately C_{gp}, whereas in a normal capacitance-neutralized amplifier the output capacitance is more than twice this value. This fact is most important at high frequencies because lower output capacitance re-

sults in increased r-f bandwidth-handling capabilities and in lower circulating kva in the output circuits.

All of the foregoing characteristics are advantageous with the exception of the increased driving power. The latter is a disadvantage because it may require more or bigger amplifier stages in the transmitter design. Because a pentode or beam tetrode does not have this disadvantage, the field of application of grounded-grid amplifiers is at frequencies at which pentodes are not available for the desired power, or where the cost of pentodes is greater than the cost of additional driving stages required by the grounded-grid circuit. Present indications are that the frequency and power boundaries are about as follows

Power in Kw	*Frequency in Mc*
0.1	300
25	30
100	10

For the stated power, the grounded-grid circuit becomes desirable at a frequency above that listed.

Most of the characteristics which make a triode desirable in a normal circuit also make it desirable in a grounded-grid circuit. However, there are some additional requirements for a good grounded-grid tube. It has been stated above that the grid and its associated external ground plane should act as a screen between anode and cathode and their respective circuits. Therefore, the tube should be so designed that the anode and cathode connections are on opposite sides of the grid connection. For example, a tube which has an external anode with the grid terminal insulated from one end and the filament terminal insulated from the other end is not at all suited for grounded-grid operation. On the other hand, a tube such as the 9C21 illustrated in Fig. 2 is ideally suited for grounded-grid operation because the grid terminal is a large metal flange which can be connected to a metal shield separating the anode circuit from the cathode circuit. In addition, the grid support of the 9C21 has very low inductance and, therefore, meets the second requirement for a good grounded-grid triode.

Let it be required to design a grounded-grid stage utilizing one 9C21 triode. The tube will be used in the circuit shown in Fig. 1. The manufacturer's data show the following typical operating conditions for normal grounded-cathode circuits

D-c plate voltage = 17,000 v
D-c grid voltage = −1,600 v
Peak r-f grid voltage = 2,200 v
D-c plate current = 7.9 amp
D-c grid current = 0.9 amp
Driving power = 1,800 w
Power output = 100 kw

Amplifier Design

It is first necessary to obtain the r-f plate voltage swing E_p. This can be estimated from the fact that in a properly excited class-C amplifier, the plate voltage will swing down to the value of the peak positive grid voltage. Because the value of the latter is equal to 2,200 minus 1,600 volts, or 600 volts, E_p is $2^{-\frac{1}{2}}(17{,}000-600) = 11{,}600$ volts rms.

Next, the fundamental components of plate current and of grid current must be obtained using the power output and driving power values given above

$$I_p = \frac{100{,}000}{11{,}600} = 8.63 \text{ amperes}$$

and

$$I_g = \frac{1{,}800\sqrt{2}}{2{,}200} = 1.16 \text{ amp.}$$

The output power and the driving power can now be calculated from the relations given earlier. We obtain



FIG. 3—Rearrangement of circuit of Fig. 1 shows that the grounded-grid amplifier is similar to the Colpitts oscillator

$$\text{Power output} = (E_p + E_g)\, I_p$$

$$= \left(11{,}600 + \frac{2200}{\sqrt{2}}\right) 8.63 = 113 \text{ kw.}$$

$$\text{Driving power} = E_g(I_p + I_g)$$

$$= \frac{2200}{\sqrt{2}}(8.63 + 1.16) = 15.2 \text{ kw.}$$

It is possible to change the power output to some extent by varying the grid bias and the grid swing. For example, if the bias should be changed from −1,600 to −2,000 volts and the grid swing by a like amount, i.e., to 2,600 volts, the power output would be 116 kilowatts.

A grounded-grid amplifier stage can go into self-oscillation, particularly at high frequencies, because of feedback from plate to cathode through the plate-filament capacitance. This action is more easily understood if the amplifier stage is redrawn as a Colpitts oscillator circuit, as shown in Fig. 3. Because we are dealing with the worst conditions, inductive tuning only is assumed. The output circuit must be inductive at the oscillation frequency, as the following analysis proves.

Conditions for Oscillation

It is well known that circuit reactance between filament and grid must be capacitative and, furthermore, should be at least one-fifth the reactance between plate and filament. This reactance will produce an excitation ratio, that is, a ratio of plate swing to grid swing, of five. In any good grounded-grid tube, the plate-filament capacitance will be so low that its ratio to the grid-filament capacitance will be much less than one-fifth. Thus, to produce oscillation, the input circuit must be inductive so as to reduce the effective capacitance between grid and filament to a value about five times that of the plate-filament capacitance. With tuned input circuits, this condition can easily be fulfilled. Let it be assumed that this condition is exactly fulfilled.

The total tank circuit capacitance is then

$$C_T = C_{PF} + \frac{5\, C_{GP}\, C_{PF}}{C_{GP} + 5\, C_{PF}}$$

In the case of 9C21, this capacitance would be

$$C_T = 1.8 + \frac{48 \times 5 \times 1.8}{48 + 5 \times 1.8} = 9.4\ \mu\mu\text{f}$$

Thus for this 100-kw tube, the tank capacitance for parasitic oscillation is only 9.4 $\mu\mu$f, a value which is quite small. This capacitance will



FIG. 4—Plate modulation characteristic of grounded-grid r-f amplifier



FIG. 5—Class-B power amplification characteristic of grounded-grid circuit

store only appreciable amounts of power at high frequencies. Assume operation at a frequency of 20 mc. The reactance of C_T is then 850 ohms. If the tube is operated at 12 kilovolts with a plate swing of 11.6 kilovolts, the reactive power is $(11{,}600/2)^2/850 = 80$ kilovoltamperes.

We also know that oscillator stability necessitates an operating Q of at least 12. Therefore, in the above case, the circuit could be loaded to 6.7 kw. If all the circuit losses, including driving power and any power delivered to the load, are less than 6.7 kw, the tube will oscillate with certain adjustments of the input and output circuits. If we assume that the normal output circuit loss is five percent of 100 kw, or 5 kw, this value plus the driving power and the normal load coupled to the tube would be sufficient to make the amplifier stable at the assumed frequency.

Modulation Characteristics

When plate modulation of only a grounded-grid amplifier stage is attempted, a characteristic such as illustrated in Fig. 4 is obtained. It will first be noted that grid current varies widely with plate voltage. As the plate voltage increases, the plate current also increases and causes an increasing load on the driver stage. Due to the regulation of the latter, driving voltage decreases and with it grid current. This decrease of grid current is quite large and is characteristic of this type of amplifier.

Over quite a range of plate voltage, the output current is linear with plate voltage as in the case of conventional class C amplifiers. However, at low voltages load current departs from linearity and will not be zero until negative values of plate voltage are reached. This phenomenon is due to the fact that r-f driving voltage and d-c plate supply voltage are in series as shown in Fig. 1. As a result the plate not only has a d-c supply voltage but also simultaneously an r-f supply voltage. Therefore, the plate current and the load current do not drop to zero until a value of negative plate voltage equal to the value of the peak driving voltage is reached. Accordingly, the resultant characteristic of modulating only a grounded-grid stage shows distortion unless one is satisfied with partial modulation. To obtain a modulation characteristic which will permit 100-percent modulation, it would be necessary to modulate simultaneously one or more successive stages.

The above problem is of little practical consequence because amplitude modulation is rarely used at the high frequencies for which the grounded-grid circuit is particularly applicable. The problem does not exist for such services as frequency-modulation, television and industrial power.

When a grounded-grid amplifier is used as a linear, class-B r-f amplifier, quite satisfactory results are obtained, as shown in Fig. 5. Such an amplifier could be used to amplify television signals.

Bibliography

(1) Alexanderson, E. F. W., U. S. Patent 1,896,534, filed May 13, 1927, granted Feb. 7, 1933.

(2) Spitzer, E. E., "Grounded-Grid Operation of Triodes as Class B and C Amplifiers", an unpublished report dated Dec. 22, 1930.

(3) Lindenblad, N. E., U. S. Patent 2,136,448, filed Apr. 14, 1932, granted Nov. 15, 1938.

(4) Romander, H., "The Inverted Ultraudion Amplifier" *Q.S.T.*, p 14, Sept. 1933.

(5) Potter, R. K., U. S. Patent 2,088,722, filed June 12, 1936, granted Aug. 3, 1937.

(6) Strong, C. E., The Inverted Amplifier, ELECTRONICS, p 14, July 1940.

(7) Labin, E., Design of the Output Stage of a High Power Television Transmitter, *Electrical Communication*, 20, No. 3, p 193, 1942.

(8) Gurewitsch, A. M., Cavity Oscillator Circuits, ELECTRONICS, p 135, Feb. 1946.

Radium-Type Vacuum

Gas molecules are ionized by alpha particles from a pellet of radium, in linear relation to gas pressure, and the resulting ion current is collected and measured with a special high-gain d-c amplifier using an acorn tube and having up to 10^{12} ohms input resistance



Alphatron radium-type vacuum gage in use on an industrial high-vacuum furnace, registering a gas pressure of 6 mm during pumpdown. The polished metal cylinder attached to the pipe at the right contains the ionization chamber (upper section) and the probe amplifier stage

PRESSURE measurements in the interval between one micron and ten millimeters are required in a number of industrial processes, some of which are indicated on the chart in Fig. 1. The chart also portrays the intervals covered by conventional gages[1] in comparison with the range of a radium-source ion gage described in this article. By utilizing the ionization effect of emanations from a small, permanent radium source, this gage gives indications of gas pressures accurately, directly, and continuously in the in-between range covered only by the unwieldy and fragile McLeod gages.

Since the ionization effect is produced by the constant flow of alpha particles from a sealed radium source, there is no filament to burn out and no filament current to set and maintain. Furthermore, the gage cannot be damaged by exposure to atmospheric pressure. It is ruggedly constructed of all-metal parts not subject to breakage. There is no degassing to be done when the gage is turned on, and the absence of mercury vapor eliminates one of the common contaminators of vacuum systems.

The use of the ionization effect in the high-pressure range avoids the lag in readings common to gages utilizing the principle of thermal radiation and gives instantaneous response to pressure changes. Within the three standard ranges no complicated calibration curves are required for different gases, there being a linear reaction to pressure. Gases other than air can be measured merely by applying a multiplying factor to meter readings.

Since air and water vapor give so nearly equal ionization currents, the instrument is ideal for all vacuum applications involving mixtures of these two gases, as in dehydration equipment. If the gage is set to read total pressure of a 50-50 mixture of air and water vapor, it will be accurate within approximately 7.5 percent for all mixture ratios.

At pressures above about 25 mm the recombination of ions produced in the chamber becomes appreciable and linearity is lost, although the gage may be calibrated for pressures up to and beyond atmospheric, as shown in Fig. 2.

Throughout its linear range, when used with the amplifier to be described, the gage measures pressures with three scales of sensitivities: 0-100 microns, 0-1 millimeter, and 0-10 millimeters. Normally the combination of gage and amplifier is calibrated for air pressures, while other gas pressures are determined by the use of conversion factors; however, the scales may be set to read directly for other atmospheres where this is desired. Figure 3 shows the relative response for the ordinary gases encountered. It will be seen that the high relative response to acetone vapor lends itself admirably to the acetone technique of leak detection on kinetic vacuum systems.

Theory of Operation

Alpha particles emitted by a radium source collide with gas molecules in the ion chamber, producing approximately 33 ion pairs per cm of path length per mm air pressure, per alpha particle.[2, 3] By the action of an electric field strong enough to effect saturation currents, these ions

Gage

By GLENN L. MELLEN
Physics Department
National Research Corp.
Boston, Mass.



FIG. 1—Pressure ranges of vacuum gages and processes. Solid lines indicate definite regions of operation, while dash-dash lines represent regions that are questionable or to which special gages may extend

are collected at a rate dependent upon their production, and thus constitute a minute current whose magnitude is a linear function of pressure. Since the alpha activity of a radium source in equilibrium with its immediate decay products is constant for all practical purposes, it only becomes necessary to measure these currents in order to evaluate pressures.

Some 10^7 alpha particles per second are ejected into the ion chamber from the 200-microgram radium source used. With a mean path length of 5.5 cm in the ion chamber, it is predictable that approximately 2×10^{-10} amp of ionization current is to be realized per millimeter of air pressure. Since the recombination of ions is a function of collection field strength and molecular mean free path, an increasing fraction of the ions produced will be lost in this manner and at some high pressure the deviation from linearity will become detectable for any one set of gage conditions. This point is at 25 mm, for the present design, and no further increase is necessary here for this is well within the operating region of simpler pressure gages.

D-C Amplifier Circuit

The essential features of the radium-type vacuum gage are illustrated in Fig. 4, and include the following: (1) the vacuum chamber, a brass shell with suitable vacuum-tight insulators and provision for making connection to a vacuum system; (2) the radium source, containing approximately 200 micrograms of radium, sealed to prevent radon loss, and in equilibrium with its immediate decay products; (3) ion collector electrodes, with a plate electrode being used to produce an electric field for ion collection, and a grid essentially at ground potential to minimize the effect of electrical leakage across the input insulator; (4) a suitable means of measuring



FIG. 2—Calibration curves for extended range of radium-type vacuum gage, indicating possibility of measuring air pressures well over atmospheric if operator knows whether he is above or below the 175-mm peak of the calibration curve. Range setting IV on the instrument is used for these higher-pressure measurements. A separate calibration curve must be prepared for each gas, using a McLeod or bellows gage as a standard



FIG. 3—Calibration curves showing linear performance of gage over its three normal ranges. For scale I, multiply abscissa values by 10; for scale III, multiply abscissa values by 100 and read as microns of mercury. Values on curves give relative response

the minute ion current produced.

The high-gain d-c amplifier devised by Shepard Roberts[4] lends itself admirably to the job at hand. The basic circuit is given in Fig. 5. Once the cathode bias (E_c) has been adjusted with no input current I_I so that the battery voltage is equaled by the cathode resistor drop E_2 in the second stage, there will be no output current I_o indicated by the meter. Now, if a minute input current I_I flows through R_I a signal voltage E_I is developed. This signal voltage is opposed by the output voltage E_o, so that the net change of bias on VT_1 is $\Delta E_g = E_I - E_o$. If μ is the overall gain of the circuit, $\mu \Delta E_g = E_o = \mu(E_I - E_o)$. From this, $E_I = E_o(1 + 1/\mu)$.



FIG. 4—Cross-section of ion chamber, showing location of radioactive source and collector electrodes

If the gain μ be made large, the factor $1/\mu$ may be neglected without sensibly affecting the relationship. Then $E_I = E_o$, or $I_I R_I = I_o R_o$. Rearranging gives $I_I = I_o R_o / R_I$; in other words, the calibration (current amplification) is a matter of resistor ratios only and is independent of widely changing tube characteristics so long as the gain remains high. At the same time the potential of the input grid with respect to ground is changed only by E_I/μ, thus minimizing the effect of electrical leakage across any insulator in the input circuit.

If a 200-microampere meter is used to indicate I_o, it is possible with resistor ratios of 10^7 to measure 2×10^{-11} ampere at full-scale deflections. This is the order of ion currents realized from the gage at 100 microns of air pressure.

Experimental and Production Models

Originally the Roberts circuit was tried with a 6C6-6K5 tube lineup and found satisfactory for gage operation at 0-1 mm and 0-10 mm sensitivities. In this version a single 1,000-megohm input resistor was used in conjunction with switchable 1,000 and 10,000-ohm output resistors. The amplifier then operated on 0.2 and 2.0 volts of signal.

To obtain a third scale by using a 100,000-ohm output resistor would require 20 signal volts on the same basis and since the battery is only 22½ volts, this means of attaining an additional range is not satisfactory.

By the same token one cannot go in the other direction to operate on a 0.02-volt signal. For a 0.2-volt signal and a μ of 100, we obtain $\Delta E_g = E_I/\mu = 0.2/100 = 2$ millivolts for full-scale deflection. Hence for one-percent scale deflection only 20 microvolts of ΔE_g are required. This was found by experience to be the lower limit that gave stable operation, free from zero-setting drift and sporadic fluctuation. Even though the zero setting may drift, the current amplification is unaffected, and I_I is determined by simply resetting and then reading. Zero is reset by disconnecting the input and adjusting E_c for zero I_o.

No attempt was made to measure the inherent grid current of the 6C6 first stage since it was possible to use the amplifier after adjusting the value of heater voltage to approximate the circuit values given in Roberts' article. By using a value of 2×10^{11} ohms for R_1, the amplifier was pressed to its limit.

In the production model, the first stage of the amplifier was located at



FIG. 5—Basic d-c amplifier circuit

the end of a cable in a probe assembly, since it was considered inadvisable to attempt piping the minute ionization currents from the gage to the amplifier. The need for three ranges of sensitivity (0-100 microns; 0-1 mm; 0-10 mm) dictated that some means of switching the input resistors be provided so that the entire blind spot in the pressure spectrum could be adequately covered. This was first effected by a switch on the probe, but later a relay was added to make all operations remotely controlled.

Acorn Tubes Is Used

The production model uses a type 954 acorn tube in place of the 6C6. The simplicity of the amplifier depends upon realizing comparatively high voltage gain in the first stage. The second stage is degenerative about 3 to 1, and the overall gain must be kept up to negate the $1/\mu$ factor.

Acorns have been used before in electrometer circuits,[5] but the signal has always been applied to the suppressor grid to keep the inherent signal grid current low, and consequently the gain has been approximately unity. Conceivably, two additional stages (to get the proper feedback phase relationship) could be added to attain the required μ, but this becomes somewhat complicated because of the need for batteries between stages.

Screen Grid Voltage

It was discovered that the signal could be applied to the control grid on the 954 and still obtain a low inherent grid current with appreciable gain ($g_m = 90$) if a proper value of screen voltage were chosen. A family of curves is given in Fig. 6 showing



FIG. 6—Operating characteristics of tube

the relation between screen voltage and grid current at various values of heater voltage. At low values the grid current is due to electron collection, while at higher values positive ion collection predominates.

To measure these minute grid currents, the amplifier was adjusted to operate at full-scale deflection with 0.2 volt E_I, so that with a 10^{10}-ohm input resistor each microampere of output current represented 10^{-18} ampere of I_I. By adjusting E_c with a 10^8-ohm input resistor for zero I_o and then switching to 10^{10} ohms input, any deflection noted will be due to the grid current I_g developing a signal across this higher R_I, and I_g may be evaluated directly. For each value of heater voltage there is a value of screen voltage that will balance positive ion and electron collection, so that essentially zero grid current exists. This screen voltage is made adjustable to compensate for tube to tube variations, and is set by a searching method so that no deflection is noted when switching between 10^8 and 10^{10}-ohm input values.

Controlling Zero Drift

It is not beyond the realm of possibility to regulate the three variables —cathode bias voltage, screen grid voltage, and heater voltage—to such a degree that zero drift becomes negligible. On the basis of measurements, the arbitrary operating value of 3.7 volts a-c was chosen for the heater voltage. By operating the 954 under the above conditions it was possible to improve the amplifier characteristics over that experienced with the 6C6. At the same time the advantage of a smaller physical dimension was gained so that all the components necessary to complete remote control could be incorporated in a compact probe assembly. Furthermore, I_g was held low by only partially temperature-limiting the emission, and therefore the warm-up time was materially reduced. The 6C6 required operating at full 6.3 volts to start, with later reduction to operating values to run; otherwise, the amplifier would drift for hours before temperature equilibrium was established. With the 954, the amplifier on highest sensitivity is ready to operate after just one minute of warm-up and will drift only 5 percent of full scale to its final equilibrium in the next five minutes.

Two relays and two high-value resistors complete the major components of the probe assembly. The upper relay mechanism operates to disconnect and ground the ion current input to the tube grid so that the amplifier may be zero balanced. The lower relay serves to connect the low side of the 10^8-ohm resistor to the 10^{10}-ohm resistor, thus changing the value of R_I. This low end of the 10^8-ohm resistor must be held above ground by at least 10^{12} ohms when in the open position so that the 10^{10}-ohm resistor will not be appreciably changed in its value by shunting. Therefore, this end is left floating, with no supporting insulator.

Control Panel

A ten-wire cable connects this probe assembly to the control panel, as shown in Fig. 7. In this unit are located the power supply, controls, second stage, battery, and output meter. The four-inch meter is a 200-microampere movement with ap-



Rear view of chassis of control unit for gage, and closeup of 954 amplifier stage, located in probe head along with two glass-encased high-value resistors (98 and 10,820 megohms here), and two switching relays. This unit fits under the ionization chamber



FIG. 7—Circuit diagram of type 510 Alphatron radium-type vacuum gage

proximately 300 ohms impedance, calibrated 0-1 mm with one hundred divisions so that the instrument may be adjusted to read pressures directly. Since the battery drain under the worst conditions can only be 400 microamperes, the life in this application is practically shelf life. Regulated d-c power is supplied to the amplifier.

Sufficient control of the partially limited emission in the first stage is obtained by an ordinary current regulator tube. To accomplish this two filament windings are connected to give 11.3 volts a-c and this is fed to the 6-4B regulator. The regulator is then loaded with a ten-ohm resistor to provide the operating value of heater supply to the 954. In use, a properly operating regulator overcompensates slightly for changes in line voltages so that the net zero shift is only one to two percent on the highest-sensitivity scale, in a direction opposite to that of a line voltage change of ten volts.

Complete Circuit

The 6K5 second stage was retained unchanged with the exception of the addition of a 0.05-μf capacitor. This serves to remove the ghost flutter of the output meter needle on highest sensitivity. The complete circuit is given in Fig. 7.

Three controls and a pushbutton are provided on the front panel. A rotary power switch permits warm-up before operation and insures that the battery is disconnected in the off position. A pushbutton operates the ion disconnect relay in the probe so that the amplifier may be zero-adjusted by the control provided. Sensitivity ratios of 10 to 1 and 100 to 1 are obtainable with the final control on the front panel. When set to range I (10 mm full scale), this control operates the switching relay to connect a 10^8-ohm input resistor in the 954 grid and simultaneously selects a 3000-ohm adjustable R_o. On range II and III (1.0 and 0.1 mm full scale) the value of R_I is 10^{10} ohms, while 25,000-ohm and 3,000-ohm potentiometers respectively are used for R_o. These variables are necessary to allow for manufacturing tolerances in R_1 and in the radium sources. They are adjusted under operating conditions to read the gage ion current as air pressure directly.

TABLE 1. OPERATING VALUES

Switch Pos.	III	II	I	IV
Range in mm	0–0.1	0–1	0–10	.....
Mult Factor	× 0.1	× 1	× 10	.....
R_I	10^{10}	10^{10}	10^{8}	10^{8}
R_O	10^{3}	10^{4}	10^{5}	10^{6}
Current in amp	10^{7}	10^{8}	10^{9}	10^{4}
I_I full scale	2×10^{-11}	2×10^{-10}	2×10^{-9}	2×10^{-8}

In Table I are shown the approximate operating conditions for use with the present design ion chambers. The fourth range is not provided as such, but it is obtainable by using the R_o value for range II with a value of 10^8 ohms for R_I. A switch on the rear of the chassis operates the switching relay for this function, and is also used while adjusting for the proper value of screen grid voltage. Under these conditions the calibration approximates the curve in Fig. 2.

Another switch in the rear operates the disconnect relay, making it unnecessary to hold the zero-set pushbutton depressed during adjustment procedures. Finally, two more controls, a coarse zero adjustment and a screen grid voltage adjustment, complete this entirely flexible amplifier.

As an illustration of amplifier stability, a production model was picked at random, balanced for zero I_a, and calibrated with a gage for the three pressure ranges. This combination was used continuously under all pressure and line conditions for one month, during which time the net change in I_a was 2×10^{-12} ampere, or enough to give only one division of deflection between ranges. The maximum deviation was three divisions of deflection on highest sensitivity.

Applications

With this new and useful gage as a tool it has become possible to gain important knowledge in the field of industrial high vacuum. Applications include large-scale bulk dehydration, in one phase of which it has already become indispensable. New and interesting applications for this instrument or a modification thereof are being encountered each day, and it is felt that here is not only a pressure gage for a difficult pressure interval but also a fundamental tool to be used on the gas molecule.

References

(1) Strong, John, "Procedures in Experimental Physics," Prentice Hall Inc., New York, N. Y., 1944.

(2) Rutherford, E. R., Chadwick, James, and Ellis, C. D., "Radiations from Radioactive Substances," Cambridge Press, Cambridge, England, 1930.

(3) Crowthers, J. A., "Ions, Electrons, and Ionizing Radiations," Longmans Green & Co., New York, N. Y., 1929.

(4) Roberts, Shepard, A Feedback Micro-Microammeter, *Review of Scientific Instruments*, June 1939, p 181–183.

(5) Gabus, G. H., and Pool, M. L., A Portable Phototube Unit Using an RCA 954 Tube, *Review of Scientific Instruments*, June 1937, p 196.

TRANSIENT Delay Line

Design criteria for a pulse-delay network useful in radar, television, or test oscilloscope work. With highest frequency component of the transient known, a simple, graphical solution is possible for required values of inductance and capacitance

By JOHN M. LESTER

Engineer
Sperry Gyroscope Co., Inc.
Garden City, N. Y.



FIG. 1—Phase-shift characteristics for one section are shown by the solid lines. The dashed lines show how the slopes vary as the cutoff frequency is approached, expressed in terms of $T\omega_c$.

WHEN designing special electronic equipment, it is often necessary to provide some method of delaying or storing electrical information for a given length of time. If this memory time is in the order of microseconds, an electrical network with special characteristics can be designed and constructed quite easily. Except for a small amount of attenuation, the signals applied to the network input will be faithfully reproduced at the output after the required time has elapsed.

Effect of *m* on Phase Shift

By choosing the correct value of m in an m-derived low-pass filter, it is possible to obtain a phase-shift characteristic that is fairly linear with frequency for almost the entire pass band. If a transient signal is passed through this filter, it will be delayed in time by an amount equal to $\beta/2\pi f$ where β is the phase shift in radians at a frequency f. No phase distortion will occur if the phase characteristic of the filter is linear up to the highest frequency included in the transient signal. By placing sections of these filters in cascade any desired delay can be obtained.

The effect of m on the phase-shift characteristic of one section is shown by the solid-line curves in Fig. 1. β is plotted against ω/ω_c for various values of m. The broken-line curves in Fig. 1 show how the slopes of the solid-line curves vary with ω/ω_c. The ordinate is expressed in terms of $T\omega_c$. Because $\beta = \omega T$, this also equals $\beta/(\omega/\omega_c)$. We see that when m equals 1.4, the phase shift is fairly linear up to 95 percent of the cutoff frequency, and the average value for $T\omega_c$ can be taken from the curve as 2.73. $T\omega_c$ will never vary more than $\pm$ 2.93 percent from this value for frequencies below 95 percent of cutoff.

Figure 2A shows a T section of an m-derived low-pass filter. Substituting a value of 1.4 for m, we get

$$L'_1 = mL_k/2 = 0.7L_k \quad (1)$$

$$L'_2 = \frac{(1-m^2)}{4m} L_k = -L_k/5.6 \quad (2)$$

$$C' = mC_k = 1.4C_k \quad (3)$$

We can see that L'_2 is negative. This negative value of L'_2 can be obtained by using the network shown in Fig. 2B. The network with mutual inductances is equivalent to the net-



An experimental delay unit of nine sections. Characteristic impedance is 500 ohms. There is a total delay of 1.5 microseconds for a transient having a maximum frequency component of 2.5 mc. The unit is illustrated about twice normal size

work of 2C. Therefore

$$\left(\frac{1-m^2}{4m}\right)L_k = -M \quad (4)$$

$$mL_k/2 = L/2 + M \quad (5)$$

$$mC_k = C \quad (6)$$

Substituting Eq. 4 in Eq. 5 we get

$$L = mL_k + \left(\frac{1-m^2}{2m}\right)L_k = \left(\frac{m^2+1}{2m}\right)L_k \quad (7)$$

Letting $T\omega_c = 2.73$ which is the value we previously determined from Fig. 1, then

$$T = \frac{2.73}{\omega_c} \quad (8)$$

or $$f_c = \frac{2.73}{2\pi T} = \frac{0.435}{T} \quad (8a)$$

Cutoff Frequency

This derivation shows that T is inversely proportional to the cutoff frequency. Referring to Fig. 2C, the cutoff frequency of an m-derived filter is

$$f_c = \frac{1}{\pi\sqrt{(L+2M)\,C + 4C\,(-M)}}$$

Since k (coefficent of coupling) $= M/L$)

then $$f_c = \frac{1}{\pi\sqrt{(LC+2kL)\,C + 4\,C\,(-kL)}}$$

$$= \frac{1}{\pi\sqrt{(LC+2kL)\,C - 4kLC}}$$

$$= \frac{1}{\pi\sqrt{CL\,(1-2K)}} \quad (9)$$

or $$\omega_c = \frac{2}{\sqrt{CL\,(1-2k)}} \quad (9a)$$

Substituting Eq. 9a in Eq. 8, we get

$$T = 1.36\sqrt{CL\,(1-2k)} \text{ when } m = 1.4 \quad (10)$$

With the use of Eq. 10 the time delay of an m-derived filter, when $m = 1.4$, can be calculated.

Terminating the Filter

So that no reflections will occur, it is necessary to terminate the filter correctly. Assuming the filter consists of pure reactances, then the terminating resistance,

$$R_0 = \sqrt{L_k/C_k} \quad (11)$$

Substituting Eq. 6 and 7 in Eq. 11

$$R_0 = \sqrt{\frac{L\,\frac{(2m)}{(m^2+1)}}{C/m}} = \sqrt{\frac{L\,(2m^2)}{C\,(m^2+1)}} \quad (12)$$

Since $k = M/L$, then from Eq. 4 and 7

$$k = \frac{\frac{(m^2+1)}{(4m)}L_k}{\frac{(m_2+1)}{(2m)}L_k} = \frac{m^2-1}{2\,(m^2+1)} \quad (13)$$

or

$$2k\,(m^2+1) = m^2 - 1$$

$$2km^2 + 2k = m^2 - 1 \quad (14)$$

and

$$m^2 = \frac{1+2k}{1-2k} \quad (14a)$$

Substituting in Eq. 12, we get

$$R_0 = \sqrt{\frac{L\,(1+2k)}{C}} \quad (15)$$

Substituting the value of 1.4 for m in Eq. 14a, we see that $k = 1/6$.

The chart shown in Fig. 3 is based on Eq. 10 and 15 which, when reduced to their simplest form, are

$$T = 1.11\sqrt{LC} \quad (16)$$

$$R_0 = 1.15\sqrt{L/C} \quad (17)$$

when $m = 1.4$

Use of Chart

Knowing the delay time for one T section and the terminating resistance, the correct inductance and capacitance for the filter can be determined from the chart. As many sections as desired may be added in cascade to give any time delay desired. The total delay will be T times the number of sections.

It must be remembered that the chart is fairly accurate only if it is used for frequencies below 95 percent of cutoff.

Using Eq. 8, we see that

$$f_{max} = \frac{0.435 \times 0.95}{T} = \frac{0.41}{T} \quad (18)$$



FIG. 2—Development of a T section of an m-derived low-pass filter. (A) The value of L'_2 is shown to be negative and is obtained in practice by the circuit of (B). (C) demonstrates the derivation of the cutoff frequency

Suppose we have a transient signal which we want to delay one microsecond. We want the impedance of the network to be 1,000 ohms. Also, the highest frequency contained in the transient signal is one mc. What will be the constants of the network?

Example

Knowing f_{max}, we first determine the maximum delay T per section realizable.

$$f_{max} = \frac{0.41}{T} \text{ or } T = \frac{0.41}{1\times10^6} = 0.41\times10^{-6} \text{ sec}$$

The number of sections will be the total time divided by T, or $10^{-6}/(0.41 \times 10^{-6}) = 2.44$.

Therefore, three sections are the minimum to be used. With three sections we will have $(10^{-6}/3) = 0.33 \times 10^{-6}$ seconds delay per section. From the chart we can determine L and C. We see that $L = 260\mu h$ and $C = 340$ $\mu\mu f$. Therefore, the networks will have the constants shown in Fig. 4, when $k = 1/6$.

Design Considerations

The following are practical problems that must be taken into consideration when constructing a delay filter:

(1) Providing small attenuation.

(2) Obtaining the correct coefficient of coupling.

(3) Preventing reflections.

The attenuation of the network depends upon the Q of the capacitors and inductors. Usually the loss due to the capacitors is negligible and can be neglected. The attenuation for frequencies lower than 95 percent of cutoff is approximately equal to $\omega T/2Q_L$ nepers, where T is the delay time in seconds. Q_L can be increased in several different ways. The size of the wire used for winding inductors can be large. However, this will increase the physical size of the filter and hence increase stray capacitance between coils. If the frequencies involved are in the order of 100 kc to 4 mc, the use of litz wire will help to increase Q_L. Also, Q_L can be increased by using powdered-iron cores.

The coefficient of coupling can be controlled by varying the spacing between adjacent coils. The spacing should be adjusted so that the coefficient of coupling is equal to 0.16.

Unless the network is terminated in its characteristic impedance or a



FIG. 3—Chart used in determining the value of inductance and capacitance of the filter when time delay T and terminating resistance R_0 are known, accurate only when used for frequency below 90 percent of cutoff

close approximation to it, echoes or reflections will occur when transient signals are inserted. Usually when several sections are used in cascade, a sufficiently good termination will be obtained when both ends of the network are terminated with capacitors equal to $C/2$. However, if a more perfect termination is desired, a half-π section where $m = 0.6$ can be used.

It is good design practice to try to use a network as low in impedance as possible. This reduces the size of the inductors and hence reduces the stray capacitance between coils and permits an increase in the Q of the coil, in turn producing less phase distortion and less attenuation.



FIG. 4—Three T sections form a filter network to delay a transient signal 10 microseconds. Impedance of the network is 1,000 ohms and the highest frequency contained in the transient is 1 mc

Bibliography

(1) Guillemin, E. A., "Communication Networks," John Wiley & Sons, Inc., p 324.

(2) Starr, A. T., "Electric Circuits and Wave Filters," Pitman Publishing Corp., p 242.

(3) Pierce, G. W., "Electric Oscillations and Electric Waves," McGraw-Hill Book Co., p 321.

FOUR-CHANNEL



Top chassis view of the four-channel electronic switch, showing the ring-counter and gate-amplifier tubes at the right and the crystal-oscillator trigger circuit tubes near the front panel. The wide-band amplifier tubes are type 807

By N. A. MOERMAN
Potter Instrument Company, Flushing, N. Y.

THE cathode-ray oscilloscope has in recent years become an indispensable tool for the research worker and the engineer. The value of this equipment and, concurrently, the reason for its success can be attributed almost wholly to its inherent versatility, a factor that is being constantly enhanced by the development of auxiliary circuits and modified cathode-ray tube types.

One application of considerable importance in research work is multiple-channel cathode-ray oscilloscope recording which has become invaluable for the simultaneous study of several interrelated phenomena of transient character. The most satisfactory method that has been employed for this purpose up to the present time has been photographic recording of the traces of several cathode-ray tubes. The obvious disadvantage of this type of system, however, is the increase in complexity and bulk of the equipment as the number of recording channels is increased.

In an effort to circumvent or minimize this disadvantage, there have been two developments of interest, the multiple-beam cathode-ray tube and the electronic switch.

An electronic switch[1, 2, 3] is a device that enables simultaneous observation of two separate phenomena with the aid of the cathode-ray oscilloscope. This is accomplished by alternately connecting the respective circuits under study to the input of the cathode-ray oscilloscope by electronic means.

This device, as supplied commercially, is valuable for a number of specific applications, but has several disadvantages for general use:

(1) Only steady-state or recurrent phenomena can be observed since reliance is placed upon persistence of vision or still photography for proper interpretation.

(2) The frequencies of the waveforms under study must be related to each other by some integral multiple.

(3) Transient phenomena can neither be viewed nor recorded satisfactorily because of the low switching frequency normally employed and the use of capacitance-coupled amplifiers.

(4) The number of circuits that may be switched is normally limited to two, although by interconnecting several units this limitation can be overcome.

Requirements of a Four-Channel Recorder

The need for a four-channel recording system imposed a unique



FIG. 1—Block diagram and type of waveform for a standard electronic switch and the four-channel switch described in text. The ring counter circuit can be developed for n channels as indicated

ELECTRONIC SWITCH

An electronic switch permits display of four or more transients at once on a conventional cathode-ray oscilloscope screen. A crystal-controlled ring counter triggers the gate amplifiers which switch and mix signals supplied to a wide-band amplifier in the equipment

requirement on the design of an electronic switch, as indicated in Fig. 1. In a conventional two-channel electronic switch, a multivibrator supplies the required square-wave switching pulses which alternately bias to cut off the respective gate amplifiers. The common plate connection between these amplifiers provides the point at which the composite signal is applied to the oscilloscope. On the other hand, the n-channel electronic switch contains n generators which supply switching pulses consecutively to gate amplifiers 1 to n, this cycle of operation being continuously repeated. The duration of each switching pulse must obviously be $1/n$ times the period for each cycle of operation.



FIG. 2—Composite four-channel waveform on expanded time scale (above). Interval between pulses is 1/100,000 sec. Below are phase relations among the switching pulses of the four-channel switch, shown with a slower sweep frequency



FIG. 3—Oscilloscope traces resulting when three different signals were introduced through the four-channel switch. Top trace presents a 60-cps square wave and the bottom a 60-cps sine wave. No signal was applied to the second-trace input. A 600-cps sine wave of large amplitude superimposes the third trace upon the others. The spacing of the dots is controlled by the crystal oscillator and allows precise determination of the slope of waveforms

Ring Counter

The requirements for a switching pulse generator have been conveniently satisfied by the use of an electronic ring counter. By means of this system it becomes theoretically possible to devise an electronic switch for an infinite number of channels. Practical considerations have restricted our application to four channels.

An electronic ring counter may be defined as a series of square-wave generating circuits (of the Eccles-Jordan type[1]) so arranged that only one circuit of the series is in the on position at any instant. Trigger pulses applied simultaneously to all the circuits pass this condition consecutively to each square-wave generator, the cycle of operation continuing as long as the trigger pulses are applied.

The on position of a pulse-generating circuit is that state of the circuit from which a positive switching pulse is obtained. A succession of trigger pulses applied to the counter ring results in positive switching pulses being supplied consecutively by circuits 1 to n. This cycle of operation is continuously repeated. Since all gate amplifiers are normally biased beyond cutoff, the function of these positive switching pulses becomes that of turning on the respective gate amplifiers. Any one of the gate circuits is brought into the conducting state for a period of $1/n$ times the switching cycle and is off during the remaining part of the cycle.

The phase relations between the switching pulses for a four-channel electronic switch are shown in Fig. 1. The composite waveform is again derived from the common plate connection between gate amplifiers. Oscillograms of the actual waveforms obtained are reproduced in Fig. 2.

At this point it may appear that considerable resolution of the waveforms under study will be lost because of the relatively short period during which any channel is active. This would be of some concern if the switching rate were comparable to or less than the frequencies contained in the waveforms under study. This apparent difficulty is largely overcome by making the switching rate as high as possible. In the apparatus described a switching rate of 25,000 cycles is employed.

The degree of resolution actually obtained with the four-channel electronic switch is shown in Figs. 3, 4, and 5.

Design Criteria

The chassis contains all the essential elements for the operation of the four-channel electronic switch with the exception of power supplies and the necessary preamplifiers. These elements are (1) the trigger pulse source, (2) the switching-pulse generator (ring counter), (3) the gate amplifiers, and (4) the output amplifier. They are described in detail below.

For proper operation of the ring counter a source of trigger pulses of the proper frequency and shape is required. A pulse frequency of 100 kc which yields a switching



FIG. 4—A 60-cps square wave (top line) recorded with a revolving-drum type camera at a speed of 285 inches per sec (above) and 195 inches per sec (below)

rate of 25,000 cycles was chosen.

In the complete four-channel switch circuit in Fig. 6, one half of tube V_3 (6SN7) is connected with associated components to form a Pierce oscillator. The other half of V_2 serves as a square-wave amplifier.

Circuit Details

Differentiation of the 100-kc square waves is accomplished by the RC combination composed of R_4 and C_2. Of the positive and negative pulses resulting, only the positive pulses are amplified by tube V_1, which is biased to cutoff. Negative pulses appearing at the plate of V_1 have the desired characteristics noted above. These are applied to a common bus for injection into the ring-counter and gate-amplifier.

The switching-pulse generator (ring counter) is composed of four 6SN7 tubes connected in standard Eccles-Jordan square-wave circuits with the addition of inductance, L_1, in each plate circuit. The inductance is placed in that side of the circuit from which the positive switching pulse is derived. A considerable improvement in the squareness of the switching pulse results without adversely affecting normal operation of the circuits.

Square-wave Generator Circuit

An Eccles-Jordan circuit (sometimes called a flip-flop circuit) has two stable states such that for either state one grid is at cutoff and the other at zero, so that one tube is off while the other conducts. Of those grids in the ring counter that are connected to the source of trigger pulses only one grid is zero at any instant. This grid is associated with the circuit that is on. The trigger pulse operates on this grid and flops the circuit to its other stable



FIG. 5—Photographic recordings of signals fed to a commercial oscilloscope through the four-channel switch, only one channel of which is used here. A high degree of resolution is possible well above commercial power frequencies

state (off). During this transition the positive rise in voltage at the left-hand plate is applied through C_1 to the cutoff-biased grid of the succeeding circuit, which is then turned on. The next trigger pulse operates on this circuit, which is then flopped to the off position as in the case of the preceding circuit. In this way, a positive switching pulse is generated at the right-hand plate of each circuit during the sequence off-on-off.

It will be noted in the schematic diagram that pushbutton switch S_3 has been inserted between the two legs of the square-wave circuits, one of which is connected in reverse order. This provides a front-panel control for initiating the proper sequence of operation for the counting ring after applying power.

Switching the Pulses

The gate amplifiers serve the twofold purpose of switching and then mixing the signals applied to their respective inputs. For this function the type 6L7 tube was selected.

At the outset, it was felt that the inner control grid of the 6L7 would be the logical point for introducing the switching pulse since cathode current cutoff could then be assured. This arrangement was tried and found to be unworkable because of the distortion introduced by applying the useful signal to the second control grid. The functions of the two control grids were then reversed and a great improvement in the operation noted. The disadvantage to this mode of operation, however, is the incomplete cathode-current cutoff, requiring isolation of the screen-voltage supplies to insure minimum coupling.

Variable resistor R_1 in the cathode circuit provides a means for orienting the trace on the cathode-ray tube with respect to the other traces. When it is desired to observe less than the four available traces, switch S_2 is thrown. This introduces a large resistor (R_2) into the cathode circuit, which then deflects the respective trace off the screen.

For added flexibility, provisions are made for restoring normal single-trace operation. This may be desired where high-frequency recording and good resolution are required, and is made possible by operating switch S_1. This shunts the trigger pulses to ground through C_3 and removes the bias on the operating 6L7 tube by connecting its second control grid to cathode.

Wide-Band Amplifier

It was evident early in the development of the apparatus that amplification of the composite signal would present some difficulty. The problem involved is that of amplifying unidirectional square-wave pulses of approximately 75 volts amplitude. These pulses are modulated by as much as 25 per cent. Capacitance coupling could not be used because of the transient d-c amplification requirement. Furthermore, it was found to introduce interchannel coupling.

The output-amplifier circuit finally evolved is shown in the schematic diagram. Triode-connected 807 tubes in push-pull were selected because of their large signal-handling capabilities coupled with low distortion. An excessively large common cathode resistor (R_3) is employed which serves two im-

portant functions: The cathode substantially follows the grid, thereby absorbing the large d-c potential at the 6L7 plates and miminizing undesirable grid loading due to the direct connection. Phase inversion is also conveniently provided.

The grid voltage of the phase-inverter tube is established at a point on a voltage divider from B+ to ground and permits orientation of the composite signal on the cathode-ray screen.

There is linear response over the useful portion (about four-fifths) of the cathode-ray tube screen. Contributing to this is the high value of plate voltage (650 volts) applied to the 807 amplifiers.

Recording

For the recording medium, use is made of a DuMont type 5LP5 cathode-ray tube (blue screen) operating at maximum voltage in order to attain maximum spot intensity. A revolving-drum type camera using a single strip of oscillograph recording paper (Eastman No. 697, 4 x 60 inches) is employed with an *f* 2.3 (three-inch focal length) lens to provide a one-to-one image.

Records taken with this apparatus are illustrated in Fig. 4 and 5. The cathode-ray tube voltages were, in this case, only three-quarters of the maximum value. These records demonstrate the degree of resolution and recording intensity that may be obtained.

Interpretation of Records

It may appear disadvantageous that the steeply sloping portions of recorded transients are defined by a series of dots. This characteristic, however, may be used to advantage where it is desired to obtain quantitative values for these slopes. For this purpose the oscillator has been crystal-controlled, thereby accurately fixing the time between successive dots. The slope measurement then becomes that of simply measuring the vertical distance between successive dots and dividing by 1/25,000 sec. There is an increase in precision attainable in this way as contrasted to the normal method, by which the horizontal component of steep slopes must be determined.

Acknowledgement

This work was done while the author was employed at the Instrumentation Laboratory, Laboratory Services OR & DC, Aberdeen Proving Ground, Md.

References

(1) Hughes, Harold K., and Koch, Richard F., Combination Vacuum-Tube Switch for Double-Trace Cathode-Ray Oscillograph, Audio Amplifier, and Mixer, *R. S. I.*, p 183, Apr. 1941.

(2) Cosby, J. R., and Lampson, C. W., Electronic Switch and Square-Wave Oscillator, *R. S. I.*, p 187, Apr. 1941.

(3) Reich, Herbert J., Electronic Switch for Simultaneous Observation of Two Waves with the Cathode-Ray Oscillograph, *R. S. I.*, p 191, Apr. 1941.

(4) Phelps, Byron E., Dual-Triode Trigger Circuits, ELECTRONICS, p 110, July 1945.



FIG. 6—Schematic circuit diagram of the four-channel electronic switch, showing the crystal-controlled trigger pulse source and output amplifier in detail. Conventional power supplies are not built into the electronic switch unit

THE SONOBUOY

Expendable radio transmitter, modulated by signals from an underwater magnetostriction hydrophone, revealed the presence of submerged submarines to patrol ships and planes



Radio transmitter inclosed in the buoy is compactly assembled. Rubber grommets provide shock mountings for many of the components. Although the equipment is expendable, it must give dependable operation during its few hours of life

THROUGHOUT THE GREATER PART of the war, the German submarine-menace was great. As is now well known, radar was highly effective in locating U-boats which had surfaced and microwave radar could even detect a submarine's periscope as it just cleared the surface. For underwater detection of enemy submarines, destroyers and DE boats used sonar. However, both radar and sonar required that a signal be sent from the searching plane or ship. Thus the searcher revealed his presence, thereby warning the enemy to take evasive action. The sonobuoy enabled searching planes and ships to locate enemy submarines without revealing their own position.

Tactical Operation

The sonobuoy contains an underwater microphone or hydrophone. This hydrophone picks up underwater sounds, such as propeller noises, from submarines. The pickup range depends upon the state of the sea, and the speed, depth and type of the submarine. Range varies between several hundred and several thousand yards. After amplification the signal from the hydrophone frequency-modulates a low-powered radio transmitter. The transmitted signal is received by patrol craft. In this ingenious manner a radio operator on or above the sea hears sounds beneath the surface of the water. The sonobuoy thus combines the underwater detecting abilities of sonar and the range of radio.

In locating submarines the radio operator of a patrolling airplane throws out a 13½ pound sonobuoy, first pulling out the 39 inch telescopic antenna, an action which also connects the batteries to the circuits. The navigator records the buoy's sea position. A 24 inch muslin parachute opens to break the buoy's fall and to assure that it strikes the sea in an upright position gently enough not to damage or appreciably detune the radio circuits. The buoy's striking

Input transformer and two-stage, resistance-capacitance coupled amplifier provide high voltage gain in audio circuit. By using reactance-tube frequency modulation, negligible modulating power is needed. Reactance tube frequency-modulates the oscillator in its grid tank. Second harmonic from oscillator is coupled into power-amplifier-doubler which feeds the quarter-wave whip antenna



the water releases the hydrophone, which unreels itself to a depth of 20 ft. A bag of dye spreads a colored blot on the sea so that the patrol plane can more readily spot the buoy position.

Several sonobuoys may be dropped in a "spread". Frequencies of the buoys in such a spread differ by 0.8 megacycle. Color coding of the buoys and on the dial of the ship's sonobuoy receiver correspond, so that the radio operator can quickly tune in and identify any buoy in the spread.

By listening over the radio the operator can tell, from the relative loudnesses of signals from buoys, near which buoy the submarine is lurking, or in which direction it is moving. While a submarine is under attack the operator hears the explosions and even sounds of the submarine breaking up when the attack is successful. Recordings of these sounds are evidence of a kill.

A soluble carbowax plug in the buoyant, watertight sonobuoy case dissolves in a few hours, and the expendable transmitter sinks, thereby preventing the enemy from recovering it. Power supply batteries were designed to have such a life that they are about exhausted when the buoy floods and sinks.



On striking the water a sensitive button in the bottom of the 4¾ by 40-inch sonobuoy releases the hydrophone downward on a cable. Batteries, turned on when the buoy is launched, supply power during the four hours of operation



Sonobuoy is thrown from patrol plane. Parachute (right lowers it into the water (left). Underwater microphone picks up submarine sounds which are relayed by the radio transmitter in the buoy to the patrol plane or a ship

Circuits

The hydrophone used in the sonobuoy consists of a waterproof-wire winding on a magnetized-nickel cylinder. Sound waves produce electrical voltages by magnetostriction. Approximately three microvolts of audio signal is fed by a high-ratio stepup transformer to a two stage amplifier which is flat from 200 to 10,000 cps and down about 12 db at 200 cps.

A reactance tube frequency-modulates the tank of the electron-coupled Hartley oscillator. The oscillator operates in the vicinity of 18 megacycles, with the plate tuned to the second harmonic. In the r-f amplifier this frequency is again doubled. The transmitter signal is thus in the 70 megacycle range, and has a 75 kilocycle maximum deviation. The antenna is a vertical quarter-wave whip. An insulator holds the antenna base just above the surface of the sea.

The radiated power, about a tenth of a watt, is sufficient for line-of-sight transmission. Depending on how high the receiving antenna is, a ship can receive a sonobuoy signal from about six nautical miles away. An airplane flying at 5,000 feet can receive signals from 40 to 50 nautical miles away. Automatic frequency control in the receiver, working from unbalance in the discriminator output, follows random drifts of the sonobuoy transmitter center frequency.

Development

Research and development engineering was carried out at the Underwater Sound Laboratory of Columbia University at New London, Conn. under National Defense Research Committee contract. Production engineering and manufacture were done by Emerson Radio and Phonograph Co., and Freed Radio Corp. The navy used hundreds of sonobuoys in both Atlantic and Pacific waters.—K. H.



Sonobuoy, shown here in block-diagram form, is a complete, compact f-m transmitter

Coaxial

By ERVIN E. GROSS, Jr.
General Radio Company
Cambridge, Mass.



FIG. 1—Basic form of coaxial butterfly circuit. High-frequency setting is shown at left, low-frequency setting at right

IN SPITE of the large increase in production and use of high-frequency equipment during the war, simple and convenient laboratory apparatus such as variable oscillators and standard-signal generators, for frequencies above 500 megacycles, have not progressed commensurably. Much equipment has been built and used at frequencies well above 500 megacycles, but most of it has been for special purposes and is not suitable for general laboratory use.

During the emergency period, when speed was essential, it proved much quicker and easier to build a series of fixed-frequency test oscillators for specified frequencies and uses than to build multiple-purpose wide-range variable oscillators.

While fixed-frequency or limited-range oscillators were being used as an expedient, development work was continued on wide-range variable oscillators. This paper is a report on one such development, using the type 2C43 lighthouse tube. The oscillators developed have a single tuning control, wide tuning ranges, good output, and no sliding contacts.

Original Butterfly Circuit

Simple negative-grid triode oscillators using a single tuned circuit between grid and plate can be made to operate at frequencies approaching the resonant frequency of the tube if the tube has properly proportioned grid-cathode and plate-cathode capacitances. A compact tuning unit such as the butterfly circuit[1] is connected with a minimum of lead inductance between grid and plate, while feedback to sustain oscillation is determined by the effective grid-cathode and plate-cathode capacitances.

Because of the low ratio of plate-cathode to grid-cathode capacitance of the disc-seal or lighthouse tubes, efforts to use these in simple oscillator circuits were not successful above 700 megacycles. However, of the available high-frequency triodes, the lighthouse tube seems to have power ratings best suited for use in laboratory oscillators, when maximum frequency and good output are required. Although this tube does not work well in the simple oscillators using a single tuned circuit, it will oscillate to higher frequencies than other available tubes, with good efficiency, when used in oscillators employing multiple tuned circuits.

Coaxial Version

To build a tuning unit to fit the lighthouse tube in a convenient manner, a much different mechanical structure from the original butterfly circuit was required. Since the tube was designed for use in coaxial-line resonators, it seemed desirable to try to build variable oscillators using elements of coaxial lines as resonant circuits. The resulting tuning unit has become known as the coaxial butterfly.

Figure 1 illustrates the basic form of the coaxial butterfly tuning unit, showing the high-frequency position of the rotor at the left and the low-frequency position at the right. This unit consists of a coaxial line shorted at one end and open at the other. The outer conductor is not a full cylinder, but has two 105-degree sections cut away. Rotating between inner and outer conductors are two 75-degree sectors which vary the frequency.

In operation the tube is connected across the open end of the line and acts as a capacitive load foreshortening the line. The length of the line at resonance is much less than a quarter-wavelength because of this loading. As the two rotor sectors are rotated, the characteristic impedance of the line is varied. This means that the amount of foreshortening caused by the tube grid-plate capacitance changes, and hence the resonant frequency is varied.

Figure 2 shows a basic unit equip-



FIG. 2—Coaxial butterfly unit, designed to make plate and grid connections automatically when pushed over the lighthouse tube

Butterfly Circuits

Coaxial versions designed to fit over the type 2C43 lighthouse tube serve as wide-range uhf signal generators suitable for general laboratory use in the range from 500 to 1,600 megacycles. A single control varies feedback and frequency for either c-w or pulsed operation

ped with terminals for connection to the plate and grid of the lighthouse tube. In addition to the loading caused by the tube grid-plate capacitance, there is some capacitance added across the open end of the line by the rotor segments.

Frequency-Capacitance Chart

To get a better understanding of these tuning units, the plot shown in Fig. 3 was made. Values of loading capacitance required for a line of unit cm length are plotted versus frequency for a range of Z_0 from 10 to 500 ohms.

Besides showing that there is not much to be gained in frequency range by making the loading capacitance larger than the tube grid-plate capacitance, the chart can be used as a means of finding the resonant frequency for a line of known impedance Z_0, known length, and a given loading capacitance, or to obtain the proper loading capacitance for a desired frequency with a line of given Z_0 and length.

The chart has proved very useful in designing some of the coaxial tuning units. For example, with the dimensions and spacings that are considered practical in these tuned circuits, Z_0 can be varied from about 30 ohms to 150 ohms. If we make the tuned circuit 2 cm long, what frequency range should we get if the total effective loading capacitance is 4$\mu\mu$f This makes $n = 2$; the chart is adapted for this line length by multiplying capacitance scale values by 2. The original 2-$\mu\mu$f line on the chart now represents 4 $\mu\mu$f, the value at hand, and the frequency values obtained will be divided by 2. For $Z_0 =$ 150 ohms the frequency then is 1,600/2, and is 3,200/2 at $Z_0 = 30$ ohms, giving a frequency range of 800 to 1,600 megacycles for the unit.

Figure 4 shows the rotor construc-



FIG. 3—Calculated curves of resonant frequency as a function of loading capacitance and Z_0 for a line of unit cm length. For a line n cm long, multiply capacitance scale values by n and divide frequency scale values by n before using chart

tion which has given the widest frequency ranges. The two full metal rings at the ends not only make a stronger and more easily supported rotor than is shown in the basic units, but serve to keep the lumped inductance at the ends of the line at a minimum so that it is possible to take advantage of most of the change in Z_0 caused by the rotor segments.

Wide Frequency Ranges

The most effective means for getting wide frequency ranges has been to reduce all spacings between the rotor and the fixed portions of the tuned circuit. This decreases the effective Z_0 when the rotor is meshed with the outer conductor. In addition, the effective loading capacitance is increased. At low frequencies, Z_0 is unchanged, and the resonant frequency is reduced. At high-frequency settings the resonant frequency is increased because the decrease in Z_0 has greater effect than the increase in loading capacitance.

Stator Design

The stator or outer conductor of the line can be altered or shaped to provide a desirable law of frequency variation. While this lowers the top frequency for a given unit, the consequent reduction in the low-frequency limit produces an increased frequency range. Figure 5 illustrates one possibility. Here a 1,000-1,300 megacycle oscillator was designed for beat operation with a fixed 1,000-mc oscillator. A logarithmic variation of beat frequency was desired

between 10 and 300 megacycles. Curve A shows the variation obtained before shaping, with most of the frequency change occurring in the relatively small region where the rotor segments are just beginning to pass under the outer conductor. Curve B shows the results of shaping the stator as indicated in sketch B, and curve C shows the final curve obtained with the outer conductor shaped in the manner shown in sketch C. It will be noted that rotation has been reduced from 90 degrees to slightly less than 70 degrees.



FIG. 4—Coaxial butterfly rotor construction which has given widest frequency ranges in uhf oscillators



FIG. 5—Example of frequency variation versus dial rotation that is possible with coaxial butterfly units. Curves A, B, and C apply when stator or outer conductor of unit is shaped as in sketches A, B, and C respectively

The Q obtained with a coaxial butterfly circuit is low when compared with that obtained in coaxial tuners of optimum dimensions. Measurements on a tuning unit with a range of 620-1,350 megacycles indicate that the Q is about 350 at the low frequency and about 200 at 1,000 megacycles.

Feedback Circuits

The basic feedback circuit used with coaxial butterfly oscillators is shown in Fig. 6. The coaxial butterfly unit supplies a high resonant impedance between grid and plate of the tube. The outer cylinder, with tube and tuned circuit forming part of the inner conductor, makes up a coaxial resonator between grid and cathode of the tube. The fields of the two circuits are linked through the openings of the coaxial butterfly. Proper feedback for oscillation is obtained by adjusting the two disc-shaped plungers within the outer cylinder.

In addition to the frequency-determining rotor, this system requires two adjustable elements which have multiple sliding contacts. This circuit can be simplified if the plungers are properly located for the highest oscillator frequency and feedback for lower frequencies is maintained by adding capacitance C_F between a point on the tuning unit and a point on the outer chamber.

Sliding contacts can be eliminated if this capacitance is added, as shown in Fig. 7, by a series of adjustable metal fingers (a) which mesh successively with a tab on a ring (d) which is carried by the rotor. While multiple tuning elements are required, a variable oscillator with a single tuning control is the result. Oscillators with capacitive feedback adjustments such as this work satisfactorily over frequency ranges of about 1.6 to 1. Coaxial butterfly tuning units can be conveniently built to cover ranges of 2 to 1.

To make use of ranges available for grid-plate tuning units, an additional element to the feedback circuit was found necessary. This addition, shown in Fig. 8, consists of added grid-cathode capacitance produced by a series of adjustable fingers (b) mounted on the cathode stub which mesh successively with the shoe (c) mounted on the feedback ring (d).

As will be demonstrated, the feedback circuits outlined affect the coupling between the grid-plate tuning unit and the grid-cathode resonant circuit as well as keep the grid-cathode circuit properly tuned. Variations in coupling are caused by the relation of the feedback fingers (a) to the openings in the coaxial butterfly unit. For this reason, and because the coupling varies with the rotor position, some amount of experimenting and compromising is required before a continuously variable oscillator with a frequency range of 2 to 1 can be obtained. The final result, however, is an oscillator that has a wide tuning range, good efficiency, a single tuning control, and no sliding contacts.

Steps in the development of oscillators using the coaxial butterfly cir-



FIG. 6—Basic feedback circuit used with coaxial butterfly oscillators described in this article



FIG. 7—Cross-section and end views of oscillator, showing C_F of Fig. 6 added to eliminate sliding contacts

cuit have been outlined. Operating characteristics and descriptions of some of these oscillators follow.

The first oscillators developed using the coaxial butterfly unit were for use in a beat-frequency oscillator having a fixed 1,000-mc oscillator beating with a variable 1,000 to 3,000-mc oscillator to produce an output frequency of 10 to 800 mc.

Beat-Frequency Oscillator

The beat-frequency oscillator was suggested as a means for obtaining pulses with extremely short rise time at low frequencies where conventional oscillators do not have sufficiently rapid starting or buildup time. The fixed oscillator was to operate as either a c-w oscillator or a pulsed oscillator.

Pulsing requires more than the usual feedback to obtain the short rise time, and early experiments using the sliding end discs for feedback adjustment showed that a change in feedback was required if the oscillator was to be shifted from c-w operation to pulsed operation. It was noted that the change was accomplished by keeping the length of the outer cylinder constant and moving the tuning unit with respect to the end discs.

It was also found that the results could be duplicated by using the capacitive-type feedback. To reduce drift, the two oscillators were kept as much alike as possible. Outer chamber dimensions were kept the same. Adjustable capacitive-type feedback was retained for the fixed oscillator to obtain the required change in feedback, and the fixed oscillator grid-plate tuning unit was built as a coaxial butterfly with the rotor omitted.



FIG. 8—Feedback circuit for wide-range coaxial butterfly oscillator, with no sliding contacts



FIG. 10—Coaxial butterfly oscillator for 1,000 to 1,300 megacycles



FIG. 9—Variations in oscillator stability and buildup time as a function of feedback capacitance location with respect to openings in the coaxial butterfly unit

Oscillator Buildup Time

Figure 9 demonstrates rather clearly that the capacitive adjustment does more than keep the grid-cathode chamber properly tuned. By shifting the point at which the capacitance is produced, frequency stability and oscillator starting or buildup time are markedly modified. As indicated by the upper right-hand sketch, the oscillator buildup time has been broken up, for convenience, into two components, which have been called T_D and T_R (delay time and rise time). Good stability required for c-w operation results when the capacitance is produced in line with the solid portion of the tuning unit, while rapid rise time and short delay time required for pulsed operation result when the capacitance is produced in line with the opening of the tuning unit.

As a pulsed oscillator, delay time was reduced to about 0.05 microsecond and the rise time was reduced to less than 0.05 microsecond. Many things was tried in an effort to improve the rise time of the oscillator under pulsed conditions. Loading the oscillator in an effort to reduce the Q of the tuned circuit was one device that was effective. The effect was not noticeable, however, until feedback had been adjusted for optimum pulse shape.

As a means to pulse the oscillator, a relatively low-power negative pulse was produced across the cathode resistor. This method was simple, worked very well, and did not require the high power that would be needed for plate pulsing.

As a c-w oscillator, the stability factor or frequency change in parts per million caused by a 30-percent change in plate voltage was reduced to 1,000. Power output of 1.7 watts with an efficiency of 30 percent was obtained with 250 volts on the plate. While operation is possible for all positions of the feedback capacitance, stability is poor when feedback



FIG. 11—Oscillator output as a function of output loop location with respect to active feedback fingers

is optimum for pulsing, and oscillator rise time is bad when feedback is optimum for c-w operation.

Variable Oscillator

Power output of an experimental model of the 1,000-1,300 megacycle variable oscillator for use in the beat-frequency oscillator varied from 0.3 watt to 0.7 watt with a plate voltage of 250 volts, while efficiency varied from 6 percent to 15 percent. A sizeable loss of power output and efficiency is the price paid for variable-frequency operation.

Figure 10 is a cutaway view of the variable oscillator which was evolved. This oscillator has a single tuning control and no sliding contacts. The structure which supports and drives the rotor segments also supports and drives the feedback ring past the adjustable fingers. The outer conductor of the coaxial butterfly is shaped to produce the desired frequency distribution, and the contour of one of the sections can be seen in the photograph.

Wide-Range Oscillator

After completing work on the beat-frequency oscillator, it was decided to try to make an oscillator having a wide range that would be suitable for laboratory use. As has already been pointed out, ranges could be made much wider than were required for the beat-frequency oscillator. Experiments showed that because of the space required by the outboard drive for the rotor, the maximum frequency for which the outer resonant circuit could be adjusted was about 1,350 mc. To get as wide a range as possible for experiments, the lower frequency was reduced. The final frequency range obtained with this oscillator was 620 to 1,340 mc. This range was again obtained with a single tuning control, with no sliding contacts.

Position of Coupling Loop

Location of an output coupling loop for this oscillator was determined experimentally. It was first roughly determined that maximum output could be obtained if the loop were located in the end disc of the outer chamber, opposite the adjustable feedback fingers.

Figure 11 illustrates the method used to locate the optimum position for the loop. At several frequencies throughout the range the oscillator end disc was rotated so that loop X was moved through the arc subtended by the feedback fingers (area ABCD). By this means it was discovered that maximum output for any frequency was obtained when the output loop was opposite the acting feedback finger. The fixed loop position which will give best output over the frequency range is then at 36 degrees, or opposite the 1,000-mc active feedback finger.



FIG. 12—Coaxial butterfly tuning unit for 800-1,600 megacycles. Tuning knob is at left, and controls the position of the rotor. The lighthouse tube is inserted in the recess at the right end of the unit

Power output obtained over the frequency range varies between 0.15 and 0.30 watt. Here again increased frequency range is gained with a reduction in power output.

Getting Higher Frequencies

To extend the useful range of these oscillators to higher frequencies, a coaxial butterfly tuning unit for a range of 800 to 1,600 mc has been built and is shown in Fig. 12. Its actual frequency range with the type 2C43 tube is 770 to 1,650 mc. This tuning unit features a more compact and simple rotor support and drive than was used on previous models. Portions of the plate end or short-circuited end of the line have been cut away to allow the rotor supports to turn. Also, portions of the grid-end disc have been sliced off to make way for the supports which hold the feedback ring to the rotor. Other mechanical changes have simplified the assembly of the unit appreciably. Oscillations have been obtained over the frequency range of this unit with about the same vigor as are obtained from the lower-frequency unit. Tests have not been completed on this oscillator, but it is hoped that a mechanically simplified feedback circuit can be devised.

Conclusions

The oscillators described in this paper, while not of the more desirable single tuned circuit type depending upon the tube electrode capacitances for feedback, do operate with a single tuning control and are somewhat more efficient. Sliding contacts have been eliminated and wide ranges have been maintained. The oscillators have high enough output to be used as laboratory oscillators or in standard-signal generators.

New tubes may soon make these circuits obsolete, but for the present they are useful and their performance is comparable to that of oscillators operating at much lower frequencies. It is hoped that the information presented here, when added to other bits of information, will make for a better understanding of ultrahigh-frequency triode oscillators.

Reference

(1) Karplus, Eduard, Wide-Range Tuned Circuits and Oscillators for High Frequencies, *Proc. IRE*, p 426–441, July, 1945.

HERE COMES
THE NEW CINCH SOCKET

ALONG WITH

THE FIRST OF BELMONT'S

"Better things to come"

ACTUAL SIZE

It's the Belmont Boulevard—the new radio creation that easily slides into pocket or purse. Yet it is a complete, 5-tube, superheterodyne radio, weighing but little more than half a pound, and just 6 inches long, 3 inches wide and ⅝ of an inch thick. Employs the remarkable "war-born" miniature Raytheon tube and the new miniature Cinch Socket. This "mite" of a socket insures positive electrical contact, holds the tiny tubes securely in place, permits easy maintenance and replacement, yields maximum insulation resistance and minimum high frequency loss, and provides manufacturers of pocket radio receivers and hearing aids a labor saving chassis installation which serves terminal board functions The tiny CINCH Socket may be had with five, six, or seven contacts. It is now in production and available on order.

CINCH MANUFACTURING CORPORATION

2335 West Van Buren Street, Chicago 12, Illinois

***Subsidiary of* United-Carr Fastener Corp., Cambridge, Mass.**

Beat-Frequency INTERFERENCE CHART

By DON BARTON
New York, N. Y.

INTERFERENCE may be present in the output of superheterodyne radio receivers if their input circuits are not selective enough to reject all but the desired incoming signal. These spurious responses will be the result of the combining of the oscillator frequency and/or its harmonics with the fundamental or harmonics of strong stations radiating a frequency differing from that to which the tuned input circuit of the converter is adjusted.



The accompanying chart plots 19 different combinations of signal and oscillator frequencies that can produce interference in a receiver using the RMA standard i-f of 455 kc. The curves are computed from formulas given previously in ELECTRONICS.[1]

The following examples illustrate several different types of interference. At 660 kc, a vertical line drawn on the chart will intersect all of the curves. Perpendiculars from these points of intersection to the left will give the interfering signal frequency. Thus one objectionable point is determined to be 220 kc from curve 10. A long-wave signal other than that of the i-f may consequently be present in the output of the receiver due to the local oscillator beating with the third harmonic of the interfering signal to produce 455 kc.

The intersection of the 660-kc line with curve 1 indicates an interfering signal of 1115 kc. Although no station operates on this frequency, audible beats would be produced by reaction with either or both the 1110-kc or 1120-kc carriers 5000 cycles away.

Curve number 4 shows that police calls may be received while curves 18 and 19 show that amateur signals can also beat at the same time. By using the formula numbered to correspond to the curve intersected,[1] the exact frequency of the interfering signal can be computed and the audio frequency of the whistle determined, assuming that the station producing the interference is on its assigned wavelength.

REFERENCE

(1) Adams, J. J., Receiver Interference Chart, ELECTRONICS, p 48, Feb. 1941.

MALLORY RL



ILLUSTRATION ENLARGED APPROXIMATELY 30%

Top Favorite Switch For Test Equipment

OF all circuit selector switches manufactured by Mallory, this RL unit is the most popular by far for low-power, industrial applications. In a class by itself, the RL switch is the answer for industrial electronic equipment requiring greater durability than provided by the conventional radio circuit selector switch. It offers from 1 to 6 circuits per section with 30 degree indexing—from 1 to 3 circuits per section when 60 degree indexing is used. But that's not the whole story by any means.

The heavy self-supporting terminals of this switch, for instance, are clinched to the stator and held firmly without rivets or staples. Contact ends are ball shaped, formed of high quality spring brass material, and heavily silver plated.

The rotor contact member is made of solid silver, insuring much lower contact resistance. The high lift of the terminals makes possible a self-cleaning action which further improves electrical contact. High quality Bakelite in the stator provides ample insulation for general applications, yet is sturdy enough to withstand rough usage.

These are only a few of many reasons why this RL switch is found in radio instruments, test equipment, and a wide variety of other applications. For full information about this Mallory "leader", ask for the RL Engineering data folder and specification layout sheets, or see your Mallory representative. Standard Mallory Switches are obtainable from your nearest Mallory Distributor.



ELEVATION VIEW OF R L SWITCH

Ask for RL Specification-Layout Sheets

Printed on thin paper to permit blueprinting, these sectional drawings indicate standard and optional dimensions—make it easy for you to order pre-production samples of RL switches built to meet your requirements exactly. Ask your nearest Mallory Field Representative or write direct for a supply.

P R MALLORY & CO Inc

MALLORY SWITCHES

(INDUSTRIAL AND ELECTRONIC)

P. R. MALLORY & CO., Inc., INDIANAPOLIS 6, INDIANA

INDUSTRIAL CONTROL

Fifty-foot Lightbeam Controls Rotating Mandrel. 164
Radar Increases Safety of Night Boat..... 164
R-F Heating in Bakery Industry..... 166
Electronic Contactors for Control Applications..... 186

Fifty-foot Lightbeam Controls Rotating Mandrel

IN MAKING heavy hose at the Hewitt Rubber Corporation in Buffalo, N. Y., part of the process involves wrapping material on a huge 50-foot rotating mandrel, this being the standard length of finished rubber hose. This is done just prior to vulcanization and is an important step in the making of quality hose.

Until recently, the driven chuck which rotates the mandrel was controlled by the operator stepping on a wire cable which was stretched the full 50-foot length or by signaling the operator of the chuck by a nod of his head whenever the machine was to be started or stopped. This signal was sometimes not seen or the response to it was slow, and the wrapper could then be caught in the machine.

Recently, photoelectric equipment was installed about 12 inches above the floor. The light beam is thrown the entire 50-foot length and the machine is stopped instantly when the operator kicks either foot forward and so interrupts the beam. This may be done effectively at any point along the machine. A telescopic lens of 32-inch focal length focuses the beam to the phototube.

When first installed, the beam both started and stopped the machine, but to start the machine a wire cable is now stretched the length of the machine. This is placed close to the wrapping bar and operated by a pull of the finger of either operator.

Besides providing greater safety to the operator, the floor is left clear of any gear that might impair the travel of the operator, who now controls the machine with a minimum of effort and so may pay full attention to his work.

This fifty-foot mandrel on a large hose-wrapping machine is stopped by the operator when he moves his foot forward and interrupts a lightbeam that extends the full length of the machine

Radar Increases Safety of Night Boat

REGULAR NIGHT sailings of the commercial passenger-carrying night boat, *City of Richmond*, will benefit from an installation of radar equipment for navigation now being made by Westinghouse. The ship plies between Baltimore and Norfolk for the Old Bay Line, which plans to add more radar units to other ships of its fleet.

The installation is of the continuous plan-position-indicator type that provides a continuous picture of ship traffic and shoreline conditions from 100 yards to 32 miles distant in three ranges 2, 8 and 32 miles radius. The equipment uses a 7-inch cathode-ray tube mounted in a small cabinet convenient to the watch officer's station on the bridge.

Westinghouse engineers mount the antenna for laboratory tests of marine radar equipment for the Old Bay Line's Baltimore-Norfolk night boat, *City of Richmond*. The antenna will rotate under a mushroom-like protective cover atop pedestal to be located on the wheelhouse roof

The installation is in two major parts: the antenna, mounted under a large mushroom-like plastic dome atop a 5½-foot pedestal on the wheelhouse roof, with the modulator, preamplifier and other r-f components in the weatherproof base of the ped-

Kodak

Free...to Makers of Electronic Equipment

You'd like to have *all* your training films made to order, of course. But if you can't manage to do this, you can still organize an up-to-the-minute training program by supplementing your own films with films made by others.

And that's where this new book, "The Index of Training Films," can help you. It lists—with hundreds of others—a wide selection of films on electronic subjects for training factory workers, salesmen, and trouble-shooters. Movies and sound-slide films cover electron-tube theory, circuits, electronic motor controls, resistance-welder control, phototube applications, and many other electronic topics.

This informative index describes and classifies outstanding films . . . tells which are free . . . which can be rented or bought, and for how much . . . and where to get them. For your copy, write . . .

Eastman Kodak Company, Rochester 4, New York



. . . a guide to ready-made Training Films

This new book lists 155 films on Electronics and related subjects which you can borrow, rent, or buy very reasonably

Mail This Coupon for Your Free Copy

Eastman Kodak Company
Rochester 4, New York

Please send me a free copy of the new book, "The Index of Training Films."

Name_____

Company_____

Street_____

City_____ State_____

Training Films

—another important function of photography



Westinghouse engineer Lynn Ulman checks receiver-indicator of the first major installation for use on long-distance passenger-carrying marine service. The seven-inch ppi scope of this receiver-indicator console will be located on the bridge

estal, and the receiver-indicator console, a cabinet two feet square and 48 inches high located on the bridge. Power is provided by a below-decks rotary converter operating on the ship's d-c line.

Although the antenna is designed to provide a full 360-degree horizontal sweep, because of its location on the wheelhouse roof the stack will obstruct its scan for about nine degrees dead astern. If complete coverage astern is needed, it will be necessary to elevate the antenna. Operation is in the frequency band from 9,320 to 9,430 megacycles.

R-F Heating in Bakery Industry

THAT ELECTRONIC HEATING has been successfully applied to food products for dehydration, cooking, melting, roasting, deinfestation, baking, defrosting, and mold inhibition was announced at an annual meeting of bakers in Chicago by V. W. Sherman, president of Sherman Industrial Electronics Co., who copyrighted the talk. It was stated that certain applications are feasible only under special circumstances and that others are dubious and should not yet be recommended for development. He described some applications that have been repeatedly tested and possess both practicability and economic soundness.

Defrosting

Thirty-pound cartons of perishable fruits like strawberries have been defrosted with electronic heat in a matter of minutes, in contrast to the four hours in warm water or the one to seven days presently required at room temperature. Smaller two-pound cakes of frozen food were defrosted in less than one minute. Five-pound blocks of frozen eggs were defrosted in less than three minutes.

All these jobs were accomplished with only three kw of 13-megacycle electronic heat. Based on this work, a 25-kw electronic defroster was designed to handle barrels of frozen food at the rate of 750 to 1000 lb per hour depending upon initial temperature. To bakers, candy and ice cream makers electronic defrosting means a saving of time, space, and handling and also the reduction of spoilage and the retention of fresh flavor. From the health standpoint, electronic defrosting insures an exceptionally low bacteria count in eggs and similar products due to the speed of the process, which reduced drastically the time food was exposed to the atmosphere.

A large bakery may require the defrosting of 10,000 pounds of product per day. Many ice cream manufacturers use 40 to 50 barrels of frozen fruit a day. Defrosting times ranging from 45 minutes to two hours cover practical requests for equipment performance at this time and a 30 to 40-minute treatment time is recommended to reduce power and cost, yet insure low bacteria count.



For a given power output, the selling price of an h-f generator increases as the output frequency required by the job becomes higher. Dielectric heaters for bakery and food work require a frequency in the order of 13 to 30 mc. Small units range $750 to $1,000 per kw and larger sizes about $400 to $500 per kw of output



Operating cost for electronic heaters up to 100 kw. The curves are based on one make only and do not necessarily apply to all makes

The special defrosting of bread frozen to retain its freshness over a period of two weeks has been successfully done with electronic heat. The appearance and taste of the product were stated by bakery men to be equivalent to that of the fresh product. Other successful defrosting ap-

turbo INSULATIONS

..keyed to every installation need!

Electronic communication circuits are a proving ground for electrical insulation. The varied conditions imposed—high voltage, heat, climatic exposure, battery acid, fumes, etc.—make several insulations, each with specific characteristics, essential. To meet these diversified requirements, TURBO engineers have developed four types of sleevings that assure unfailing operation under any given operating condition. Each is supplied in a full range of colors and sizes that speed installation and simplify maintenance.

FLEXIBLE VARNISHED OIL TUBING: offers immunity to corrosive fumes, acid, alkalis and most solvents, with enduringly high dielectric values. It is impervious to moisture and non-hygroscopic.

VARNISHED GLASS TUBING: capable of functioning in high ambient temperatures—enclosed motors, unventilated areas, and general heavy duty installations.

WIRE IDENTIFICATION MARKERS: two types—sleeve type that slips directly over pipes, tubes, conductors; and tab type with flexible flag attached to sleeve. Both available in any marking.

Write today for free Specimen Board with samples and sizes of each.

TURBO

TURBO SAFE-GUARDS IT—IT SAFE-GUARDS IT

WILLIAM BRAND & CO.

276 Fourth Ave., New York 10, N. Y. • 325 W. Huron St., Chicago 10, Ill.

plications have included eggs (40 lb/hr/kw), chickens (30 lb/hr/kw), and a wide variety of packaged frozen foods.

Another application somewhat related to defrosting is the warming through of dough to promote rising. A reduction of shortening required is said to be made possible by the rapid and substantially uniform warming experienced with electronic heating.

Cooking and Baking

With only three kilowatts or less of electronic heat, heavy cookies ⅜ inch thick by 3 inches in diameter have been baked in 75 seconds. Fruit cake has been baked in glass dishes. Homogeneous foods such as meat loaf, diced vegetables, cored apples and many meal and flour products have been readily cooked. A five-pound leg of lamb was roasted perfectly in 30 minutes, gravy and all. This would have taken 2 to 3 hours in an ordinary oven.

Cooking or baking is an art that requires more than time and temperature. The application of electronic heat to such an art will require cooperative development. For example, the electronically baked cookie had no brown crust, and its surface color was much the same as its interior. Crusting could be readily added as a finishing operation using infrared lamps or electric strip heaters. In either case, the overall baking time would be definitely reduced but such necessary changes in baking technique must be decided by trial.

Melting

Chocolate, cocoa mixtures, sugar in several forms, starches, and other products can be melted with electronic heat. The rapid and substantially uniform heat was of real advantage. In certain cases special fixture design was required because of the product's tendency to foam. This was the case with dextrose and with lump sugar. Sugar syrup does not foam, nor does chocolate, nor starch which rapidly reduced to a jelly-like mass with electronic heat. When the product to be heated has both lumps and powder, the lumps may be expected to heat about twice as fast as the powder.

Mold inhibition is an excellent application and has produced positive

"The whole is equal to the sum of all its parts"—Elementary? Of course—as simple and unchanging as all great principles. This axiom is a fundamental manufacturing creed at Stancor. We know the established excellence of Stancor Transformers is vitally dependent upon the perfection of each successive manufacturing step—from engineering considerations of individual specifications—through coil-winding, laminating, assembling, finishing, testing—and, finally, to careful packing for shipment.

All individual manufacturing operations have one common denominator—QUALITY—uncompromising, changeless QUALITY that continues to prove—"IN TRANSFORMERS, STANCOR GIVES MORE."

IN TRANSFORMERS STANCOR Gives More

STANCOR
STANDARD TRANSFORMER CORPORATION
1500 NORTH HALSTED STREET CHICAGO 22, ILLINOIS

POSITIVE CONTROL

of Varying Power Supply

CASED MODEL

Raytheon Voltage Stabilizers

DELIVER OUTPUT VOLTAGE CONSTANT TO ±½%

FLUCTUATION of line voltage need not impair the performance of your electrical equipment. Such variations are easily corrected with magnetic-type, entirely automatic Raytheon Voltage Stabilizers.

Positive control is gained. Power supply is stabilized to ±½%. Reliability and accuracy of performance are effectively improved, *and at low cost.*

Investigate. Determine how positive control of line voltage can benefit your equipment. Our Bulletin DL-48-537 gives the detailed story. Write for it today.

Get These Principal Operating Advantages:

- **Control of output voltage to within ±½% of 115 or 230 V.**
- **Stabilization at any load within rated capacities.**
- **Quick response. Stabilizes varying input voltage within 1/20 second.**
- **Entirely automatic. No adjustments. No moving parts. No maintenance.**

RAYTHEON

Excellence in Electronics

RAYTHEON MANUFACTURING COMPANY

***Industrial Electronics Division*, Waltham 54, Mass.**

plications have included eggs (40 lb/hr/kw), chickens (30 lb/hr/kw), and a wide variety of packaged frozen foods.

Another application somewhat related to defrosting is the warming through of dough to promote rising. A reduction of shortening required is said to be made possible by the rapid and substantially uniform warming experienced with electronic heating.

Cooking and Baking

With only three kilowatts or less of electronic heat, heavy cookies $\frac{3}{8}$ inch thick by 3 inches in diameter have been baked in 75 seconds. Fruit cake has been baked in glass dishes. Homogeneous foods such as meat loaf, diced vegetables, cored apples and many meal and flour products have been readily cooked. A five-pound leg of lamb was roasted perfectly in 30 minutes, gravy and all. This would have taken 2 to 3 hours in an ordinary oven.

Cooking or baking is an art that requires more than time and temperature. The application of electronic heat to such an art will require cooperative development. For example, the electronically baked cookie had no brown crust, and its surface color was much the same as its interior. Crusting could be readily added as a finishing operation using infrared lamps or electric strip heaters. In either case, the overall baking time would be definitely reduced but such necessary changes in baking technique must be decided by trial.

Melting

Chocolate, cocoa mixtures, sugar in several forms, starches, and other products can be melted with electronic heat. The rapid and substantially uniform heat was of real advantage. In certain cases special fixture design was required because of the product's tendency to foam. This was the case with dextrose and with lump sugar. Sugar syrup does not foam, nor does chocolate, nor starch which rapidly reduced to a jelly-like mass with electronic heat. When the product to be heated has both lumps and powder, the lumps may be expected to heat about twice as fast as the powder.

Mold inhibition is an excellent application and has produced positive

"The whole is equal to the sum of all its parts"—Elementary? Of course—as simple and unchanging as all great principles. This axiom is a fundamental manufacturing creed at Stancor. We know the established excellence of Stancor Transformers is vitally dependent upon the perfection of each successive manufacturing step—from engineering considerations of individual specifications—through coil-winding, laminating, assembling, finishing, testing—and, finally, to careful packing for shipment.

All individual manufacturing operations have one common denominator—QUALITY—uncompromising, changeless QUALITY that continues to prove—"IN TRANSFORMERS, STANCOR GIVES MORE."

IN TRANSFORMERS STANCOR Gives More

STANCOR
STANDARD TRANSFORMER CORPORATION
1500 NORTH HALSTED STREET CHICAGO 22, ILLINOIS

POSITIVE CONTROL

of Varying Power Supply

CASED MODEL

Raytheon Voltage Stabilizers

DELIVER OUTPUT VOLTAGE CONSTANT TO ±½%

FLUCTUATION of line voltage need not impair the performance of your electrical equipment. Such variations are easily corrected with magnetic-type, entirely automatic Raytheon Voltage Stabilizers.

Positive control is gained. Power supply is stabilized to ±½%. Reliability and accuracy of performance are effectively improved, *and at low cost.*

Investigate. Determine how positive control of line voltage can benefit your equipment. Our Bulletin DL-48-537 gives the detailed story. Write for it today.

Get These Principal Operating Advantages:

- **Control of output voltage to within ±½% of 115 or 230 V.**
- **Stabilization at any load within rated capacities.**
- **Quick response. Stabilizes varying input voltage within 1/20 second.**
- **Entirely automatic. No adjustments. No moving parts. No maintenance.**

RAYTHEON

Excellence in Electronics

RAYTHEON MANUFACTURING COMPANY

Industrial Electronics Division, Waltham 54, Mass.

ACRO
OPEN BLADE
SWITCHES



Check these Advantages

✓ **LONGER LIFE**—based on ACRO patented beryllium Rolling Spring principle. Some ACRO Switches are guaranteed for ten million operations.

✓ **ALL SHAPES AND SIZES**—requiring less space—to fit any conceivable need of your new units. Will perform perfectly, mounted in any position.

✓ **OPERATING CHARACTERISTICS TO FIT THE JOB**—1, 2 and 3 poles—single throw or double throw. Return type, set type—wide range of operating pressures. Many applications solved by multiple mountings.

✓ **GREATER DEPENDABILITY**—Careful designing and manufacturing, producing positive, fast action and greater contact pressures, make ACRO Snap-Action Switches sturdy and trouble-free.

✓ **RATINGS**—15 Amps. at 125 volts A.C.

Send in your engineering details for quick help.

ACRO ELECTRIC COMPANY

1316 Superior Avenue • Cleveland 14, Ohio

results. Whole wheat bread, Boston brown bread, and white bread so treated remained mold-free for over two weeks. An untreated control loaf showed mold before the end of the second day. The protective treatment was given directly after wrapping and sealing the loaf in cellophane. Electronic heat developed the temperature of 140 F uniformly throughout the loaf in a matter of seconds. The small amount of moisture condensed on the inside of the cellophane wrapper during heating was quickly reabsorbed by the loaf during the cooling-off period. The treated product suffered no change of texture or taste.

Other Food Applications

Carmelizing, dehydrating, deinfesting, popping, and sterilizing have been done. Work in the food field has covered a long list of products ranging alphabetically from apples to yeast and including birdseed, candy, cereal, cinnamon, corn, eclairs, gelatin, licorice, malt, meats, muffins, nuts, potatoes, spices, and starch.

Figures 1, 2, and 3 show how white flour, a prepared biscuit mix, and a



Fig. 1—Electronic heating of white flour

ginger bread mix, respectively, responded to electronic heating which was applied as a protection against infestation. Although each food responded in a somewhat individual manner it may be noted that if the power had been adjusted to exactly one kilowatt in each case, then the 75-degree temperature rise would have been accomplished in substantially the same time (40 to 45 seconds) for each one-pound sample. In

Heat is a limiting factor in design, as designers and manufacturers of electrical equipment know. It's an obstacle to maximum operating efficiency and is a prime source of trouble for the user of the equipment.

As a base for impregnating varnishes of all types, including those specifically developed for high temperature applications, Fiberglas Electrical Insulation Materials provide the fully tested solution to many high-heat problems. Furthermore, it provides a means of overcoming many other conditions which are the major sources of insulation failure—such as moisture, corrosive vapors or acids, and overload.

In addition to unmatched mechanical and electrical advantages, Fiberglas Electrical Insulations can help give your product extremely valuable merchandising features and sales influence.

The full line of Fiberglas Electrical Insulation Materials can help you solve a heat problem—help increase the operating efficiency of your products—reduce maintenance requirements or provide a potent sales advantage.

Get complete information—write for a copy of "Are your motors a good insurance risk?" The name of the Distributors serving your locality will also be furnished if you desire. Owens-Corning Fiberglas Corp., 1860 Nicholas Bldg., Toledo 1, Ohio. Branch Offices in Principal Cities.

In Canada: Fiberglas Canada Ltd., Oshawa, Ontario

OWENS-CORNING
FIBERGLAS
TM REG US PAT OFF

Electrical Insulation Materials

It is a BETTER Electronic Component, when it is a POTTER CAPACITOR

Metal-Contained — Oil-Filled with Neoprene Bakelite Seals

VASTLY SUPERIOR TO ORDINARY CARDBOARD TUBULARS

Now—with the increasing multitude of electronic applications, exacting the utmost in dependability, make sure with Potter Quality. Light, durable, space-saving—the highest achievement in capacitor material design and construction, for *today's* precision requirements in electronics. *Aluminum*-contained—oil-filled—neoprene bakelite seals. *Durable.* Space-saving. Far surpassing cardboard tubulars *in every point.*

Here's Evidence! Remarkable Record of Potter Acceptance

Under the most rigid Signal Corps inspection—under conditions of the most intense humidity, acceptance of POTTER CAPACITORS ran 99 9/10 percent. Potter Capacitors have been specified for many types of Army, Navy, and C.A.C. equipment.

Assure your product the constant, high fidelity reproduction of Potter Capacitors to your specifications—performance always faithful to the ideal, under any and every condition of operation.

In ratings up to 2,500 volts

Ask for full details. Get *all* the facts on Potter superiorities—and compare! ***PROMPT DELIVERY. Wire or Write***

THE POTTER COMPANY
ESTABLISHED 1925
1952 SHERIDAN ROAD, NORTH CHICAGO, ILLINOIS
Preferred by leading manufacturers of electronic equipment

a commercial installation, where radiation and fixtures losses are negligible compared to energy in the product, almost double this heating rate per pound would be experienced for each kilowatt of applied energy.

For the bakery the following are felt to offer the most immediate value: an electronic baker for baking thick cookies either completely or at least during the early stages so as



Fig. 2—Electronic heating of prepared biscuit mix

to strike through and initiate heating of the core, an electronic mold inhibiter for packaged goods, and an electronic defroster for frozen fruits and eggs.

Popular Misconceptions

To make use of electronic heat today, the following ideas must be discarded as either downright fanciful or at least of no proven basis.

(1) That for each material there



Fig. 3—Electronic heating of gingerbread mix

Here's a heart-throbbing story

The Cardiotron is a product of Electro-Physical Laboratories, Inc., 25 West 18th Street, New York 11, N. Y.

THE new Cardiotron, a direct-writing medical instrument, makes an instantaneous tape recording of heart action, permanently visible the instant it occurs. Shown at left, this ultra-sensitive device uses four G-E Neon Glow Lamps, engineered into the product design, to provide these sales-making protection features: (1) quick visual indication of proper grounding and current flow, (2) correct connection to AC, (3) protection against surges, and (4) good voltage regulation.

-and it can improve your product







TYPICAL new and practical uses of G-E Glow Lamps are shown at left. They merely hint at hundreds of almost unbelievably low cost applications on home appliances, wiring devices, and many types of industrial equipment. Why not consider these distinctive sales features of G-E Glow Lamps on *your* products:

1. Distinctive orange red glow, needs no cover glass.
2. Dependable long life—rated at 3,000 hours.
3. Very low current consumption.
4. Variety of sizes and wattages.
5. High resistance to vibration and shock.
6. Usable on AC or DC circuits.
7. Work on regular 105-125 volt circuits without the use of step-down transformers.
8. Practically no heat.

FREE NEW FOLDER *describes typical uses for G-E Neon Glow Lamps and gives lamp data. Write address below.*

G-E LAMPS

GENERAL ELECTRIC

Nela Specialty Div. Lamp Dept., 1 Newark St., Hoboken, N. J.

Your SHURE *Glider* Pickup Check List

✓	low mass	✓	no springs no counterweights
✓	faithful tracking	✓	absorbs shocks
✓	higher output	✓	longer record life
✓	greater lateral needle point compliance	✓	clearer, fuller tone qualities
✓	1⅛ oz. needle force	✓	lever-driven crystal

MODEL 93A—$5.50 LIST

Immediately Available at Shure Distributors Everywhere

Patented by Shure Brothers. Licensed under the Patents of the Brush Development Company

SHURE BROTHERS

Designers and Manufacturers of Microphones and Acoustic Devices

225 West Huron Street, Chicago 10, Illinois
Cable Address: SHUREMICRO

SHURE

is one special frequency which produces super results not possible at a frequency slightly different.

(2) That higher frequency will always give better results.

(3) That there is something magic about a Btu of electronic heat.

(4) That electronically heated material escapes the conventional laws of thermo-dynamics, chemistry, etc, and that nothing limits the maximum speed of electronic heat.

(5) That dielectric fields, as such, have germicidal power.

(6) That electronic heaters have some mysterious effect upon persons.

The special-frequency fallacy seems logical until one runs tests on food



Fig. 4—The electrical loss factor of food is practically constant over a wide frequency range

after food as represented in Fig. 4. Over the usable frequency range, we have no magic frequency and could use almost any practical value as long as it is effective and does not require too high a voltage across the product. In spite of exceptions in the chemical field, it may be stated that thus far no magic frequency has basis for recognition in the heating of food products.

Use of a higher frequency sounds progressive but it gives better results only if lower work voltages are essential or if some unusual circumstance exists.

Electronic heater fields have neither germicidal power nor human sterilization power. They are merely capable of producing heat in a faster and more effective manner. The heat so created may be more advantageously located but it behaves exactly

More for the Money

An FM transmitter is not something you buy every day . . . it must serve you a *long time.* It should therefore be purchased with the greatest of care.

REL FM transmitters are built with one basic idea in mind — *to incorporate every single feature demanded by the Broadcaster.* That is why so much attention has been directed toward providing **maximum performance, reliability, simplicity, accessibility** of all parts— and use of the best components.

It is REL'S constant specialization and concentration on manufacture of FM equipment specially designed to meet the requirements of the Broadcaster that makes it possible to offer such fine equipment at such low prices.

Investigate before you buy! If your location permits, visit our plant and see the REL transmitters in production . . . or consult our nearest sales representative for further details.

PIONEER MANUFACTURERS OF FM TRANSMITTERS EMPLOYING ARMSTRONG PHASE SHIFT MODULATION

REL

Sales Representatives

SOUTHEAST

John F. Bivins
1806 Wellington Road
Highpoint, North Carolina

Electronic Supply Co.
112 North Main Street
Anderson, South Carolina

PACIFIC COAST

Norman B. Neely Enterprises
7422 Melrose Avenue
Hollywood 46, Cal.

MIDWEST

REL Equipment Sales, Inc.
612 N. Michigan Blvd.
Chicago, Ill.

MICHIGAN

M. N. Duffy & Co., Inc.
2040 Grand River Ave. W.
Detroit, Mich.

RADIO ENGINEERING LABS., INC.

Long Island City, N.Y.

New CANNON PLUG meets radio standardization demands



Designed for all low-level sound transmission circuits

. . . Cannon high quality at a new low price

For 15 years Cannon Plugs have been standard equipment on the best microphones, sound systems and other broadcast equipment. Now, with the trend toward parts standardization and the demand for more compact fittings, Cannon Electric introduces the new "radio universal" Type "XL"—manufactured with the well-known Cannon quality, at a new low price.

All the quality features you expect in any Cannon Plug are built into the new "XL"—ample voltage and amperage capacities, specially positioned grounding contact, all screw threads tapped in metal, high quality molded insulation.

Ready now are two plug types and four receptacle types with three contacts of 15-amp capacity for No. 14 B&S wire.

Check these **SPECIAL ENGINEERING FEATURES**

1. *Convenient latchlock to hold connection tight.*
2. *Extremely light weight (as low as 1½ ounces).*
3. *Compression gland with cable relief spring.*
4. *Polarized connection.*
5. *Smart, modern design.*





CANNON ELECTRIC

Cannon Electric Development Co., Los Angeles 31, Calif.

Canadian Factory and Engineering Office:
Cannon Electric Co., Ltd., Toronto, Canada

REPRESENTATIVES IN PRINCIPAL CITIES — CONSULT YOUR LOCAL TELEPHONE BOOK

Get this Special "XL" Bulletin. Write Dept. A-287, Cannon Electric Development Co., 3209 Humboldt St., Los Angeles 31, Calif.

like a Btu from any other heat source.

In other fields we may reasonably expect to see electronic defrosters developed for commercial kitchens and for frozen food stores.

Electronic cookers for special restaurant and domestic use are practical but still expensive and additional development is indicated. The heating fixture and work mechanization requires job engineering in every case and since the job will decide what the electronic heater must be capable of doing, it necessarily follows that the purchase of equipment for an industrial application should be based upon the recommendation of experienced industrial electronic engineers.

Operating Costs

The maintenance problem is confined to routine inspection and the replacement of tubes (average life 2,000 hours). Service cost records, based on several hundred r-f generators ranging in output from three to 75 kw and located throughout the East and Middle West, have indicated an average annual maintenance cost approximately five percent of the purchase price of the generator.

The total of all elements of operating cost rarely exceeds 10 cents per hour per kw of output. A three-kw output unit costs about 30 cents per hour to operate whereas a 25-kw output unit can be operated for only $1.80 per hour, which is less than six cents per hour per kw of output.

These figures take into consideration an overall electrical efficiency of 50 percent, conservative tube life of 2000 hours, equipment life of ten 2400-hour work-years (300 days × 8 hours), and annual maintenance cost equal to 5 percent of purchase price.

• • •

Electronic Contactors for Control Applications

W. D. MACGEORGE
Technical Consultant
Automatic Temperature Control Co., Inc.
Philadelphia, Pa.

INDUSTRIAL MACHINE and process operations provide a wide field for application of electronic relays and, since their construction presents no appreciable problem, new designs

Get the RIGHT ANSWERS

—when you choose Black Line Equipment!



WHAT SIZE MACHINE SHOULD I BUY? Your machine should have ample capacity for peak loads, but you should not pay for excess capacity which you will not use. The Bruning BW System not only provides a careful analysis of your print needs, but also makes available the exact size machine to fit your needs—thanks to the completeness of the BW line. (Illustration shows only a few of the many BW machines available.)



HOW MANY TYPES OF PRINTS WILL I NEED? Your black line equipment should be capable of providing various kinds of prints for departmental differentiation. The Bruning BW System provides black line prints on white paper, black lines on green paper, red line and brown line prints. In addition, there are BW Transparents and BW Film for special purposes.

WHAT ABOUT SERVICE? Bruning representatives sell a complete line of engineering and drafting supplies . . . all the way from tracing paper to drafting machines. Therefore, Bruning has a continuing interest in you as a BW customer . . . and Bruning experience is always available to help you get the most out of your BW machine.

You Get These Six Major Advantages With the BRUNING BW SYSTEM

1. A versatile, simple method for making black line prints directly from tracings.
2. 17 years' experience in analyzing printmaking needs.
3. A complete line of materials, including white and green-tinted papers, thin, medium and heavyweight papers, black, red or brown line prints, BW Transparents to supplement original tracings and BW Film for intensifying pencil lines on tracings.
4. A complete line of printing and developing machines to fit every requirement.
5. A continuing service . . . because Bruning sells everything for the engineer and draftsman, not just BW equipment. Buying a BW machine is, therefore, not a "one time sale."
6. Continuing research and development in the customer's interest.

CHARLES BRUNING COMPANY, INC.

Since 1897

NEW YORK — Atlanta, Kansas City, St. Louis

CHICAGO — Boston, Milwaukee, San Francisco

LOS ANGELES — Detroit, Newark, Seattle, Houston, Pittsburgh

CHARLES BRUNING COMPANY, INC.
4712-16 Montrose Avenue, Chicago 41, Illinois

Gentlemen: I want to know more about Bruning BW Prints and equipment. Please send me information.

*Name*_____

*Company*_____

*Street*_____

*City*_____ *State*_____

New CANNON PLUG meets radio standardization demands



Designed for all low-level sound transmission circuits

. . . Cannon high quality at a new low price

For 15 years Cannon Plugs have been standard equipment on the best microphones, sound systems and other broadcast equipment. Now, with the trend toward parts standardization and the demand for more compact fittings, Cannon Electric introduces the new "radio universal" Type "XL"—manufactured with the well-known Cannon quality, at a new low price.

All the quality features you expect in any Cannon Plug are built into the new "XL"—ample voltage and amperage capacities, specially positioned grounding contact, all screw threads tapped in metal, high quality molded insulation.

Ready now are two plug types and four receptacle types with three contacts of 15-amp capacity for No. 14 B&S wire.

Check these **SPECIAL ENGINEERING FEATURES**

1. *Convenient latchblock to hold connection tight.*
2. *Extremely light weight (as low as 1½ ounces).*
3. *Compression gland with cable relief spring.*
4. *Polarized connection.*
5. *Smart, modern design.*





CANNON ELECTRIC

Cannon Electric Development Co., Los Angeles 31, Calif.

Canadian Factory and Engineering Office:
Cannon Electric Co., Ltd., Toronto, Canada

REPRESENTATIVES IN PRINCIPAL CITIES — CONSULT YOUR LOCAL TELEPHONE BOOK

Get this Special "XL" Bulletin. Write Dept. A-287, Cannon Electric Development Co., 3209 Humboldt St., Los Angeles 31, Calif.

like a Btu from any other heat source.

In other fields we may reasonably expect to see electronic defrosters developed for commercial kitchens and for frozen food stores.

Electronic cookers for special restaurant and domestic use are practical but still expensive and additional development is indicated. The heating fixture and work mechanization requires job engineering in every case and since the job will decide what the electronic heater must be capable of doing, it necessarily follows that the purchase of equipment for an industrial application should be based upon the recommendation of experienced industrial electronic engineers.

Operating Costs

The maintenance problem is confined to routine inspection and the replacement of tubes (average life 2,000 hours). Service cost records, based on several hundred r-f generators ranging in output from three to 75 kw and located throughout the East and Middle West, have indicated an average annual maintenance cost approximately five percent of the purchase price of the generator.

The total of all elements of operating cost rarely exceeds 10 cents per hour per kw of output. A three-kw output unit costs about 30 cents per hour to operate whereas a 25-kw output unit can be operated for only $1.80 per hour, which is less than six cents per hour per kw of output.

These figures take into consideration an overall electrical efficiency of 50 percent, conservative tube life of 2000 hours, equipment life of ten 2400-hour work-years (300 days × 8 hours), and annual maintenance cost equal to 5 percent of purchase price.

• • •

Electronic Contactors for Control Applications

W. D. MACGEORGE
Technical Consultant
Automatic Temperature Control Co., Inc.
Philadelphia, Pa.

INDUSTRIAL MACHINE and process operations provide a wide field for application of electronic relays and, since their construction presents no appreciable problem, new designs

Get the RIGHT ANSWERS

—when you choose *Black Line Equipment!*



WHAT SIZE MACHINE SHOULD I BUY? Your machine should have ample capacity for peak loads, but you should not pay for excess capacity which you will not use. The Bruning BW System not only provides a careful analysis of your print needs, but also makes available the exact size machine to fit your needs—thanks to the completeness of the BW line. (Illustration shows only a few of the many BW machines available.)



HOW MANY TYPES OF PRINTS WILL I NEED? Your black line equipment should be capable of providing various kinds of prints for departmental differentiation. The Bruning BW System provides black line prints on white paper, black lines on green paper, red line and brown line prints. In addition, there are BW Transparents and BW Film for special purposes.

WHAT ABOUT SERVICE? Bruning representatives sell a complete line of engineering and drafting supplies . . . all the way from tracing paper to drafting machines. Therefore, Bruning has a continuing interest in you as a BW customer . . . and Bruning experience is always available to help you get the most out of your BW machine.

You Get These Six Major Advantages With the BRUNING BW SYSTEM

1. A versatile, simple method for making black line prints directly from tracings.
2. 17 years' experience in analyzing printmaking needs.
3. A complete line of materials, including white and green-tinted papers, thin, medium and heavyweight papers, black, red or brown line prints, BW Transparents to supplement original tracings and BW Film for intensifying pencil lines on tracings.
4. A complete line of printing and developing machines to fit every requirement.
5. A continuing service . . . because Bruning sells *everything* for the engineer and draftsman, not just BW equipment. Buying a BW machine is, therefore, not a "one time sale."
6. Continuing research and development in the customer's interest.

CHARLES BRUNING COMPANY, INC.

Since 1897

NEW YORK
Atlanta
Kansas City
St. Louis

CHICAGO
Boston
Milwaukee
San Francisco
Detroit
Newark
Seattle

LOS ANGELES
Houston
Pittsburgh

CHARLES BRUNING COMPANY, INC.
4712-16 Montrose Avenue, Chicago 41, Illinois
Gentlemen: I want to know more about Bruning BW Prints and equipment. Please send me information.

*Name*_____
*Company*_____
*Street*_____
*City*_____ *State*_____

Now available — an

ELECTRONIC VOLTMETER

BATTERY OPERATED

THIS MODEL 302

Sensitive Electronic Voltmeter is a new battery operated version of the standard Model 300 A.C. operated voltmeter. Operates from lightweight batteries contained within the carrying case.

MODEL 300
AC operated

Incorporating the popular single logarithmic voltage scale and uniform decibel scale, the Model 302 battery operated instrument retains all of the desirable features and performance of the standard Model 300 AC operated voltmeter illustrated at the left.

Voltage Range=.001 to 100 volts
Frequency=5 to 150,000 cycles
Accuracy=2% at any point on scale

The Model 302 Voltmeter will be found useful where A.C. supply is not available, as for example in airplanes, boats, automobiles, in the field, etc. Also valuable for making measurements on ungrounded and symmetrical circuits. Batteries meet JAN specifications.

Send for Bulletin for further description

BALLANTINE LABORATORIES, INC.
BOONTON, NEW JERSEY, U. S. A.

are appearing frequently. Basically, however, these electronic relays may be divided into three main groups: the vacuum-tube type, the cold-cathode type, and the hot-cathode type.

Vacuum-tube Type

Figure 1 shows a fundamental circuit for this type of unit. Tube V_1, usually a medium-mu triode such as the 6J5, is biased to, or near, cutoff by the bias supply B_2. In this condition, little or no current flows through the plate-cathode circuit.



Fig. 1—Circuit of electronic relay using a vacuum tube. Addition of capacitor C_1 provides delayed action

When the control contacts S_1 are closed, the grid of the tube is connected directly to the cathode. This reduces the bias on the tube to zero and a current of between six and ten milliamperes flows through the relay and pulls it in.

The current-multiplying effect of such a circuit is large. With a bias voltage of −10 volts and a grid resistor of two megohms, the maximum current that can flow through the control contacts S_1 will be five microamperes.

The contacts on the relay can be easily designed to handle a single or dual three-ampere inductive circuit. This gives in effect a current amplification of 3/0.000005 or 600,000. For noninductive circuits, the relay contacts can be rated at a higher current capacity and the amplifying factor may run as high as two or three million.

If the contacts S_1 form a high resistance when they are in the closed position, the bias will be only partially removed from the grid of the tube and the plate current will not rise to its full value. This may cause the relay action to be erratic and prevent snap action.

This type of electronic relay has

For linear variation of light output with current

SYLVANIA GLOW MODULATOR TUBES

The Glow Modulator Tube 1B59/1130B produced by Sylvania Electric is designed to meet the needs of practically any application requiring an essentially linear relationship between current and light output.

In this crater-type tube, a high ionization density is obtained. In addition, the discharge is viewed in depth. These two factors combine to provide a high effective density.

The Sylvania Glow Modulator Tube 1B59/1130B

Electrical Ratings:

Operating Voltage	140 volts max.
Operating Current	5—35 ma.
Starting Voltage	225 volts max.
Modulating Frequency Range	15—15,000 c.p.s.
Useful Light Range	3500—6500 Angstroms
Filament Voltage	None: Cold Cathode

Applications

The high-intensity light output of Sylvania Glow Modulator Tubes, and their virtually linear relationship between current and light output, suggest many fields of application, such as:

- Facsimile recording
- Sound on film
- Oscillograph timing markers
- Stroboscopic devices
- Seismograph recorders
- Photoelectric counters

Sylvania engineers will be glad to work with you in exploring specific fields of application for Glow Modulator Tubes.



Fig. 1



Relationship between light output and current in the 1B59/1130B

Fig. 2

SYLVANIA ELECTRIC

Electronics Division . . . 500 Fifth Avenue, New York 18, N. Y.

MAKERS OF ELECTRONIC DEVICES; RADIO TUBES; CATHODE RAY TUBES; FLUORESCENT LAMPS, FIXTURES, WIRING DEVICES; ELECTRIC LIGHT BULBS

Case Histories from the RICHARDSON files

PRODUCT REDESIGN

Problem: *Redesign intricate push-button switch parts. Parts must have good insulating properties, permanency of finish and appearance.*

Solution: Molded INSUROK—because it can be *precision molded* into practically any form—makes available many new design and structural possibilities. Threads, holes, trade-marks—can be molded right into INSUROK parts and no further finishing is required after molding.

Whether you are designing a new product or redesigning a present one—let *Richardson Plasticians* help you. They are highly trained in the proper use of INSUROK Precision Plastics, and will show you new ways to higher profits and greater satisfaction. Write today!



Courtesy, Allen-Bradley Company

INSUROK *Precision Plastics*

The RICHARDSON COMPANY

LOCKLAND, CINCINNATI 15, OHIO FOUNDED 1858 *Sales Headquarters:* MELROSE PARK, ILL.

Sales Offices: NEW YORK 6 • CLEVELAND 15 • DETROIT 2

Factories: MELROSE PARK, ILL. NEW BRUNSWICK, N. J. INDIANAPOLIS, IND.

time-delay action. Since the bias cidcuit of the tube must be direct current to obtain proper operation, resistive and capacitive components can be added to delay the action of the grid and therefore, of the relay. A suitable capacitor connected as C_1 in Fig. 1 will serve this purpose. The relay then will not respond to very rapid changes in contacts S_1 and for this reason, contact chattering can be minimized and suitable time delays for certain applications can be introduced.

Cold-cathode Tube

Figure 2 illustrates the fundamental circuit given in tube manuals for a radio-frequency-controlled relay. Tube V_1 could be an OA4G cold-cathode gas triode, or a similar tube. Resistors R_1 and R_2 are proportioned



Fig. 2—Conventional relay circuit for a filamentless cold-cathode tube

so that the igniter electrode will normally be maintained below its firing potential. The control contacts S_1, when closed, raise the igniter potential by means of paralleling resistor R_2 and fire the tube. A relay current of twenty-five milliamperes is usually maximum for this type of tube.

As soon as the control contacts are opened, the igniter is returned to its original potential and the tube will cease firing on the first a-c supply cycle that makes the anode of the tube negative to the cathode. In all relay circuits where a-c is used and the tube acts as a half-wave rectifier, the relay is subjected to half-wave pulses and must either be a fully shaded pole a-c type or must be paralleled with a suitable filter capacitor to smooth out the half-wave pulses and prevent chattering.

Assuming a 115-volt, rms, a-c supply for the circuit shown in Fig. 2, the peak anode-cathode voltage would be 154 peak volts and the igniter

AGALOY

SMALL COLD DRAWN SEAMLESS AND WELDED TUBING

The big advantages of AGALOY small tubing are:

Proper inside and outside surface conditions . . . Processed to bend and form as required.

Corrosion-resistant, heat resistant, dimensional accuracy:

Stainless (Types 304, 308, 316, 317, 321, 329, 347, 410, 430, 446 and others)... Monel metal ...Nickel...Inconel...L Nickel.

Available in sizes 5/8-inch outside diameter and smaller

AGALOY TUBING COMPANY

75 WEST STREET, NEW YORK 6, N. Y.

Chicago Office:
221 North La Salle Street, Chicago 1, Illinois

Mill:
Springfield, Ohio



Send for your copy "Plan with Agaloy Tubing"

Burlington

PANEL INSTRUMENTS

The heart of every Burlington Instrument — and the reason for its high degree of dependability — is the Burlington Precision Movement.

Design, material, and manufacturing processes are selected in such a manner that Burlington gives you a rugged instrument — which may be subjected to rough usage — and still retain its original calibration characteristics. All DC instruments employ Alnico magnets which are known to be more highly resistant to shock, heat, vibration, and stray fields than any other magnetic material.

All ranges AC & DC are available in 2½", 3½" and 4½" sizes, both square and round, flush mounting.

Engineering Service Furnished for Specialized Applications. No Obligation. Write Today for Further Information.

BURLINGTON INSTRUMENT CO.

108 FOURTH STREET BURLINGTON, IOWA

PANEL INSTRUMENTS • VOLTAGE REGULATORS • AUTOMATIC SYNCHRONIZERS • FREQUENCY REGULATORS

electrode should be maintained at approximately 60 peak volts to prevent firing. To insure ignition for run-of-the-mill tubes, this potential should be raised to 90 peak volts when control contacts S_1 are closed. If R_1 is 150,000 ohms and R_2 is 100,000 ohms, the additional current required through R_2 to raise the igniter to the firing potential of 90 peak volts will be 90 — 60 volts/100,000 ohms, or 0.0003 ampere. This additional current would be obtained through resistor R_3 and would have to pass through control contacts S_1.

Limitations

Increasing the values of resistors R_1 and R_2 would reduce the control current requirements proportionally, but their values cannot be made too large because the igniter current required to fire the tube is appreciable (approximately 100 microamperes), and an excessive voltage drop through R_1, when the tube fired, would cause unstable operation. To supply the 0.0003-ampere control current, R_3 would require a value of 413,333 ohms.

The cold-cathode circuit is simple to construct and, if the tubes used are reasonably uniform, will give satisfactory results for most applications. This circuit has certain disadvantages, such as the necessity for handling rather high potentials in the control circuit, and the limitation of the relay current to 25 milliamperes.



Fig. 3—Actuation by a specific carrier frequency is provided by adding a tuned circuit to Fig. 2

The relay circuit shown in Fig. 3, is an interesting application of the cold-cathode tube to r-f carrier relay service. This circuit is similar to Fig. 2 except that a high-Q tuned r-f circuit (LC) is inserted as shown. When no r-f is present, the igniter is maintained below its firing potential by the voltage divider $R_1 - R_2$; if an

UNIVERSAL

Cinemaster II CAMERA DESIGN

SIMPLIFIED BY TRUARC RETAINING RINGS!

Views of footage counter assembly which "watches" amount of unexposed film.
BEFORE TRUARC—
To insure unerring accuracy of film footage control, this vital assembly required 3 parts, including a specially machined knurl for holding and controlling the assembly. This made servicing difficult.
AFTER TRUARC—
Use of a special crescent type Truarc ring reduced assembly to 2 parts. This construction readily permits removal of footage control shaft from both motor plates—makes possible quick easy servicing of *all* enclosed parts.

NOW YOUR MACHINES CAN HAVE THE

DESIGN ECONOMY made possible by Waldes TRUARC Retaining Rings! Truarc allows lighter, more compact units—makes assembly of machine parts quicker, easier. Its perfect circularity gives better, more dependable retention. Truarc rings save weight, space, time and costs in every type of mechanical application. The crescent type is only one of six special Truarc rings. There's a Truarc ring for your machines, too.

FREE! Send today for your free copy of our new booklet—"Outstanding Truarc Applications in American Industry." See how Truarc can improve your product, while reducing production and maintenance costs. Specify booklet **18A.**

U. S. PAT. REG. 18,144



WALDES TRUARC
TRADE MARK
RETAINING RINGS

WALDES KOHINOOR INC., LONG ISLAND CITY 1, N. Y.

CANADIAN REPRESENTATIVE: PRENCO PROGRESS AND ENGINEERING CORP LTD., 72-74 STAFFORD STREET, TORONTO



springs for ELECTRONIC USES

Reliable

Reliable specializes in the design and production of springs to high precision standards—springs exactly adapted in every detail to the work they must perform. Master craftsmanship is applied to every job in our plant. Spring users whose demands are distinctly above average — who require an uncommon degree of accuracy and uniformity—find Reliable spring service most satisfactory.

We are large volume producers, yet our organization is built so that it is easy for you to bring your individual problem directly to competent executives, and receive their personal attention. In addition to our regular production facilities, we maintain a complete small order department. Carefully designed tools reduce the necessity for time-consuming setups, and large stocks of standard sizes of wire speed up delivery. Reliable engineers are fully qualified to help you work out technical problems in spring design. Reliable Representatives in key cities are always available for preliminary engineering and counsel.

Advise us of your requirements. Catalog sent on request.

THE RELIABLE SPRING & WIRE FORMS CO.

3167 Fulton Rd., Cleveland 9, Ohio • ***Representatives in Principal Cities***

YOU CAN RELY ON

Reliable Springs

ROUND AND FLAT WIRE SPRINGS · CLIPS · HOOKS · BENDS · LIGHT STAMPINGS

r-f carrier of the proper frequency appears across the line terminals, an r-f voltage will appear across L and supplement the existing igniter cathode potential sufficiently to fire the tube.

Hot-cathode Type

If the cold-cathode triode is replaced by a hot-cathode thyratron, the control circuit voltage may be reduced to a few volts. This is often important because when it is desired



This electronic contactor is employed in a temperature control system that requires snap-acting spdt contacts carrying 12 amperes of noninductive a-c and which are actuated by an impulse of two microamperes

to use very light moving contacts, the contact potential must be kept at a minimum to prevent the electrostatic forces present from causing contact chattering. In addition, the current available for relay operation is practically unlimited, with 100 milliamperes as a normal value for the smaller thyratrons.

Figure 4 shows a typical circuit using a GL502A thyratron. The maximum relay current for this tube is 100 milliamperes. Bias is supplied to the grid by the 6.3-volt filament transformer T_1, and prevents the tube from firing. When control contacts S_1 are closed, the grid is returned to the cathode, the bias is removed, and the tube will fire.

The rms current flowing through the control contacts is given by the expression 6.3 volts/$(R_1 + R_2)$. If we assign a value of two megohms to

A NEW ITEM...
An Old Story

For more than twenty-five years, new and unusual electrical appliances of all types—molded in whole or in part of Durez phenolic plastics—have been successfully marketed to the consumer.

One of the latest items to come within this category is the "Heet-It" illustrated. This new appliance was designed primarily for heating baby food in the nursery—to save busy mothers many daily trips to distant kitchens. Other applications such as a bedside coffee and broth cooker are obvious.

Why Plastics?

Notice the attractive Durez plastic case and cover. The manufacturer of "Heet-It", Electrical Reactance Corporation, experimented and found that plastics were better suited for these jobs than any other material. Again it's a matter of history repeating itself. Year after year manufacturers in the electrical appliance field have been selecting plastics for specific jobs of this type.

Why Phenolic Plastics?

Because the phenolics are the most versatile of all plastics, alert design-engineers have learned to make them their starting point in solving a materials problem. In this case, the properties called for were dielectric strength, heat resistance, impact strength, attractive finish, and resistance to the acids found in foods. All of these, and more, are inherent characteristics of phenolic plastics.

Why Durez Phenolic Plastics?

For the past quarter century, Durez production has been devoted exclusively to phenolic plastics and resins. As a result, there are now more than 300 multi-propertied Durez phenolic molding compounds from which to select the plastic that precisely fits your job. Furthermore, Durez technicians have gained a wealth of experience through active participation in the successful development of many and varied products for manufacturers in practically every field of industry. Naturally, the benefits which this rich background can bring about are very valuable—and they are yours for the asking.

Write for Free Booklet

"Machining Data on Phenolic Plastics" is an informative manual covering all the standard phenolic plastic machining operations encountered in the average plant. Send for your free copy. No obligation, of course. Durez Plastics & Chemicals, Inc., 84 Walck Road, North Tonawanda, New York. *Export Agents: Omni Products Corporation, 40 East 34th St., New York, N. Y.*

PLASTICS THAT FIT THE JOB

TURN TO TURNER

★ for *Style*

★ for *Dependability*

★ for *Performance*

Model 22 Microphone Gives You All Three

There's more than beauty of styling behind the Turner 22 Microphone. This famous member of the Turner Line is a precision unit — engineered to faithfully reproduce every desired sound without harmonics or distortions — ruggedly built to perform with unfailing dependability under difficult operating conditions. Good reason why so many leading manufacturers of electronic recording and communications equipment specify the Turner 22 as standard for maximum performance . . . why you want the TURNER 22 for your equipment. Available in both rugged crystal and dynamic models. Ask your distributor or write for complete performance characteristics.

You Get These Features in the Turner 22

★ Choice of Moisture Proofed Crystal or Rugged Dynamic Cartridge.
★ 90° Tilting Head for Semi- or Non-Directional Operation.
★ Removable Cable Set.
★ Barometric Compensator.
★ Mechanical-Shock Proofing.
★ No blasting from Close Speaking.
★ Low Feedback.
★ Certified Performance.

Turner Microphones Licensed Under U. S. Patents of the American Telephone and Telegraph Company, and Western Electric Company, Inc.

Free Turner Catalog

Write for your copy

The TURNER Co.

905 17th Street N.E., Cedar Rapids, Iowa

Pioneers in the communications field

TURNER *Microphones*

Crystals Licensed Under Patents of the Brush Development Co.

$R_1 + R_2$, the control current will be $6.3/2 \times 10^6$ or 3.15 microamperes. Even lower currents are possible under certain conditions.

Resistor R_1 is placed in series with the grid to prevent any possible damage to this element due to the accidental connecting of a large external voltage source to contacts S_1. A value of 50,000 ohms is usually adequate.

Capacitor C_1, shown in dotted lines, may be connected across R_2 to improve the phasing of the circuit and enhance its snap-acting qualities. The addition of C_1, although its value is usually quite small, will increase the control current requirements slightly. A capacitance value of 0.001 μf in parallel with a two-megohm value of R_2 would permit a control current of 3.9 microamperes to flow if the bias supply has a potential of 6.3 volts.



Fig. 4—At low control voltages, a hot-cathode thyratron permits the use of light-weight contacts

The circuit shown in Fig. 4 has one disadvantage. If its installation is not properly supervised, a short-circuit or high grid potential may result. This difficulty results from the fact that one of the control contacts is connected directly to the supply line and if the other one becomes grounded, trouble may result. To avoid this difficulty, a transformer-isolated unit, such as that shown in Fig. 5, may be used.

The 100-milliampere relay current capability of the GL502-A is usually sufficient, but it should be kept in mind that larger tubes handling amperes may be used without difficulty. For instance, the RCA 3D22 can be substituted in the circuit given in Fig. 4, without appreciably increasing the control current

BH SPECIAL TREATED FIBERGLAS SLEEVING



HEAT RESISTANT TO 1200° F!

SNUB TEST
Proves BH Non-Fray Feature
Make this test yourself. Tap a piece of ordinary saturated sleeving on your desk top and see how easily it frays. Then do the same with BH Extra Flexible Fiberglas Sleeving. It only fuzzes a little—doesn't break down—doesn't fray.
THE RESULT
The BH Way
The Ordinary Way
BH EXTRA FLEXIBLE FIBERGLAS SLEEVING
2 WAYS BETTER
NON-FRAYING • NON-STIFFENING

IF YOU NEED an electrical insulation that's not affected by temperatures up to 1200°F., yet is unusually flexible, workable and durable, you'll find it in BH Special Treated Fiberglas Sleeving. Even in direct contact with heat units this remarkable sleeving won't burn.

Reason? It's made of inorganic Fiberglas and treated by the exclusive BH process. No saturant is used, yet the sleeving won't fray when cut and it is *permanently* flexible. In addition to many other properties it is moisture, oil and grease resistant . . . works easier, simplifies assembly and lasts longer. Made in natural color only—all standard sizes. Get your free samples today and compare!

HERE'S ANOTHER NON-BURNING SLEEVING

BH *Extra Flexible* Fiberglas Sleeving won't burn because both yarns *and* impregnation are non-inflammable. This high quality sleeving has all the advantages of pure Fiberglas, is toughened against abrasion, is non-fraying and non-stiffening. It lasts indefinitely without rotting or cracking—the ideal all-purpose electrical insulation for all kinds of industrial equipment and home appliances. Available in all standard colors and sizes from No. 20 to 5/8", inclusive. Put it to the toughest tests you know and watch the results!

ALL BH PRODUCTS AVAILABLE IN STANDARD 36" LENGTHS AND 500-FT. COILS

BH PRODUCTS

BENTLEY, HARRIS MANUFACTURING CO.

Dept. E Conshohocken, Penna.



IN LAST PLACE

ON THE TROUBLESHOOTER'S CHECK LIST

AND PROUD OF IT!



J-B-T Instrument Type Rotary Selector Switches are available in 20 position SS-20 and 14 position, SS-14 models, one to six decks, non-shorting standard, and shorting on special order.

... for these are the instrument and tester makers own switches, designed and developed to meet the need for trouble-free, dependable performance in hard service.

They are extensively used in high quality test equipment, portable instruments, in inspection set-ups, and experimental circuits.

Now, because of quantity production, they are in a price range which makes it sensible to consider them for many other electronic applications. And they are available for immediate delivery. Your jobber probably has them in stock by now.

ADVANTAGES:

RUGGED

COMPACT

VERSATILE

J-B-T INSTRUMENTS, INC.

431 CHAPEL STREET • NEW HAVEN 8, CONNECTICUT

4-JBT-2

and with the ability to deliver 0.75 ampere of relay current.

Motor Control

Another use to which the thyratron circuit is well suited is the direct operation of a motor from contacts carrying microamperes without the use of intermediate electromechanical relays. A direct-current motor can be connected in the anode circuit of tube V_1 in Fig. 4. However, the operation of an a-c two-phase motor requires certain changes. Figure 6 shows a circuit which is adapted to



Fig. 5—To prevent grounding one or both control contacts, an isolation transformer can be used

this type of operation. The motor shown is a two-phase, capacitor-type unit and provides reversing operation from a single pair of control contacts, S_1. The operation is such that when the contacts are open, the motor will rotate in one direction and when they are closed, the motor will rotate in the opposite direction.

Tubes V_1 and V_2 are both biased from the 6.3-volt filament circuit and the grid of V_2 is raised to firing potential by coupling capacitor C_3, which is supplied with line potential whenever V_1 is dormant. When contacts S_1 are open, V_1 is dormant and V_2 fires; when the control contacts



Fig. 6—With this circuit, one pair of control contacts permits reversing a two-phase motor

Just

ONE

of the large

VISITRON

family



Rauland Visitron Phototubes are the recognized leaders in the field of light-sensitive devices . . . uniformity, dependability and high sensitivity through the years have earned them that reputation. Whatever the application, sound-on-film, electronic control or television pickup, there is a *Rauland Visitron* Phototube available to do the job perfectly. Or, we can produce a specially designed tube to meet an entirely new application. Let the experienced *Rauland* engineers consult with you about your phototube requirements.

To be sure . . . specify *VISITRON!*

ALSO MANUFACTURERS OF DIRECT-VIEWING AND PROJECTION TYPE CATHODE RAY TUBES

RADIO · RADAR · SOUND

Rauland

COMMUNICATIONS · TELEVISION

Electroneering is our business

THE RAULAND CORPORATION • CHICAGO 41, ILLINOIS

New communications records!

30,000 words per hour!

or 2760 Sq. In. of pictures

THE NEW FINCH "Telefaxer" *breaks all records for speed and accuracy* in the transmission and reception of words and pictures. 30,000 words per hour or 2760 sq. in. of pictures can be handled by radio. 9600 words per hour or 918 sq. in. of pictures, by ordinary telephone wire. And not one error or deviation from the original manuscript!

Anything that can be printed or written on paper, including drawings and photographs, can be transmitted by this most modern instrument of communications. With Finch Telefaxers, time and money are saved and the mistakes of telegraphic printers are avoided.

- Made by the manufacturers of Finch Facsimile equipment for broadcasting printed news and pictures.
- Write for new illustrated folder giving full particulars.

FINCH TELECOMMUNICATIONS, INC., Passaic, N. J., U.S.A.
Sales Office: 10 East 40th Street • New York 16, N. Y., U.S.A.

finch *First in Facsimile*

are closed, V_1 fires and reduces the potential supplying coupling capacitor C_3 to a value which is nearly zero. This removes the firing voltages from the grid of V_2 and it becomes dormant.

The motor is supplied by transformers T_1 and T_2, alternately. When V_2 fires, transformer T_2 feeds an alternating current to motor winding A. Winding B is supplied through phase-shift capacitor C and a rotating field results which drives the motor. Some efficiency is lost due to the shunting effect of transformer T_1 on motor winding B, but the motor operation is satisfactory for most purposes. When V_1 fires, the operation is reversed and transformer T_1 supplies power. Since the input to transformers T_1 and T_2 is half-wave, the addition of some filter capacitance (not shown in the diagram) to the circuit will serve to improve the wave form of the current reaching the motor.

Although any of the three basic relay circuits discussed will be found satisfactory for many operations, the hot-cathode thyratron offers the most promise in the control field since it combines high sensitivity, snap action and large current capacity.

• • •

PRIVATE PLANE SPEAKER

A soundproofed cabin and dual engine mufflers in the Stinson Voyager 150 permit use of a loudspeaker mounted in the dome and eliminates being fouled in the headphones if it is necessary to bail out. The radio equipment is mounted on the left of the instrument panel

Shapely

Post-Formed Phenolite chassis for high voltage circuit breaker. All holes and cut-outs are punched in the flat blank (*foreground*) before post-forming in channel shape. Use of Phenolite chassis in place of metal eliminates insulation of each separate part of assembly.

POST-FORMED PHENOLITE*

shapes profitable production and new products

There are opportunities for you in Post-Formed Phenolite—the laminated plastic that simplifies production and offers countless new applications for profitable-selling products!

Economical to produce, Post-Formed Phenolite parts are made in a matter of minutes. Practically any shape or form may be obtained simply by heating the sheet material a few seconds, then forming in low-cost wooden molds with standard press equipment. No sanding or "flash" removal is necessary. Fabrication may be done before or after forming.

Phenolite is extremely light in weight (about ½ that of aluminum); yet it has remarkable mechanical and impact strength. It possesses good machinability . . . is an excellent electrical insulator . . . resists heat and moisture . . . is resistant to abrasion . . . and is not affected by solvents and oils.

Find out some of the many ways in which this versatile material can be used. Write for full information and the assistance of one of our trained engineers.

NATIONAL VULCANIZED FIBRE CO.

OFFICES IN PRINCIPAL CITIES — WILMINGTON, DELAWARE

*FORMABLE THERMOSETTING SHEET MATERIAL

TUBES AT WORK

Video and Audio on One Carrier..... 208
Simple Converter Circuit for New F-M Band..... 212
Frequency Stabilization at 450 Mc..... 214
Radio Design Data Presented in Chicago..... 216
More on Spherics, Storm Detector..... 224

Video and Audio on One Carrier

A NEW television system in which sound and vision can be transmitted from a single transmitter occupying a normal band space has been developed by the British firm of Pye Radio Ltd.

The best method of understanding the new system is to consider the old system used by the BBC before the war, in which the picture was broken up into 405 lines and 25 pictures per second were transmitted. Typical lines are shown as *AB*, *CD*, *EF* in Fig. 1 and the tonal value along the line is expressed as the height of the waveform. During the periods *BC*, *DE*, etc, the electron beam in the camera is returning to start another line.

The time required to scan a line under this arrangement is 90 microseconds and at the end of the line the leading edge of the synchronizing pulse triggers the time-base in the receiver and suppresses the flyback, which occupies 10 microseconds. This obviously means that for 10 percent of the total transmission time the transmitter is idle. Actually it is the flyback which demands the greater part of the 10 microseconds, not the synchronizing pulse.

In the Videosonic system, this idle period is utilized to transmit the sound program and it is done by inserting a pulse into the 10-microsecond period and arranging that the width of the pulse is a measure of the audio modulation. At their maximum, the pulses occupy five microseconds and they narrow down to one microsecond at audio troughs. The mean width is three microseconds. Figure 2 illustrates this point and at the line-scanning frequency of the present system, 10,125 pulses per second are transmitted.

At the receiver end, separation is easy and depends on the pulse amplitude being greater than the maximum video amplitude. If the former is considered as 100 percent of the r-f carrier, the greatest video amplitude corresponding to a peak "white" is about 75 percent. All that is necessary then is to incorporate in the receiver simple limiting circuits which will only pass signals whose amplitude is greater than peak "white" signals. In practice the ratio of 75 to 100 percent has been found ample.

Advantages

There is no mutual interference between the sound and vision signals since the pulse corresponding to the former is absent during the scanning period. A new method of blacking out the flyback must be used but no difficulties have arisen in this direction.

The advantages of the new system are:

(1) The sound transmitter can be dispensed with.

(2) The received sound signal is more free from noise than under the



Fig. 1—The method of scanning a television picture is shown at (A). The resulting video waveform is shown at (B) and the radio-frequency waveform at (C)



Fig. 2—Method of inserting a sine-wave sound pulse in the flyback periods *BC*, *DE* of Fig. 1 so that the width of the pulse varies with the sound to be transmitted. At the receiver, the pulses at the bottom are separated from the video and passed through a low-pass filter that feeds the loudspeaker



relays OF TOMORROW

in Designs of Today!

FOR COMMUNICATIONS IN TRAINS • TRUCKS • BUSES • PLANES...

Relays **BY GUARDIAN**— years ahead of today— offer designers of two-way radios definite advancements which contribute to better long-life operation. This is especially evident with Guardian Relays and Switches used in two-way radios for trains, trucks, buses, planes.

For instance, Guardian's series 165-A Relay (A1 Si Mag insulated), for antenna changeover and break-in is small, compact, vibration-resistant. Laboratory tests with 2 normally open contacts prove series 165-A withstands vibration of 16.2 g.+ in both energized and de-energized positions. This is achieved by rugged overall construction and precise counterbalancing of the armature assembly. For H.F. and U.H.F. the series 165-A has a contact capacity to handle all required frequencies. Operates at temperatures ranging −65° to +160°F. and at altitudes from sea level to 50,000 ft. Truly, series 165-A merits a trial *now!* For V.H.F. antenna switching or keying try the war-tested Vacuum Switch Relay by Guardian.

Let us furnish cost-free information about the complete Guardian line of Radio Relays, also all Telephone Type Relays including the small Midget; and a special Switch used on push-to-talk circuits.



Series 165-A Relay



Series X-100 Relay

GUARDIAN ELECTRIC

1625-D W. WALNUT STREET CHICAGO 12, ILLINOIS

A COMPLETE LINE OF RELAYS SERVING AMERICAN INDUSTRY



PRECISION METAL SHIELDED WIRE

THE ULTIMATE IN PERFECT SHIELDING AND COAXIAL CIRCUIT COMPONENTS

•

***Better* because it is Shielded with Seamless Metal Tubing**







QUALITY PERFORMANCE
Precision metal shielded wire is especially suited for closely coupled air core transformers, shielded grid, filament, and antenna leads, and wherever low-loss transmission is required.

VARIETY
A single inner conductor or number of conductors can be shielded with seamless copper, brass, aluminum, or nickel tubing, plated if desired, in random or cut lengths, or formed to customers' specifications. Outside diameters range from 0.018" to 0.375", with any desired wall thickness.

STABILITY
Formed parts are self-supporting. This simplifies assembly and enhances appearance. Rapid changes in barometric pressure, temperature, and humidity do not cause injurious moisture condensation. Dirt is excluded. Since tube is seamless and dielectric is continuous, conductor and shield remain coaxial even when formed into coils or other intricate components.

EASY TO HANDLE
Tubing is easily stripped and formed right on the job, or can be furnished cut to exact length, stripped and formed, ready for instant application.

PRECISION METAL SHIELDED WIRE offers many advantages. It is an absolute method of shielding insulated wire or wires with seamless aluminum, copper, brass, or nickel tubing to provide the most perfect shielding yet devised against electrical interference, noise, moisture, or mechanical damage. As a coaxial line, it provides low loss over a range of frequencies and uniform capacity. Unlimited combinations of desirable electrical characteristics are available to meet your most exacting requirements.

We will be glad to cooperate on engineering problems. Write for further information.

PRECISION TUBE COMPANY

3826 Terrace Street, Philadelphia 28, Pa.

older system. Theoretical investigations have shown that it would be equivalent to increasing the transmitter power 100 times.

(3) The old difficulty of routing the sound and vision signals at the receiver vanishes.

(4) No ether space is occupied by the sound transmitter.

(5) The steady level of the sound pulses makes compensation for fading easier.

(6) The receiving antenna could be made more efficient since it would only have to operate on a single frequency band.

The chief disadvantage of the system is coupled with the existing 405-line transmission. At present, as the line frequency is 10,125, the audio frequency limit would be about 5,000 cycles—an undesirable figure since British listeners have been accustomed to transmitters with a practically flat response between 30 and at least 10,000 cycles. To achieve an upper audio limit of 10,000 cycles the number of lines would have to be increased to 1,000 which would give a line pulse frequency of 25,000.

One advantage of the pulse insertion scheme is that it would be quite easy to incorporate additional pulses corresponding to stereophonic sound, or for color work.

Figure 3 is an oscillogram of the Videosonic waveform during the 10-microsecond period. The sound pulse having a mean duration of three microseconds is shown extending downwards. Figure 4 is a photograph taken on a special receiver to show the variable sound-width pulses occurring during the flyback periods. These pulses build up a white band of variable width reminiscent of the



Fig. 3—The waveform during the 10-microsecond period as it appears on an oscilloscope

PERATURE
TION*

What temperature detection time best fits your product? The fast response of the Fenwal Thermoswitch allows you to engineer into your product the optimum speed of detection—from A to Z. Compare the response time of the Thermoswitch with other thermostats.

Chart shows the time interval required for a Fenwal Thermoswitch to change 10°F. when subjected to a 20° change in temperature. Compare this performance with that of Type 1 and Type 2 thermostats. Proper application can modify this response time to any value desired, from A to Z.



Study the advantages of Fenwal Thermoswitches before making any commitment, for the Thermoswitch has many advantages which are not found in other types of temperature control units . . . the unique principle of operation of Fenwal Thermoswitches permits extreme accuracy combined with rugged yet compact construction.

Send for your copy of the Thermotechnics booklet which includes "Fourteen Facts in Fenwal's Favor."

CROSS SECTION
CARTRIDGE
THERMOSWITCH

* 1 of the "Fourteen Facts in Fenwal's Favor".

Fenwal

FENWAL INCORPORATED

ASHLAND MASSACHUSETTS

THERMOTECHNICS FOR COMPLETE TEMPERATURE REGULATION

Webster Electric Cartridges and Pickups

GIVE LIFE-LIKE REPRODUCTION OF TONE!

You can select the correct cartridges or complete tone arms for radio-phonograph combination sets.

Dependability, on the tone arms and cartridges you incorporate in the machines that you manufacture, is an important part of selection. Because of this fact, many manufacturers have chosen Webster Electric Tone Arms and Cartridges. This acceptance has been built upon successful performance over a period of years.

Proved are these features—balanced construction that produces maximum output at designated tracking pressures—with minimum distortion and minimum mechanical reproduction. There are models designed for sharp cut-off at higher frequencies, while others provide response over an exceptionally wide frequency range through use of an extremely lightweight moving mass—a new Webster Electric development.

In all cases sharp resonance peaks have been avoided, and efficient performance can be obtained with any permanent or semi-permanent needle of standard make.

The new cartridges are available in 8 gram net weight for use with very light tone arms, and in 18 gram weight for the more common applications. Pin or solder type terminals are optional.

Why not write for full information and complete listing of tone arms and cartridges that are now available?

(Licensed under patents of the Brush Development Company)

WEBSTER ELECTRIC
RACINE WISCONSIN

Established 1909

Export Dept. 13 E. 40th Street, New York (16), N. Y. Cable Address "ARLAB" New York City

"Where Quality is a Responsibility and Fair Dealing an Obligation"

Fig. 4—Photo of the screen of a special receiver showing the variable sound-width pulses during the flyback period

sound track on motion picture film.

Two racks of the equipment contain the sound waveform generator and the mixer units. The function of these is to produce pulses at the correct instant having a width dependent on the audio waveform to be transmitted and then to mix these pulses into the vision waveform. These two racks would take the place of the sound transmitter at the television station, with the addition of high-power audio amplifiers.

• • •

Simple Converter Circuit for New F-M Band

THE FINAL CIRCUIT of the Hallicrafters converter for tuning to the new f-m band is shown in the diagram. The unit employs a double-triode



Complete circuit of the Hallicrafters f-m converter. All capacitor values are indicated in micromicrofarads

3 LEADERS *in internal curing*

INSULATING VARNISHES

For Transformers



IRVINGTON #100

A clear internal drying varnish noted for long-life at high temperatures. Life test of over 1100 hours at 105°C. Thorough penetration and curing is obtained even in the deepest windings. Provides firm, though flexible, transparent bonding, so clear that coded leads are readily identified. Possesses excellent electrical properties, and is oil, acid and moisture resistant.

For Motors



HARVEL #512C and 612C

Phenol-aldehyde type varnishes derived from Cashew Nut Shell Liquid. Set dry throughout by heat induced chemical polymerization, thus cannot leave gummy half-cured interiors. Provide high insulation resistance at all temperatures, and are outstanding in this feature at operating temperatures up to 300°F. Extremely resistant to acids, alkalis, moisture, and oilproof.

For Fluorescent Transformers and Ballasts



HARVEL #612C

Now widely used by Fluorescent Ballast manufacturers, because the unique structure of this cashew varnish aids greatly in keeping ballasts hum-free.

All the above varnishes will cure most satisfactorily under conventional convection baking methods, or infra-red. For complete information write Dept. 106, Irvington Varnish & Insulator Company, Irvington 11, New Jersey.

IRVINGTON *Varnish and Insulator Company*

Irvington 11, New Jersey, U.S.A.



Yours for the asking

A new informative booklet on gears. It has illustrated sections  **on practically every known form of gearing, together with**  **many reference tables and formulas. Write for your copy today on your company stationery.**

Quaker City Gear Works
INCORPORATED

1910 N. Front Street, Philadelphia 22, Pa.

7N7 for mixer and oscillator to form a double superheterodyne when connected to a prewar f-m receiver.

When placed on position 1, the four-gang switch permits operation of the receiver on other frequencies by feeding the antenna directly to the receiver antenna terminal. When set to positions 2, 3, and 4, the switch connects trimmer capacitors into the tuned circuits for covering frequency ranges of 84 to 93, 93 to 102, and 102 to 111 megacycles respectively. All tuning over each range is done by means of the regular tuning dial of the receiver.

Power for the converter is obtained from one of the power amplifier sockets in the receiver by an adapter that fits under the tube.

• • •

Frequency Stabilization at 450 Mc

By PETER B. MYERS
National Bureau of Standards
Washington, D. C.

DUE TO THE recent FCC allocations and the growing interest in the very high radio frequencies, the matter of constant frequencies at vhf becomes increasingly important. Crystal control is required for greatest constancy but quartz plates above about 30 mc are still impractical and involve delicate hand finishing.

At the present time, higher constant frequencies are generally obtained by electrical harmonic generators working off standard low-frequency crystals. Above about 100 mc, the number of harmonic generators and auxiliary pieces of equipment becomes excessive and other means of frequency control are needed. The mechanical harmonics of a quartz plate may however be utilized; for example, using the fifth mechanical harmonic of a 30-mc plate, the fundamental oscillation would be 150 mc and one stage of electrical harmonic generation (tripling) would produce standard crystal-controlled frequencies of 450 mc.

Used Harmonic Crystal

Mechanical harmonics may be excited in specially prepared AT or BT cut crystals, in which odd harmonics

"ZIRMET CUTS PUMPING TIME 30%"

Says Taylor Tubes, Inc.

Zirmet Benefits Both Tube Manufacturer and Tube User

Interested in reducing pumping time? Then you'll certainly want to look over these excerpts from a letter sent us by Taylor Tubes, Inc., commenting on their use of Zirmet (Foote Ductile Zirconium)...

"The application of the Zirconium Metal to the fins of the T-125 means that we are able to cut our pumping time by about thirty per cent, and the gettering action while the tube is actually in operation, is very good.

"The type T-125 tube is widely used in diathermy at frequencies up to 70 MC, and of course, in Amateur Radio operation at the present time, at 28 to 30 MC. We feel that the Metal is most effective in obtaining a higher order of vacuum in this particular application. It is well worth the small added expense."

Taylor Type 125 Tube for diathermy and radio applications.



Carbon Anode of Taylor Type 125 Tube. Four pieces of Zirmet 1/16" x 1 1/2" x .005" are welded to the molybdenum fins.

Zirmet is literally "what the doctor ordered" and may prove equally effective for you.

Many Advantages for Tube Maker and User

If you are a tube manufacturer, the use of Zirmet as a continuous getter means less pumping time, better vacuum, less shrinkage, clean tubes, and, naturally, satisfied customers. If you are a tube user, you can count on better emission and longer life when you buy a tube containing Zirmet the *continuous getter*.

Investigate Zirmet now. Write or telephone our engineers today for details and prices.

Foote MINERAL COMPANY

A Step Ahead in Industrial Ores and Chemicals

Chemicals • Ores • Metals • Alloys

PHILADELPHIA • ASBESTOS • EXTON, PENNSYLVANIA

Home Office: 517 GERMANTOWN TRUST COMPANY BLDG., PHILA. 44, PA.

West Coast Representative: Griffin Chemical Co., San Francisco, Cal.

FINE MATERIALS . . .
FINE ENGINEERING . . .
Fine Equipment



DESIGNED BY SPECIALISTS

THE FACT that we have specialists to properly design custom-built electronic equipment insures the quality you desire. Each device is carefully engineered for your specific job, and constructed in accordance with Audio Development Company's long established high standards; built to give complete and lasting satisfaction.

Among the types of equipment we build are controls, (chemical and positioning), amplifiers for specialized application, audiometers, measuring devices, etc.

Since we design and build the transformers for our electronic apparatus, the highest degree of engineering coordination is available.

Write us or our nearest representative for further information. Descriptive literature is available on standard audiometers, group hearing aids and transformers. Other electronic units—special transformers, filters, etc., are custom built to meet *your* requirements.

Please address all correspondence to our representative nearest your location:

Burlingame Associates, Ltd.
11 Park Place
New York 7, New York

Maury E. Bettis & Company
Room 400, B.M.A. Building
Kansas City, Missouri

Seattle Radio Supply, Inc.
2117 Second Avenue
Seattle, Washington

Walter P. Downs, Ltd.
702 Dominion Square
Montreal, P.Q., Canada

Cinema Engineering Company
1508 West Verdugo Avenue
Burbank, California

ADC
Audio Development Co.
2833 13th Ave. S., Minneapolis, Minn.
"Audio Develops the Finest"

up to the 23rd have been excited. A limiting factor is the optical flatness of the crystal. Mason and Fair found that the Q of the crystal increases in general with higher mechanical harmonics.[1] Special circuit arrangements are needed for harmonic oscillations above the seventh.

In recent experiments, the fifth mechanical harmonic of a 10-mc crystal was employed, followed by two electrical triplers, to reach 450 mc. Push-pull triplers incorporating midget tubes were used throughout. The oscillator tube was a 6C4 as were the tubes of the first tripler. Since the 6C4 was not found to be suitable for use at 450 mc, two type 6F4 were used in the final stage.

The output proved to be as stable as that obtained at the crystal's fundamental frequency. The generally accepted figure of 0.0025 percent as the maximum deviation in frequency of a crystal in the absence of regulation of any kind would limit the drift to 11 kilocycles at 450 megacycles. A two-hour test of the apparatus with a regulated power supply showed a maximum drift of 1.1 kilocycle at 450 megacycles, amounting to a frequency variation of ± 0.00025 percent or 2.5 parts in a million.

The crystal temperature coefficient was the same for the overtones as for the fundamental. The power output of the crystal oscillator used was less at each higher overtone, but the power was ample at 50 mc to drive a buffer amplifier.

The writer acknowledges his indebtedness to W. D. George and M. C. Selby of the Radio Laboratory of the National Bureau of Standards, where the experimental work was carried out; and his obligation to the Optical Division of the Bureau for the preparation of 10-mc quartz crystals with optically flat and parallel faces.

REFERENCE

(1) Mason, W. P., and Fair, I. E., A New Direct Crystal-controlled Oscillator, Bell Telephone System Monograph B-1363.

• • •

Radio Design Data Presented in Chicago

ASPECTS OF f-m receiver design, receiver response trends, and intermodulation effects in audio systems were

Why Not Pay Us a Visit

You Are Always Welcome

If you would permit us to pilot you through the various departments of our modern plant, you would readily understand why Jefferson Electric has earned the reputation for sustained quality in quantity production.

You would agree that it would be difficult to find a plant with all of the many features needed to produce in such quantities with such high standards of quality, accuracy and uniformity.

Engineering, research, experimental departments geared to the latest manufacturing methods and technique are combined with modern equipment and unusual esprit de corps.

When in Chicago, plan to pay us a visit—our suburban location is readily accessible. For your convenience you can call us by local Chicago telephone—Mansfield 7161. JEFFERSON ELECTRIC COMPANY, Bellwood (Chicago Suburb), Illinois. *In Canada:* Canadian Jefferson Electric Co., 384 Pape Avenue, Toronto, Ontario.

JEFFERSON ELECTRIC

TRANSFORMERS



How Much Could MILFORD Save for YOU on special, small metal PARTS and FASTENERS MADE TO ORDER?

Counterbored head, drilled secondary hole to 1/3 of way down through shank.

67% SAVING

Collared and drilled and delivered by the million.

72% SAVING



Two views—to show welding ring, vent hole, under cutting.

69% SAVING

5/8" deep tapped hole features this Milford special part.

37% SAVING

If your product calls for a small, metal part or fastener — it's a job for Milford.

If you use a part or fastener of standard design or size because the cost of a special design or size is too high — it's a job for Milford.

Typical of the endless variety of parts and fasteners which Milford manufactures to order by the millions for American industry — AND AT IMPRESSIVE SAVINGS — are those shown above.

For specific information, send a blueprint or sample.

THE MILFORD RIVET & MACHINE CO.
859 Bridgeport Ave. MILFORD, CONN.
1002 West River St. ELYRIA, OHIO

Inquiries may also be addressed to our subsidiary:
THE PENN RIVET & MACHINE CO., PHILADELPHIA 33, PENNA.

Designers and Manufacturers of: SPECIAL COLD-HEADED PARTS; SPLIT, SEMI-TUBULAR AND DEEP-DRILLED RIVETS; RIVET-SETTING MACHINES; SPECIAL MACHINE SCREWS AND SCREW MACHINE PARTS.

among the subjects covered by ten technical papers delivered at the Chicago Engineering Conference, sponsored by the Chicago Section of IRE. Held early in February, the meeting was attended by more than 500 radio engineers.

Details of f-m receiver design were discussed by Frank C. Gow of RCA Laboratories, who pointed out that series tuning in preselector stages is more effective than parallel tuning and that common coupling can be minimized by efficient design of the r-f circuits and by grounding the stator of the converter tuning capacitor.

Oscillator efficiency and stability can be obtained with four methods of conversion: a pentagrid using inner grid injection, pentagrid using outer grid injection, separate oscillator and mixer, and dual triode oscillator-converters. Greater stability can be obtained by using second harmonic conversion, although conversion transconductance is lower. If oscillation occurs, it can be cured by biasing the converter grid. Outer-grid injection results in more efficient, stable operation. For good operation, a 16-μv signal in the antenna is sufficient.

High frequency triode mixers are characterized by low input conductance but inductance is sometimes inserted in the plate lead to form a series-resonant circuit to increase grid input resistance. Triode mixers have lower noise level than pentodes.

In the design of the i-f amplifier, stability is the first consideration, with selectivity next. Effects of input loading on the selectivity of avc stages can be reduced by using high-C tuning circuits and adding degeneration by omitting bypass capacitors from bias resistors.

Audio Quality

The new FCC standards on good engineering practices concerning f-m broadcasting specify an a-f bandwidth of from 50 to 15,000 cycles in a manner which includes a minimum of distortion and unpleasant effects. Such specifications make necessary radical changes in audio frequency design, measuring techniques and concepts, according to J. K. Hilliard of Altec Lansing Corp. All elements of distortion must be reduced to a low degree, otherwise results of ex-

HEINEMANN
MAGNETIC CIRCUIT BREAKERS

— as Simple as

A B C



They Are

ENTIRELY MAGNETIC

A MAGNETIC-HYDRAULIC TIME-DELAY

Where specified, HEINEMANN Circuit Breakers have a true inverse time delay in a hermetically sealed unit which allows passage of inrush current. Continued overload, however, opens the breaker in time inverse to the ratio of the current. Breakers are made with time-delays closely matched to customers' specifications.

B HIGH SPEED LATCH

This latch mechanism operates with the least amount of friction and greatest speed of any latch known. It performs two functions, opening the breaker with the least mechanical delay, and opening it independently of handle operation. It functions only under overload or short circuit conditions.

C MAGNETIC HIGH SPEED BLOWOUT

This blowout adds speed to the arc interruption. Individual arcing chambers carefuly insulated from each other have magnetic blowout contacts mounted in them. As the value of the current to be interrupted increases, the quenching effect becomes greater, due to the intensified magnetic blow-out field.

Send for NEW Catalog Showing Complete Line and Engineering Data . . .

HEINEMANN CIRCUIT BREAKER CO.

Subsidiary of Heinemann Electric Co., Est. 1888

97 PLUM STREET **TRENTON, N. J.**

HOW MANY VARIATIONS ARE THERE TO A STANDARD DESIGN

Acme Electric transformers are designed to basic standards to which variations can be adapted to exactly meet the requirements of the application. For example, Mounting Type 100 is for horizontal mounting while type 101 is for vertical mounting, yet both are basically identical. And in either case, one or both mounting legs may be turned down for side mounting to save space. The number of leads or terminals may also be varied to comply to the electrical specifications desired. All things considered, Acme transformers made from standard parts to special specifications are available in hundreds of ratings and to exactly the physical dimensions, design and electrical characteristics you require. Acme TransformerEngineers will be glad to assist you by designing transformers to improve the performance of your product. Bulletin 168 gives more details.



TYPE 100



TYPE 101

THE ACME ELECTRIC & MFG. CO.
31 Water St. **CUBA, N. Y.**

Acme ACME Electric

tending frequency range will produce quality which is less pleasing than that obtained with a limited bandwidth.

Distortions may be in frequency and amplitude, and may be due to hum and noise or caused by interaction of complex frequencies or intermodulation. To meet the FCC requirements, an amplifier should have a total hum and noise at least 66 db below the full modulation or overload point. It should have a reserve sine-wave carrying capacity at least six db beyond full modulation.

There should be no significant difference in frequency response of the amplifier between runs made with oscillator and oscilloscope at maximum operating level, a level of 30 db below that point, and 60 db below maximum level. For direct transmission, six percent intermodulation should not be exceeded in the frequency band, and if the signal is be recorded and rerecorded or is to be transmitted through a network of amplifiers, it is desirable that intermodulation products be held below four percent.

Test Technique

Intermodulation tests consist of transmitting simultaneously two known frequencies through equipment under test and then measuring the degree of interaction and distortion of the two by determining the amount of new frequencies generated. First and second harmonics of intermodulation and ripple components are usually present.

The test method uses two oscilla-



Block diagram of intermodulation analyzer



MN-62A



MN-60A

MN-63A

MN-37

THE *NEW* NA-1 AIRCRAFT NAVIGATIONAL SYSTEM

Latest addition to the already famous Bendix Radio Compass Line

A new example of Bendix Radio Creative Engineering—The NA-1 System furnishes automatic visual bearings and simultaneous aural reception of cw, mcw or voice signals in the range 100-1750 kc. It also serves as a low frequency range receiver, or manual direction finder, and operates on a straight wire antenna or static reducing loop throughout its frequency range.

The MN-62A Radio Compass Receiver is designed for operation with r.f. transmission lines up to 30 feet in length, for flexibility in location of loop and sense antenna. All receiver and loop control circuits are included in a single case. The receiver operates from a primary power supply of 115 V., 400 cycles a.c. and 28 V. d.c.

The MN-60A Iron Core Loop—Small, streamlined, is ideal for highspeed craft. It increases payload of aircraft by reducing air-drag.

All functions of the NA-1 System are controlled with the type MN-63A Remote Control Unit, or with custom-built controls designed for specific overall systems and types of airplanes. Bendix Radio specializes in the design of such consolidated control assemblies.

Bearing indicators are available in several types and sizes for either a single or dual compass system.

All components of the NA-1 System are built to the same rigid specifications that have made Bendix the Greatest Name in Aircraft Radio. They bear CAA type certification for scheduled airline operation.

For full information, write to Sales Department

BENDIX RADIO DIVISION • BALTIMORE 4, MARYLAND

BENDIX RADIO

REG. U.S. PAT. OFF.

STANDARD FOR THE AVIATION INDUSTRY

Precision Bendix AVIATION CORPORATION

Whatever your instrument rectifier needs, for any instrument installation or repair job, you can be sure you're right, when you . . .

Choose
CONANT
Instrument Rectifiers

OVER 90 PERCENT of all rectifier requirements are served by 12 types—4 basic assemblies in 3 series. These series are Conant's 500, 160 and 160-C.

Conant special developments include:
BALAC—for applications that involve the balanced bridge principle in AC operation, and
UNI-SCALE— the rectifier assembly that completely eliminates temperature variations.

YOU NEED THESE BOOKS!

"New Rectifier Replacement Guide" for most test equipment. Know, at a glance, the correct type and size rectifier necessary for any installation. Write for your "Guide" today, it's free.

"Instrument Rectifiers and Rectifier Type Instruments", by H. B. Conant. It's 'must' reading for every user of instrument rectifiers. Send 25c to help cover handling and mailing.

Remember: (1) Every order for Conant Rectifiers is shipped to you *prepaid*, and (2) Substantial quantity discounts apply on large orders.

When you need rectifiers or when you need information, contact your local representative, or write

Instrument Rectifiers
CONANT ELECTRICAL LABORATORIES
6500 O STREET, LINCOLN 5, NEBRASKA, U. S. A.

20 Vesey St., New York 7, New York
85 E. Gay St., Columbus, Ohio
600 S. Michigan Ave., Chicago 5, Ill.
1215 Harmon Pl., Minneapolis 3, Minn.
2017 Grand Ave., Kansas City 8, Mo.
1212 Camp St., Dallas 2, Texas
378 Boulevard N. E., Atlanta, Ga.
4018 Greer Ave., St. Louis, Mo.
1526 Ivy St., Denver, Colo.
4214 Country Club Dr., Long Beach 7, Cal.
Export Div., 89 Broad St., N. Y. 4, N. Y.
50 Yarmouth Rd., Toronto, Canada

tors, one having low frequency output of 40-60-100 cps and the other with frequencies of 1,000-7,000-12,000 cps combined in a hybrid coil and fed through an attenuator to the equipment under test.

A block diagram of the intermodulation analyzer is shown. The input attenuator can dissipate 50 watts and is adjustable over a 90-db range in one-db steps. The output of the equipment under test consists of a low-frequency signal with a high-frequency signal superimposed plus harmonics of the original tones and intermodulation distortion.

To measure the intermodulation, the original low-frequency component must be removed. This is done in the 800-cycle filter following the attenuator. The filter output, a carrier and its resultant side bands, is then amplified and demodulated. A 200-cycle low-pass filter removes the carrier and transmits only the ripple components up to 200 cycles. The 200-cycle cutoff was set to admit at least second harmonics for all original low frequencies, more being accepted for the 40 and 60-cycle tones.

The ability of an amplifier system to transmit the low frequencies that occur simultaneously with the higher frequencies of speech and music is very important. Without such carrying capacity, extreme distortion may result. Transformers and other devices which change their impedance at low frequencies are a major cause of such distortion. All types of systems show the least distortion near the middle portion of the transmission band. For this reason, test frequencies were chosen near the outer portions of the band.

Practical Aspects of High Fidelity

That too much emphasis is placed on frequency response and not enough on entertainment value of reproduction was stressed by Hugh S. Knowles of Jensen Radio Manufacturing Co. He stated that high-fidelity sets produced in 1935 were capable of reproducing frequencies up to 7,000 cycles, which is far above the average today. Receivers produced in 1937 covered the range from 40 to 4,000 cycles and those produced in 1941, 70 to 3,500 or 4,000 cycles.

Chinn and Eisenberg specify wide-range reproduction as 30 to 10,000





The photo above shows a cut-away view and completed assembly of Allied type TKHX-26 sealed relay with ten soldered terminals individually color marked.

DIVERSITY OF DESIGN *plus* IN ALLIED'S HERMETICALLY-SEALED RELAYS

These relays are designed to fit your specific applications and to fill your special requirements completely, but this is not all.

When you specify "Allied" you are sure to get a unit that is completely engineered as a sealed relay — not just equipment built around older types. Moreover these sealed relays are produced completely, from start to finish, in Allied plants, by one organization, under coordinated standards.

These products have back of them a wealth of pioneering experience in the sealing of relays to protect them from dirt, moisture and many foreign substances or to prevent tampering or accidental damage to the working parts. This experience is today expressed in a completely organized sealed-relay division, using the most modern techniques and equipment including a specially designed sealing room where air temperature, humidity and cleanliness are scientifically controlled.

There is wide diversity of design in Allied sealed relays. But of far greater importance are the benefits of experience, complete engineering, and modern manufacturing by one organization. Before you specify be sure to get all the facts about Allied relays.

ALLIED CONTROL COMPANY, INC.

AL-102

GENERAL OFFICES: 2 East End Ave. (at 79th St.) New York 21, N. Y. *Factories:* New York City (2 East End Ave.) Plantsville, Conn. Chicago — 4321 N. Knox Avenue, Chicago 41, Illinois. *In California:* Allied Control Co. of California, Inc. 1633 South Hope St., Los Angeles 15, Calif.

Here's the switch you've been looking for. Now a simple and efficient means of switching coax lines is available in three models. Present Types handle 50-ohm coax at frequencies up to 4000 megacycles. ***Characteristic impedance is maintained thru all switch details.***

Application: Selection of antennas, receivers, low power transmitters; Intra-equipment switching in coax links; with phase monitors in directionals; double-ended selection of insertion devices, filters, etc.

Model 74 handles single line with choice of six channels. Model 718 in similar to Model 74 but with 8-channels. Model 72-2 is a double-pole, double-throw type for switching two circuits simultaneously. Other versions of the novel switching action of the COAXWITCH and other impedance levels are under development. If you have a coax switching problem, we can help you. Data sheets are available. Write Bird Electronic Corporation, 1800 East 38th St., Cleveland 14, Ohio, for your copy today.



BIRD ELECTRONIC

Instrumentation for Coaxial Transmission

cycles, medium from 50 to 8,000 cycles and narrow range from 100 to 4,500 cycles. The narrow range is wider than that of most production models of today. Surveys have shown that a band between the narrow and medium ranges is preferred by the public.

Response curves commonly shown as indicative of performance often lead to incorrect conclusions since the curves are dependent on location of the microphone and loudspeaker even in rooms that may be built to a given set of specifications. The loudspeaker output should go up at high frequencies to sound best to the ear. Subharmonic distortion is sometimes introduced to aid reproduction. Distortion from intermodulation varies greatly with frequency and may affect entertainment value of wide-range systems. The speaker felt that the entertainment value of a two-channel system reproducing frequencies up to 3,500 cycles is better than a one-channel system with 15,000 cycle response and that a spread-source effect in reproducing music is desirable even though it cuts articulation efficiency.

• • •

More on Spherics, Storm Detector

FURTHER TECHNICAL details of the spherics detector for locating distant storm centers (ELECTRONICS, Feb. 1946, p 212) have been disclosed by the Office of the Chief Signal Officer. The equipment enables weather forecasters to plot storms across thousands of miles of ocean by detection of static electricity in thunderstorms, cloud masses, or rainfall.

Experience proved that the spherics technique was not as effective in tropical climates as in more temperate regions. It was also found that nocturnal observations were significantly less accurate than those made in the daytime. And due to the comparatively low frequency of the spheric impulses (7 to 10 kilocycles), deflection of the ground wave causes a considerable factor of error, especially in coastal locations. Another element of error is introduced when the direction finders pick up low-frequency communication transmis-

Why do it the hard way ?
Just snap on a SPEED NUT !


"U" TYPE SPEED NUT SNAPPED BY HAND INTO BOLT RECEIVING POSITION
PRESS DEPT
SPEED NUTS eliminate handling of material
SNAP!
DON WOOTTON

A SPEED NUT CASE HISTORY

One car builder used four welding machines to attach cage nuts on fender stampings for head lamp assembly. Three men were needed for each machine . . . one hauled stampings from the press department and two more wrestled the stampings and located them in fixtures on the welder. Because of all this handling, stampings were frequently damaged. And after painting, threads had to be retapped.

Changing to self-retaining Speed Nuts radically reduced the costs of this operation! Two men now do this work on a conveyor and quickly snap the Speed Nuts into place by hand. We will be glad to give you complete details of this case history on request.

* * *

In Canada: Wallace Barnes Co., Ltd., Hamilton, Ontario
In England: Simmonds Aerocessories, Ltd., London
In France: Aerocessoires Simmonds, S.A., Paris
In Australia: Simmonds Aerocessories, Pty. Ltd., Melbourne

Time was when the only way to fasten a nut in place for blind location assembly was to weld, rivet or clinch a cage nut over the bolt hole. This anchored the nut . . . but man, what a job it was!

Changing to Speed Nuts really simplifies this type of operation! Effort is reduced to a fraction — hands freed for more productive work. Welding machines eliminated. Less floor space needed. And, there is less handling and easier final assembly. You get all this *plus* a better finished product because the spring tension lock of Tinnerman Speed Nuts *prevents vibration loosening.*

There are many types of self-retaining Speed Nuts . . . . . all designed to drastically reduce the cost of blind location fastening. Let us show you how they can be used on your product to effect really worth-while savings. Send in your assembly details today!

TINNERMAN PRODUCTS, INC.
2106 FULTON ROAD • CLEVELAND 13, OHIO

Speed Nuts* PATENTED

MORE THAN 3000 SHAPES AND SIZES

*Trade Mark Reg. U. S. Pat. Off.

FASTEST THING IN FASTENINGS

For FM and TV

NEW ANDREW COAXIAL CABLE WITH

51.5 OHMS IMPEDANCE!

Meets Rigid FM-TV Standards



3⅛" COAXIAL CABLE

A new coaxial cable, especially designed for FM and TV use, is now a reality at the Andrew Co. Scheduled for mid-June delivery to the first orders received, these new cables, in 4 sizes, introduce the following important engineering features:

1. Characteristic impedance of 51.5 ohms. (The regular Andrew cables for AM applications have a nominal impedance of 70 ohms.)

2. Connectors and associated fittings have been engineered with special care to avoid reflections and discontinuities. Being completely solderless, these fittings simplify installation and eliminate problems of flux corrosion and pressure leaks.

3. Insulators are spaced 12 inches apart in the 3 large size cables, and 6 inches in the ⅞-inch cable.

4. Improved low loss insulation material is used, having a dielectric constant of 6.0 and a maximum loss factor of .004 at 100 mc.

5. Close tolerances have been established on conductor and insulator dimensions, in order to maintain a constant characteristic impedance.

6. Inner and outer conductors are made of copper having a minimum conductivity of 95% IACS at 25° centigrade.



6⅛" COAXIAL CABLE

Your order now is the best assurance of early delivery on this new coaxial cable for your FM or TV installation.

Write or wire the Andrew Co., 363 East 75th Street, Chicago 19, Illinois, for complete information or engineering advice on your particular application.

ATTENUATION CURVE

Attenuation is calculated to provide for conductor and insulator loss, including a 10% derating factor to allow for resistance of fittings and for deterioration with time.



● The new 51.5 ohm air insulated coaxial cable for FM and TV comes in 4 sizes, priced tentatively as follows: ⅞", 42c per ft.; 1⅝", 90c per ft.; 3⅛", $2.15 per ft.; 6⅛", $5.20 per ft. Andrew Co. also manufactures a complete line of accessories for coaxial cables.

ANDREW

ANDREW CO.

363 EAST 75th STREET

CHICAGO 19, ILLINOIS

sions simultaneously with spheric impulses.

As used by the Signal Corps, each spherics set weighs about 450 pounds and costs about $5000. The frequency range of the latest model is 3.6 to 17.5 kilocycles.

Fixed Loop Antennas

Most radio direction finders are designed to detect continuous-wave signals which are sufficiently enduring in time to permit the determination of direction by rotation of an antenna. The detection of spherics obviously poses greater problems, and the static direction finder is engineered with two separate antennas which do not rotate. The two loop antennas are erected at right angles to each other so that the plane of one is perpendicular to the north-south direction and the plane of the other is perpendicular to the east-west direction.

Each antenna consists of 400 turns of wire wound inside a waterproof aluminum shield. The output voltage of each loop is coupled to identical but separate high-gain amplifiers, which are designed to produce identical output voltages in response to equal stimuli. The output voltages of the amplifiers in turn are coupled to the deflection plates of the oscilloscope.

When the loops are mounted at right angles to each other, signals arriving along the ground produce in each loop a voltage whose value is determined by the strength and angle of approach of each received signal. Since the two loops are identical in construction, their output voltages are identical in wave shape



Loop antennas of the direction-finder system for locating distant storms

HOW TO *Cut Costs and "Corners"* ON YOUR BLANKING DIES

You can save steel and time in the making of dies for blanking, trimming, beading, or any application involving the cutting of sheet metals to regular or irregular shapes, by assembling them from FCC Composite Steel Die Sections.

These prefabricated die parts consist of fine tool steel cutting edges, in a selection of grades, electrically welded by a special process to non-hardenable mild steel bases. Thus, screw and dowel holes may be easily drilled after heat treating, and there are numerous other advantages that will be immediately obvious to the die maker.

Thousands of die shapes may be made up from combinations of thirty-five standard sections. Specially shaped sections are manufactured to customers' specifications in five to ten days.

● Make *your* dies this money-saving way—full data on request.

WRITE FOR ENGINEERING DATA

It contains a print showing the various standard shapes available for quick shipment, and explains how to order special shapes, including rib-reinforced extra high sections. It also contains prices. Get your copy—write for it today.

ADDRESS DEPT. E-40

W & D 9477-C

ALLEGHENY LUDLUM STEEL CORPORATION

Forging and Casting Division
Detroit 20, Michigan

Send for complete catalog describing the full line of I.C.A. Antennas. Or, if convenient pick up a copy when you visit our exhibit at the R.P.E.E. Show, Steven's Hotel, Chicago.

Booth #34

(May 13th to 16th inclusive)

insuline

CORPORATION OF AMERICA

INSULINE BUILDING · LONG ISLAND CITY, N. Y.

More than a quarter-century of Quality production.

and phase, and are equal in magnitude for signals arriving from angles of 45, 135, 225, and 315 degrees.

The output voltages of the two loops are amplified to the point where they are strong enough to deflect the oscilloscope electron beam. The output voltage of the north-south loop amplifier is applied to the vertical plates and theoutput voltage of the east-west loop amplifier is applied to the horizontal plates.

In view of the brief duration of the oscilloscope flashes, a certain element of error is inherent in the instantaneous visual reading of the directional bearings. The Signal Corps is attempting to overcome this problem by developing auxiliary photographic equipment which records the oscilloscope indications on 35-mm film. This equipment includes a motion picture camera through which the film is drawn continuously at a speed of one to five inches per second, and a continuous action developer which automatically processes and dries the exposed film received directly from the camera. The film is then projected upon a viewing screen.



Electronic equipment of the static direction finder. Only half of the cathode-ray tube is calibrated since the individual direction finders provide data with 180-degree ambiguity

The camera action is synchronized at all stations of the spherics network by a radio timing unit which produces timing pulses, accurate to within 1 part in 50,000. This auxiliary photographic equipment is still in the laboratory stage.

KOSÁN ELECTRICAL TERMINAL STUDS

Installed . . . Locked in . . . Replaced from front side of panel!

1. Drill, counterbore and tap
2. Stud ready for insertion
3. Stud inserted, ready for ring installation
4. Terminal locking ring
5. Assembly completed, with terminals
6. Terminal locking ring removed



Molded-In Type. Terminal Stud molded solidly in panel, can be removed by simple means and replaced with two-piece type without damage to material or disturbance of other terminals.



Two-Piece Type. Panel drilled, counterbored and tapped, terminal stud inserted and locked with ring. Quick and easy removal may be effected as indicated. (No. 6 above)

Electrical Terminal Studs can now be installed, locked-in and replaced from the front side of the panel. This development is possible because of the Rosán Terminal Locking Ring which not only locks the stud firmly in the material, but allows the terminals to be tightly fastened without rotation.

The Rosán Terminal Stud may be molded into the panel, or easily installed after forming. It can be just as easily removed by prying under the flange at the top of the ring, without disturbing other studs or terminals.

Send for samples and full information on this time and moneysaving fastening system.

(Patents issued and pending, U. S. A. and foreign countries)

National HEADED AND THREADED PRODUCTS

THE NATIONAL SCREW & MFG. CO., CLEVELAND 4, O.

THE ELECTRON ART

AIEE Winter Convention

SPECIFIC INFORMATION on new frontiers initiated or given impetus by technical advances during the war was presented before approximately 2,000 engineers attending the 1946 AIEE Winter Convention held January 21-25 at the Engineering Societies Building, New York City. Of particular interest to ELECTRONICS readers were the sessions on communications, sound recording, industrial tube applications, and radar. Beginning on page 236 abstracts of the more informative papers are presented.

Electronic applications were mentioned in nearly all sessions. Although major portions of these sessions dealt specifically with electrical engineering, such as hydroelectric systems, power transmission and machine tool process drives, electronic techniques were mentioned in the sessions on excitation systems, industrial power applications, and instruments and measurements.

Power Generation

Electronic excitation systems for large a-c generators were described and principles of design and performance characteristics presented by Westinghouse engineers. These exciters provide reliable, continuous service, good generator regulation, and quick generator recovery from load switching and system shorts. Circuits using thyratrons can be designed so that tubes can be replaced without interrupting service.

Essentially these electronic exciters are rectifiers for supplying the d-c fields of generators. This particular design feature is a means of maintaining d-c excitation despite generator output voltage and current variations, especially during shorts. Besides the obvious method of operating from an auxiliary generator, the output of the exciter can be stabilized over wide ranges of main generator output either by compensating series transformers, firing angle control, or electronic regulation.

Power Applications

Industrial power applications utilizing electronics include induction heating and radiography. During this session, H. F. Storm of Allis-Chalmers Mfg. Co., Milwaukee, Wis., derived a graph of centimeters penetration for long, cylindrical charges heated by induction. The graph covers the frequency range from one cycle to one hundred megacycles and resistivities from one to one-thousand micro-ohms per centimeter.

X-rays produced by electrons magnetically accelerated in the Betatron have higher penetration than those currently produced by direct potential acceleration. Thicker sections of metals can be more quickly radiographed by these x-rays than by lower energy rays.

How the Betatron has been developed from a laboratory instrument into an industrial tool was related in a paper prepared by J. P. Girard of Allis-Chalmers Mfg. Co., Milwaukee, Wis., and G. D. Adams, University of Illinois, Urbana, Ill. Tests indicate that, like steel, most metals have a



Radiograph of Ford Model T motor made from Betatron produced x-rays

region of minimum absorption in the vicinity of twenty-million electron volt x-rays. Therefore the Betatron is designed to work in this range. Sections having wide variations in thickness can be radiographed. The small spot size of the Betatron x-ray source approximates the ideal point source, making possible enlargement of the specimen on the radiograph by simply increasing the specimen to film distance.

Other projected applications of the Betatron include medical therapy and nuclear research. (News comes from General Electric Co. that engineers of their x-ray laboratory are developing a Betatron x-ray generator. At



Miniature pentode developed for war time radar and having high figure of merit opens new frontier in such wide band systems as television and pulse modulation

Depend on OHMITE *Experience*

FOR THE RIGHT RHEOSTAT CONTROL







Time-proved Design! Widest Range of Sizes!

You get these advantages: (1) Ohmite experience with countless rheostat applications. (2) Service-proved Ohmite features that assure permanently smooth, close control. (3) Extensive range of sizes and types for easy, economical selection of the best unit for every application.

There are ten wattage sizes ranging from 25 to 1000 watts—from 1 1/16" diameter to 12" diameter—in uniform or tapered winding—in single or tandem units—in regular or special designs. Stock models from 25 to 500 watts, in many resistance values.

Consult Ohmite engineers on your rheostat control problem.

Send for Catalog and Engineering Manual No. 40

Write on company letterhead for this helpful guide in the selection and application of rheostats, resistors, tap switches, chokes and attenuators.

OHMITE MANUFACTURING COMPANY
4816 FLOURNOY STREET, CHICAGO 44, U.S.A.

Be Right with OHMITE

RHEOSTATS • RESISTORS • TAP SWITCHES • CHOKES • ATTENUATORS

the IRE Winter Technical Meeting engineers of Westinghouse Electric Corp. described high speed x-ray equipment capable of recording impact pressure waves.)

Measurements

In addition to instruments and measurements largely concerned with testing electrical machinery, three papers pertaining to electronic circuits were presented. In the first, prepared by engineers of the Leeds and Northrup Co., electronically balanced recorders having high input impedances and balancing time in the order of seconds were described. These recorders were developed for use with thermocouples and phototubes. Vacuum tubes within the recorders provide signal amplification, others control the balancing motors.

An automatic oscillograph with a memory was described by A. M. Zarem, California Institute of Technology, Pasadena, Calif. The oscillograph consists essentially of a long-persistance screen, cathode-ray tube. The unit was designed to record randomly occurring transients.

The cathode-ray tube is normally in constant operation. The time base is operating; the signal is applied. When a transient occurs in the system being monitored, the transient is immediately drawn on the tube



Automatic oscillograph records transients whenever one occurs

screen. The transient also blanks the beam preventing masking of the transient by later steady state signals and trips a camera focused on the screen. The transient trace is photographed before it decays. The system can reset itself in preparation for the next transient once the initial transient trace has been photographed. The beam blanking is removed, the film moved to the next frame, and the camera reset.

Servomechanism problems can be studied by electrical analogy methods described by Westinghouse engineers. The principle of the technique is to represent all mechanical properties such as time lag, inertia, stiffness, and friction by their electrical analogies. The electrical analogies are wired into the servo control circuit. Oscilloscopic observations at essential points in the circuit indicate system behavior. By this method, servomechanisms can be quickly studied and the effects on stability and speed of response of the parameters determined. The paper is specifically concerned with angular position servomechanisms.

Atomic Power

Generation of electric power from atomic fission promises to be the greatest directly constructive social benefit of atomic power. However, engineering difficulties which must be overcome before this application is economically feasible will require years of experience with this new energy source.

In an address before the Institute, J. R. Dunning, Columbia University, New York City, explained that, because of the necessarily thick shielding to confine harmful radiation within the atomic boiler, power plants would be too heavy for all but stationary locations although the reduced bunker requirements might enable atomic prime movers to be carried on the largest battle ships giving them a virtually unlimited range. Reactions within atomic boilers are self regulating; any desired temperature can be produced and maintained.

During his lecture Dr. Dunning demonstrated detection and recording of actual atom splitting, and showed that water acts to decelerate neutrons to their resonant velocity, thereby increasing their effectiveness in splitting atoms.

Addressing a combined meeting of the AIEE with the IRE, L. R. Groves, Maj. Gen. in charge of the Manhattan Project, said that the expense of developing the atomic bomb was only slightly greater than a week of modern warfare. Because of the uncertainty of obtaining usable results, the tactical command proceeded on the assumption that the atomic bomb would not be available. The atomic bomb project used 90,000 electron tubes.

During the AIEE symposium on nuclear energy at which K. K. Darrow, Bell Telephone Labs., Inc., C. G. Suits, General Electric Co., J. A. Hutcheson, Westinghouse Electric Corp., and P. W. Swain, McGraw-Hill Publishing Co., spoke, it was pointed out that present high cost of producing nuclear energy prohibits its im-



Simplified to the extent that one man in the pilot house can operate it, war developed radar opens new frontiers in maritime safety and independence from weather

PACKAGED R. F. RADAR ASSEMBLY ELIMINATES DESIGN HEADACHES

* R. F. RADAR UNIT #412

The DeMornay-Budd packaged R. F. Unit provides a complete R. F. assembly for microwave radar. It is now possible to obtain as standard items all the microwave R. F. components necessary in the fabrication of a complete radar—DeMornay-Budd Standard Transmission Line Components plus packaged R. F. Unit.

The R. F. Radar Unit is delivered complete and ready to operate. It is wired and contains all the necessary tubes and crystals. The unit uses a packaged magnetron capable of delivering 20 kw., peak power, at 9375 mc. Two type 2K25 local oscillator tubes are provided, one for receiver and A.F.C. and the other for beacon operation. A type 1B35 A-T-R tube, a type 1B24 T-R tube and the necessary type 1N21 crystals are included in the assembly. A 20 db. directional coupler permits accurate measurements to be made at any time with a maximum of convenience and safety.

Since the use of radar beacons is contemplated in the near future, the unit has been designed with a beacon cavity and crystal mount. The unit can be supplied without the beacon cavity and crystal mount and beacon local oscillator, and a termination supplied in their place so that it becomes a simple matter to convert to beacon operation when necessary.

We offer complete laboratory research facilities and have available such production test equipment as: Standing Wave Detectors, Calibrated Attenuators, Slug Tuners, Power Supplies, Square Wave Modulators, in addition to transmission line components shown in diagram above. Write for information or catalog.



R. F. Radar unit #412 (indicated by asterisk) used in conjunction with standard DeMornay-Budd transmission line components.

DE MORNAY BUDD

EQUIPMENT FOR 97% OF ALL RADAR SETS

DE MORNAY-BUDD, INC.
475 GRAND CONCOURSE, NEW YORK, N. Y.



there is NO SUBSTITUTE

for good, honest WIRE, unwinding itself cross-country, through mighty public buildings and humble cottages, in and out of America's radio sets and legion other communications units. You are getting some CORWICO Wire now . . . and more is on the way . . .



CORWICO cornish
WIRE COMPANY, INC.
15 Park Row, New York 7, N. Y.
"Made by Engineers for Engineers"

mediate constructive use. In areas where other fuels are scarce, such as Australia, atomic energy will first be harnessed for power generation. Based on present knowledge, small power units for automobiles, homes, and airplanes are not feasible. To support long-range development, much fundamental research in nuclear physics is necessary. The development of the atomic bomb exhausted our surplus of fundamental knowledge. The only new fact learned was the discovery of nuclear fission in 1939. Fission, distinguished from radioactivity, occurs in sereval relatively abundant elements making nuclear energy marginally economically available.

Most solid fuel consumed in this country produces low pressure, low temperature industrial steam. It is in this field rather than in power generation that atomic energy can best be applied. The limiting economic factor in electric power is transmission. Nuclear energy is most usable in large power generating stations; therefore it is not an immediate competitor for coal because of the technical difficulties and high initial cost of electrical power distribution.

Of particular importance are the applications of nuclear fission in the fields of medicine, chemistry, and for penetrating further into fundamental knowledge of matter from which other sciences can build.

Demonstrations

Displays of wartime developments and field trips to plants indicated new frontiers in a tangible form. Greatest interest was shown in a dial radiophone for automobiles demonstrated by engineers of the Fred M. Link Corp., New York. Operation is on the experimental 152-162-mc band. Dialing on a standard Western Electric dial phone selectively calls other cars or a tie-in station to line subscribers. Communication over the f-m radio link was maintained between engineers at the DuMont Laboratories on Madison Ave. and a moving car.

Awards

The Edison Medal, awarded annually to the individual contributing most significantly to economic and



How do induction and dielectric heating work?

What are their advantages and limitations?

Where can you use them?

How do r. f. generators compare with motor-generator and spark gap units?

Now you can get the facts with this new book

The answers are all here in this new fact-packed book by Westinghouse . . . including full-color illustrations and 14 case histories of induction and dielectric heating . . . brazing, annealing, hardening, soldering, plastic molding, rubber curing, plywood bonding. Write today for your copy on your business letterhead, please. Ask for B-3620. Westinghouse Electric Corporation, P. O. Box 868, Pittsburgh 30, Penna.

J-08161

Westinghouse

PLANTS IN 25 CITIES . . . OFFICES EVERYWHERE

Electronics at Work


HEADQUARTERS FOR ALL TYPE
MOISTURE & MILDEW PROOFING
COMPOUNDS
Our wartime experience developing and producing moisture-mildew proofing compounds for all services has equipped INSL-X with the "know-how" to solve any problem in this field.
We have on hand at all times, the materials to render immediate service. Lacquer, wax or varnish with any fungicide alone or in combination with another. Any quantity—put up in any size containers.
When commercial or military requirements call for moisture-mildew proofing, check with INSL-X!
Literature on Request
INSL-X MEANS MODERN INSULATION
THE INSL-X COMPANY INC.
857 MEEKER AVE., BROOKLYN 22, N. Y.
CHICAGO · DETROIT · LOS ANGELES · PHILADELPHIA
CLEVELAND · ST. LOUIS

dependable power generation and transmission, was presented for 1945 to Philip Sporn, American Gas & Electric Corp., by W. E. Wickenden, president, on behalf of the AIEE. W. H. Harrison, American Telephone & Telegraph Co., received the Hoover Medal for 1945. This medal, awarded by the national civil, mining, mechanical, and electrical engineering societies, takes its name from its first medalist, and is given to a fellow engineer for distinguished public service. S. F. Voorhees, New York architect, made the award on behalf of the participating societies at a combined meeting of the AIEE with the IRE.

Communication

Electronic Regeneration of Teleprinter Signals

By H. F. WILDER
Western Union Telegraph Co.
New York, N. Y.

DIFFERENCES in transmission velocities over wire lines of the harmonic components of rectangular teleprinter pulses and presence of noise result in deterioration of the signal after transmission over long distances. To restore the sharpness of the impulses and provide a gate to noise, a regeneration repeater is introduced in the line.

To accomplish the function of a signal regenerator electronically, a timing gate is used. The arrival of the start signal in the series of impulses of a teleprinter character trips a relay which sends an impulse down a lumped, timing network. The progression of this timing impulse down the relay line activates a tube at the times there should be polarity reversals of the signal. Thus this tube only accepts signal reversals at the instants they should occur. In this way the signal is restored to its original sharpness, and noise is rejected.

Tunable Rejection Filter

By R. C. TAYLOR
Western Union Telegraph Co.
New York, N. Y.

IN COMMUNICATIONS it is frequently necessary to reject a narrow frequency band. To do this a bridge is used; each arm is resonant at the

"TO ATTAIN STILL HIGHER STANDARDS OF SERVICE..."

"An asset in which the Nickel Plate Road takes great pride is the high standard of service which it renders to the shipping public. With its record for outstanding performance during the war years back of it, the Nickel Plate is looking forward to the utilization of new technological developments, such as radio and teletype, in order to attain still higher standards of service and usefulness."

President,
The New York, Chicago & St. Louis R.R. Co.

To fulfill completely its promise of increased rail efficiency, railroad radio equipment must be so designed that individual system units, such as transmitters, receivers, power supplies, and remote control units, will be readily accessible for inspection and quickly removable for service, replacement, or relocation.

Realizing the importance of these requirements, the Farnsworth Mobile Communications Division has engineered its railway communications equipment on the bases of *standardized design* and *unitized construction.*

Practical results from the application of these two engineering principles include the facts that—

(1) The basic components of Farnsworth systems, whether of space-radiating or inductive type, are *separate units,* which can be *quickly disassociated* from a system, either for maintenance or relocation.

(2) The same receiver, transmitter, or remote control unit is usable for wayside, mobile, or relay installations, thus providing *complete interchangeability* of basic equipment throughout any Farnsworth communications system.

(3) *Space-radio and inductive type* Farnsworth *units can be interchanged,* whether a part of mobile or stationary installations, and can be *readily utilized in combination* to meet varying railway operating conditions and requirements.

These are a few of the many engineering features incorporated in Farnsworth railway communications equipments to guarantee *maximum availability and flexibility with simplified, low-cost maintenance.* Farnsworth Television & Radio Corporation, Dept. E-4, Fort Wayne 1, Indiana.

FARNSWORTH TELEVISION & RADIO CORPORATION

Farnsworth Radio and Television Receivers and Transmitters • Aircraft Radio Equipment • Farnsworth Television Tubes • Halstead Mobile Communications and Traffic Control Systems for Rail and Highway • the Farnsworth Phonograph-Radio • the Capehart • the Panamuse by Capehart

A New BEACON ANTENNA

At the instigation of Link Radio of New York, the Workshop has recently developed a new antenna for their main station police radio transmitting and receiving on the new 152-162 mc band. Essentially, it is a collinear coaxial beacon, vertically polarized, and entirely enclosed in a non-metallic pressurized housing. The pattern has been flattened out to give high gain in comparison to an ordinary dipole. This means much greater coverage with the same power input.





The above graph shows an actual test plot of the vertical patterns of the new Workshop antenna and a conventional half-wave dipole. Note that the power output along the horizon is approximately 2½ times the power output of the dipole. Exhaustive field tests under actual operating conditions even have shown power gains over 4 times that of the dipole.

PATENT APPLIED FOR

This new antenna is an example of Workshop specialization in antenna manufacture. If you have an antenna problem in the high-frequency spectrum — from 40 mc up — you will find our exceptional design, measurement and test facilities well adapted to a solution of your problem. Write or phone the details.

THE WORKSHOP ASSOCIATES
INCORPORATED
Specialists in High-Frequency Antennas
66 NEEDHAM STREET, NEWTON HIGHLANDS 61, MASS.

rejection frequency and the resonant dissipations in the arms are equal, therefore the bridge is balanced and does not pass that frequency.

An analysis made of the filter using circle diagrams shows that the



Basic Wheatstone bridge rejection filter eliminates pilot frequencies from carrier communication and telemetering circuits

Q of the inductors determines the narrowness of the rejection band. Two rejection filters in tandem tuned to slightly different frequencies can be used to reject a wider band than one alone. This practice preserves the sharpness of the rejection band.

Inertia Throat Microphones

By L. G. PACENT
Pacent Engineering Corp.
New York, N. Y.

and E. H. GREIBACH
Sonotone Corp.
Elmsford, N. Y.

COMMUNICATION from such noisy locations as airplanes and machine shops can be made using throat microphones. These units pick up the vibrations of the larynx transmitted directly through the throat walls rather than the atmospheric vibrations. Thus they respond to speaking but are relatively insensitive to air-borne noise.

The throat vibrations of speech are weak in overtones. To compensate for this, a rapidly rising response characteristic is required of the magnetic inertia microphone. This requirement necessitates setting the resonant frequency in the



DONUT-SHAPED. The extreme compactness, shape and mounting arrangement of Sprague Type 50P Capacitors offer many unique design possibilities in sealed assemblies where self-contained protection for the capacitor is not needed.

***HYPASS 3-TERMINAL NETWORK.** Sprague Hypass Capacitors are unique in that they do not resonate at frequencies as high as 150 megacycles or more. They are of great advantage where wide frequency bands must be filtered or by-passed. Two terminals are connected in series in the circuit. The third connects to ground.

***VITAMIN Q WITH HERMETIC GLASS-TO-METAL SEAL** The Sprague achievement of perfecting glass-to-metal seals has resulted in many interesting Capacitor and Resistor developments. These include Capacitors sealed in glass tubes and having maximum flash-over distance between terminals. Impregnated with famous Sprague VITAMIN Q, these units are ideal for operation at extremely high voltages and high ambient temperatures.

3 RECENT CAPACITOR TYPES *Worth Knowing*

Sprague engineering leadership extends to Mica, Dry Electrolytic and countless Paper Dielectric Capacitor types in addition to those illustrated above. Sprague engineers welcome the opportunity to make recommendations based on your specific requirements.

SPRAGUE

PIONEERS OF ELECTRIC AND ELECTRONIC PROGRESS

*Trademarks Reg. U. S. Pat. Off.

SPRAGUE ELECTRIC COMPANY, NORTH ADAMS, MASS.

All Engineers and Designers of

MOTORS
GENERATORS
MAGNETOS
REMOTE INDICATORS

should consider

PERMANENT
MAGNETS

These Permanent Magnets are representative of some that have been designed for Motors, Generators, and allied equipment. If you have not used Permanent Magnets for these applications . . . consult us for engineering advice.

Write for Technical Bulletin—"Permanent Magnets for Industry," containing valuable data on design, production characteristics and applications of Permanent Magnets.

THE ARNOLD ENGINEERING COMPANY

SUBSIDIARY OF ALLEGHENY LUDLUM STEEL CORPORATION

147 EAST ONTARIO STREET, CHICAGO 11, ILLINOIS

Specialists in the Manufacture of
ALNICO PERMANENT MAGNETS

vicinity of three to four kilocycles. Although so high a resonant frequency improves intelligibility of the microphone signal, it decreases the output. For sound powered com-



Curves A and B show response for single and double resonant units respectively. curve C shows effect of damping the double resonant microphone to improve quality

munication systems, high output from the microphone is necessary. This requirement can be met by introducing a second resonant frequency in the vicinity of one kilocycle.

Objective Testing of Throat Microphones

By E. H. GREIBACH

Sonotone Corp.
Elmsford, N. Y.

LABORATORY TESTING of throat microphones and bone conduction earphones requires a counterpart of the human organ under study. In both cases the transmission characteristic of the skin layer enters into the unit, therefore a single unit can be used in testing either element. The artificial throat is essentially a dynamic loudspeaker, but has masses, springs, and pads to produce the required impedance vs frequency characteristic. Viscoloid pads have given a fair approach to the loss component of the skin, but it is difficult to simulate both skin stiffness and resistance by even a combination of pads.

In operation the driving coil is fed from a resistance-capacitance network to produce uniform velocity of the testing platform over the frequency range. The filter pad is placed on the platform and then the throat microphone. In this way the microphone sees a simulation of the impedance looking through the skin into the throat. By driving the plat-

CLOTH *is what we make it*



filled

Intermesh treatment with various types of plastics, starch, etc., to produce a natural cloth finish with various properties such as—toughness, abrasion, resistance, flex strength, grease and oil impermeability, dimensional stability, etc.

impregnated

Interthread treatment with various newer plastics to give bulk strength, stiffness, transparency, resistance to moisture, mildew, heat, cold, chemical actions, etc., retaining cloth surface appearance.



coated

Surface treatment on a cloth structure to meet a great variety of functional and decorative uses.

HOLLISTON
Special Purpose Fabrics

THE HOLLISTON MILLS, INC., NORWOOD, MASSACHUSETTS

FRANKLIN LAMITEX

(LAMINATED BAKELITE)

is so versatile!

Pictured below just a few of the many thousand various parts we at FRANKLIN FIBRE-LAMITEX have furnished completely machined to exacting specifications for countless uses.

SHEETS, RODS and TUBES,

FABRICATED OR MOLDED PARTS



FRANKLIN LAMITEX and VULCANIZED FIBRE are highly machineable. We will machine parts if you lack facilities—or furnish sheets, rods, and tubes. Both LAMITEX and FRANKLIN FIBRE can be drilled, tapped, turned, threaded, punched, shaved, bored, reamed, sawed, milled or completely fabricated into automatic screw machine parts.

Check these FRANKLIN LAMITEX characteristics

High dielectric strength
Low power factor
Low moisture absorption
Remarkable dimensional stability
High mechanical strength
Low co-efficient of thermal expansion
Low in weight (about half that of aluminum)
Unaffected by solvents and oils
Unaffected by most organic acids, dilute mineral acids or salt solutions

SEND FOR CATALOG CONTAINING COMPLETE DATA.

FRANKLIN FIBRE-LAMITEX CORP.

WILMINGTON, DEL. — 187 LAFAYETTE ST., NEW YORK 13, N. Y.

form with a receiver and measuring the current generated in the driving coil the unit can be used as an artificial mastoid.

Sound Recording

Wire Recording

By D. W. PUGSLEY
General Electric Co.
Schenectady, N. Y.

POSSIBLE USES of wire recording include that for the home, commercial and public announcements at broadcast stations, pocket recorders, and recording in such vibrating locations as cars, trains, and aircraft. The long, continuous records which can be made recommend wire for recording telephone conversations, air and rail traffic messages, and recording for students, the blind, and the sick.

At the present stage of the art, satisfactory frequency response can be obtained at two feet per minute, with a 40-db dynamic range, and three percent total harmonic distortion. Recording, splicing, dubbing, and erasing are easy. Noise is 40 db below signal; there is freedom from interference from external vibration. Records can be played back many times, require small storage space, and are not easily damaged.

However, driving the record and loading the magazine are difficult. The blank is expensive. Because of the difficult and lengthy production of recordings on wire commercially produced recordings in quantity are unlikely.

Wire Recorder Head Design

By T. H. LONG
C. G. Conn, Ltd.
Elkhart, Ind.

TESTS ON HEADS through which the magnetic wire runs in a groove showed that the accumulation of magnetic mud in the gap lowered the response to 5,000 cps by 15 db at a wire speed of two feet per second. Low frequencies were less effected. Also lifting of the wire slightly from the bottom of the groove reduced the output 3 db at 5,000 cps, although it did not affect the low frequency output. In addition to these practical defects, there is the theoretical magnetic defect that flux penetration is less for a curved surface than for a flat one.

An improved head design was de-

Announcement

Federated Metals Division, American Smelting and Refining Company, is happy to announce that as of February 1, 1946, it has completed arrangements with the Gardiner Metal Company of Chicago to produce and market the entire line of Gardiner *extruded* solder.

THESE INCLUDE:

SOLID WIRE
ACID CORE
ROSIN CORE
RIBBON
EXTRUDED BODY SOLDER

FMD Federated

As a result of this arrangement, Federated's capacity to produce extruded solders has been broadened. This means a further improvement in service for Federated customers. The combined facilities and experience make available to extruded solder users everywhere, a fund of knowledge and quality of service second to none. These advantages, plus precise metallurgical control, assure buyers of uniform, high quality extruded solders.

Federated Metals Division
American Smelting and Refining Co.
120 Broadway, New York 5, N. Y.
Nation-wide service with offices
in principal cities

ALUMINUM · BRASS · BRONZE · BABBITT · SOLDER · TYPE METAL · DIE CASTING ALLOYS · ZINC DUST



Haydoneered Timing will provide the heartbeat for tomorrow's industry. New timing devices—now measuring and motivating thousands of functions in war plants all over the country—will find even greater scope in the flood of peacetime production to come.

If you are planning a postwar product with movement requiring regulation, let Haydon Engineers lend you a hand. /

AC TIMING MOTOR

Available 450 RPM to 1 REV. per month: manufactured to your specific voltage, frequency, speed and torque requirements.



HAYDONEERED TIMING

Haydon

MANUFACTURING COMPANY
* INCORPORATED *

Forestville, Connecticut

WRITE TODAY FOR CATALOG

veloped after observing that the playback response was 8 db higher when the wire was running across the top of the lamination than when it was at the bottom of the groove. The new head with either open or closed winding duplicates the performance of conventional closed winding types if stainless steel wire having a coercive force of about 175 oersteds and usual retentivity is used.

By lengthening the gap to about



Experimental model of open head. Level winding technique, ease of cleaning, and greater high frequency response are obtained

half an inch, level winding can be used. The record is played back and forth along the gap, distributing wear and helping to keep the surface clean. It was found desirable to fill the gap with hardened beryllium copper to prevent undercutting of the gap material and eventual shunting of the gap by magnetic mud.

B-H Tracer

By T. H. LONG and G. D. MCMULLEN
C. G. Conn, Ltd.
Elkhart, Ind.

MAGNETOSCOPE measurements show that variations of coercive force over the length of record wire are sufficient to produce several decibels variation in the low-frequency playback. Changes in wire tension were observed to produce appreciable instantaneous changes in coercive force and retentivity.

The instrument used for these measurements consisted of a magnetizing coil capable of 1,500 ampere turns per inch, although some wires will require more than 2,500 ampere turns per inch for saturation. A balance coil was used to exclude the

No electrical equipment can be any better than its insulation



This varnish was chosen to meet the exacting insulation requirements on transformers for aircraft electric power . . . .

G-E INSULATING VARNISHES 1673 & 1696

Clear G-E varnishes . . . temperature resistance . . . flexibility . . . long life . . . for transformers of all kinds

. . . and the same varnish can protect a fluorescent ballast with long-lived, heat-resisting insulation.

General Electric is one of the world's largest and most experienced manufacturers of insulating varnishes. The capacity to produce millions of gallons for myriad war applications and 45 years of experience in varnish research and manufacture are now available to peace industry. Strict G-E Quality Control assures uniformity of product in every shipment of G-E Insulating Varnishes. For details consult your local General Electric Merchandise Distributor. Or write direct to Section RIMA-4614, Resin and Insulation Materials Division, Chemical Department, General Electric Company, Schenectady 5, New York.

GENERAL ELECTRIC

CD 46-13

G. E. OFFERS A COMPLETE LINE OF INSULATING MATERIALS



This is the invariable first reaction of engineers and consumers when meeting Marion Glass-to-Metal Truly Hermetically Sealed Instruments face-to-face. Let us begin by saying that zero adjusters correct for mechanical changes in an instrument caused by drift of the hair springs, ageing of the moving system, and are often used to correct (but incorrectly) errors brought about by unbalance of the moving system. Marion "hermetics" eliminate the need for zero adjustment for the following reasons:

Drift-free Springs: Marion "hermetics" use special silvered beryllium copper hair springs which are essentially drift-free. And the instruments as a whole are thoroughly aged at 170° to 180° F for at least 48 hours, assuring permanent "set" to the components of the moving system. These factors permit overloads far in excess of normal specifications, without permanent zero shift of the instrument.

"Apologist for Error": When a panel instrument is overloaded and its pointer is slammed, re-setting with the zero adjuster *does not* correct the error caused by the unbalance of the moving system. It only apparently corrects this error, and conceals its magnitude. Slammed instruments should be repaired or replaced if stated accuracy is to be maintained, and not just covered up by that *apologist for error*, the zero adjuster.

Independent Tests . . . by private and governmental laboratories in the United States and Canada prove that Marion "hermetics" sustain zero setting under severe and continuous shock, vibration, temperature and humidity cycling. Maximum permanent zero shift recorded on any "hermetic" by any laboratory has been ½ of 1% after completion of any and all combinations of the foregoing tests.

Marion Glass-to-Metal Truly Hermetically Sealed

2½" and 3½" Electrical Indicating Instruments

Write for 12-page brochure

MARION ELECTRICAL INSTRUMENT CO.
MANCHESTER, NEW HAMPSHIRE
EXPORT DIVISION
458 BROADWAY · NEW YORK 13, N. Y. U. S. A.
CABLES: MORHANEX

IN CANADA: THE ASTRAL ELECTRIC COMPANY, SCARBORO BLUFFS, ONTARIO

influence of air flux from the measurements. The detector coil was centered in the magnetizing coil where nearly uniform flux can be expected.

A magnetizing frequency of 200 cps was used. The amplifier was designed to have wide frequency response and negligible phase shift because of the necessity of reproducing the irregular B-H curve. The time constant of the integrating circuit was 100 times the half period of the fundamental frequency. Hum bucking as well as complete filtering was necessary in the power supply to eliminate power frequency disturbances in the trace. The B-H curve was reproduced on a conventional oscilloscope.

Magnetic Tape Signal and Noise

By D. E. WOOLDRIDGE
Bell Telephone Labs., Inc.
New York, N. Y.

THEORETICAL ANALYSIS of perpendicular recording on tape, made to determine what properties of tape and associated magnetic elements affect noise and signal output levels, indicate methods of decreasing noise and increasing signal.

Although magnetic theory is still insufficient to correlate tape noise with any measurable magnetic property, it can be said in general that noise is less in demagnetized tape than in saturated tape. High signal to noise level should be produced by tapes having high coercive forces. To meet this requirement, vicalloy tape having a coercive force of 200 to



Using vicalloy tape perpendicularly magnetized and offset pole pieces, the characteristic of curve A was obtained. Curve B shows characteristic of old unit for comparison

more efficient ...in miniature

ACTUAL SIZE

At the press of a button, the modern fire siren screams its warning for miles. In contrast, it took a husky man to strike an iron tire hard enough, with a heavy sledge, to sound an alarm even over a comparatively small area. Greater efficiency in miniature is as evident in the fire alarm as it is in the Electronic Tube.

TUNG-SOL Miniature Tubes are more impervious to the effects of shock and vibration as they are constructed with smaller, lighter parts. The glass button base has better dielectric properties than the old style bases. Lower lead inductance, lower inter-element capacities, and higher mutual conductance are characteristics of TUNG-SOL Miniatures that assure superior performance in high frequency currents. The advantages of smaller lighter tubes in over-all set design needs no amplification.

The TUNG-SOL engineers who developed TUNG-SOL Miniatures are at the service of radio set and other electronic equipment manufacturers. They will be glad to aid in using Miniatures to the best advantage, by advice as to circuits and tube selection. Of course such consultation is held in strictest confidence.

TUNG-SOL

vibration-tested

ELECTRONIC TUBES

TUNG-SOL LAMP WORKS, INC., NEWARK 4, NEW JERSEY

Sales Offices: Atlanta • Chicago • Dallas • Denver • Detroit • Los Angeles • New York

Also Manufacturers of Miniature Incandescent Lamps, All-Glass Sealed Beam Headlight Lamps and Current Intermittors

Permoflux Designs Assure Faithful Reproduction!

Because Permoflux Speakers excel in translating the tone capabilities of carefully designed circuits, more and more of the country's outstanding radio manufacturers are specifying them as preferred equipment. Manufactured in a full range of true-dimensioned sizes for every power handling requirement, Permoflux Speakers provide the answer to today's growing demand for better tone quality.

TRADE MARK
PERMOFLUX
PERMOFLUX CORPORATION
4900 WEST GRAND AVE., CHICAGO 39, ILL.

PIONEER MANUFACTURERS OF PERMANENT MAGNET DYNAMIC TRANSDUCERS

250, five times that of earlier tapes, was developed.

Output signal level is limited largely by a region of high reluctance in the pole piece tips. The best material for the pole pieces is already available, molybdenum permalloy. By using wider pole pieces (0.041 inch by 0.040 inch), offset so that the leading edge of one is opposite the following edge of the other, a self-supporting head requiring fewer turns to saturate the tape and giving greater output was obtained. A-c bias is both quieter and capable of giving higher level, high quality recordings than other forms of bias.

Combining these improvements, high quality recordings equalized from 100 to 8,000 cps with a useful volume range of 50 db at a tape speed of 16 ips were obtained.

Phonograph Reproducer Design

By W. S. BACHMAN
General Electric Co.
Bridgeport, Conn.

STRAINED WIRE resistance reproducer design is carried out. The techniques of analyzing the mechanical components are applicable to other reproducer types. Because the output voltage of the polarized strained wire is proportional to its displacement, this type of reproducer is useful in measuring recorded frequency characteristics. A variable reluctance reproducer having low mechanical impedance by virtue of its small moving mass is designed. Both types of reproducer have the supporting arm resonance damped by the suspension compliance.

Studying Disk Performance

By H. E. ROYS
RCA Victor Division
Indianapolis, Ind.

TOOLS AND TESTS for measuring performance, primarily of lacquer recordings and pressings, have been advanced to assure improvements in record fidelity. Cutting force can readily be measured by replacing the permanent magnet field of a cutting head by an a-c field, reorientating the armature assembly to respond to tangential rather than radial forces, and feeding the armature coil output to a meter. Measurements using such a technique indicate the self-regulating effect of a free head

a rigid steel plate is the foundation of a GOOD RHEOSTAT

The first Ward Leonard Rheostats were built with a steel plate foundation. Its rigidity protected the insulating enamels, proved an excellent dissipater of heat and gave a substantial foundation for contacts, terminals and control members. Many of those early Rheostats are in active service today.

While the present day Ward Leonard Plate Type Rheostats have been modernized, made even smoother in action and offer many more steps of control in smaller diameters, they are still built on a rigid steel plate foundation.

With the wide range of types and sizes of Ward Leonard Rheostats you will find the one to meet your requirements—from the smallest electronic to the largest industrial application. Send for Rheostat Bulletins today.

Visit our booth No. 100 at the
RADIO PARTS AND ELECTRONIC EQUIPMENT SHOW
STEVENS HOTEL, CHICAGO, MAY 13 to 16

WARD LEONARD
RELAYS • RESISTORS • RHEOSTATS
Electric control devices since 1892

WARD LEONARD ELECTRIC COMPANY
32 SOUTH STREET, MOUNT VERNON, N.Y. • OFFICES IN PRINCIPAL CITIES



LET'S LOOK AT LINES

that build Tracing Cloth Preference

If you could pick up a line freshly inked on Arkwright Tracing Cloth, you'd *see* your preference. Your line retains its edge and doesn't go flat or "mushy". It prints like a taut wire, even re-inked over heavy or repeated erasures.

This evenness and crispness of line, coupled with the unusual transparency of Arkwright Cloths, assures contrasty, easy-to-read prints . . . and the transparency is permanent. It is obtained by special mechanical processing. Arkwright Cloths do not cloud up nor become brittle with age, because no surface oils at all are used.

Want a treat? Send for working sample. Rule lines. Notice how they flow on evenly. Erase. Hold up to light and see if you can see the markings of a ghost. You'll then have a real preference. Arkwright Finishing Co., Providence, R. I.

★

Sold by leading drawing material dealers everywhere

★

Arkwright
TRACING CLOTHS
AMERICA'S STANDARD FOR OVER 20 YEARS

against a head controlled by an advance ball. The self-regulating action of the floating head tends to maintain a constant recorded signal level. Effects of lacquer hardness, turntable drive, and cutter bounce can also be determined.

Intermodulation measurements of distortion, which give closer correlation with listener tests than harmonic distortion measurements, show the effects of tip radius and processing of pressings. These tests are easier to apply than harmonic tests because shifting of phase and frequency caused by turntable flutter do not affect the results.

Sound Recording in Business

By L. D. NORTON
Dictaphone Corp.
Bridgeport, Conn.

IMPROVEMENTS in electrical recording and reproducing techniques, plus the additional facilities available if dictaphones can be connected to electrical speech channels, make electrical dictaphones feasible. To compete with the acoustic instrument of proven reliability and simplicity, electrical dictaphones must be equally simple and reliable in operation. From a critical examination of requirements for business recorders standards were proposed.

Industrial Electronics

Development of Magnetrons

By W. C. BROWN
Raytheon Mfg. Co.
Waltham, Mass.

EARLY LABORATORY magnetrons operated at relatively low frequencies, at low efficiencies, and delivered low



Looking into the cavities of a 300 kw magnetron, cover removed

ONE OF the big advantages of using graphite for anodes is the high thermal emissivity of this remarkable material. Because "National" graphite is almost an ideal black body, it is a nearly perfect heat radiator. In fact, no other anode material even approaches "National" graphite in this respect.

This means that anodes of "National" graphite will operate at lower temperatures for a given amount of energy dissipated. Thus, *all* tube parts will operate at a lower temperature, resulting in less distortion and more uniform tube characteristics.

In addition to this important property, here are others that, combined, make "National" graphite a most valuable anode material: High electrical and thermal conductivity, low electron emission, extremely low thermal expansion, and no melting point! Furthermore, graphite can be machined into intricate shapes to very close tolerances.

The full story on the possibilities of graphite for your anodes may be had by getting in touch with National Carbon Company, Inc.

This graph shows the total energy radiation from graphite and other anode materials in watts per sq. cm.



NATIONAL CARBON COMPANY, INC.

Unit of Union Carbide and Carbon Corporation
The word "National" is a registered trade-mark of National Carbon Company, Inc.

UCC

General Offices: 30 E. 42nd St., New York 17, N. Y.
Division Sales Offices: Atlanta, Chicago, Dallas, Kansas City, New York, Pittsburgh, San Francisco


Type RT-20
Types RT-12 and RT-14 (heavier)
Type RT-15
Type RT-13
Type RT-10
Types RT-1, RT-2, RT-4, RT-5
Types RT-6, RT-8, RT-9
There's a REX-TUBE Type to Fit the Most Exacting Application

Rex-Tube isn't a cure-all, of course. But within its capacity this rugged, flexible metal hose will handle efficiently and economically just about anything you give it to do. There are sizes and types, for example, that range from oil can spouts . . . to heavy duty tubing used in steaming out tank cars.

Production men throughout industry know that many of their exacting problems can be solved with Rex-Tube or with the other flexible metal hose products in the complete C.M.H. line, including: Rex-Weld, Rex-Flex S.S., Avioflex and Cellulined. We can help you, too! Write today for Booklet E-144.

Flexible Metal Hose for Every Industrial Use

ARMY E NAVY

CHICAGO METAL HOSE CORPORATION

MAYWOOD, ILLINOIS

Plants: Maywood and Elgin, Ill.

power. Recent, rapid development of magnetrons has resulted in tubes delivering megawatts in the 3,000 megacycle range at efficiencies up to fifty percent. In the 10,000-mc range, up to 300 kw are developed.

Except for the power supply, the magnetron is a complete transmitter within itself. Development of the packaged magnetron, which has an attached permanent magnet, has reduced bulk and weight of the magnetron to the point where it is a simple, reliable tool for electronic engineers.

Hydrogen Thyratron

By H. H. HEINS
Sylvania Electric Products, Inc.
Emporium, Pa.

PULSE TECHNIQUES used in navigational equipment such as radar, loran, and shoran, and in communication systems of the pulse modulation types require rapid, high power pulsing. The hydrogen, cold-cathode thyratron was designed to supply the high peak currents and voltages necessary. Because of the short deionization time of hydrogen, rapid switching rates are possible. Electrical characteristics are little changed by a wide variation of temperature.

The hydrogen thyratron can be used for switching capacitor discharge type welding circuits, and in place of spark gaps in induction-heating equipment.

Dielectric Heating

Bp I. E. MOUROMTSEFF
Westinghouse Electric Corp.
Bloomfield, N. J.

LABORATORY TESTS indicate that dielectric heating can be used for disinfecting grain in bulk, sterilizing packaged cereals, making safety glass, gluing wood laminations and shoe soles, and curing textile fibers. It has proven useful in drying enamel insulation on wire, and rolls of paper. Medical doctors have found dielectric heating advantageous in treating common colds and some other ailments, although the effects can be duplicated by other forms of heat treatment. Despite the technical possibility of these applications, initial costs of dielectric heating installations are prohibitive at present.

Dielectric heating depends on the presence of permanent molecular di-

RADIO TRANSMITTERS
by Press Wireless

Radio Transmitter
Model T50CF-1

This modern, 50-kilowatt, 4 to 21 megacycle radio transmitter is actually two transmitters in one. The entire unit may be used as a 50kw transmitter for on-off CW or frequency-shift keying with an FS keyer and may be modulated by a high-level Class-B modulator. Complete controls and an individual power supply for the exciter and driver stage provide a medium-power r-f carrier of 3-kilowatts on CW or FS—separate and independent of the power amplifier section. The separate controls and high-voltage power supply for the PA make this section available as an independent Class-C final amplifier unit for use with a suitable double-sideband Class-B modulator-driver. The PA section may be adjusted for operation as a Class-B linear amplifier when used with a suppressed-carrier exciter or other r-f driver source.

DESIGNED for CW or FS operation, this equipment with companion Modulator Model TM 50-1 will transmit MODUPLEX* where AM and FS signal intelligence appear simultaneously on the same carrier.

MODEL T50CF-1 provides protection throughout for personnel and equipment by elaborate interlocking and automatic recycling control circuits. An automatic-shutdown feature cuts off the transmitter after a preset interval if the external (remote) keying line is idle.

Press Wireless will deliver this high quality transmitter and others of 2,500, 5,000, or 20,000 watts with associated equipment within five months from the receipt of your order.

Descriptive literature sent at your request.

*Trade Mark

PRESS WIRELESS MANUFACTURING
CORPORATION
Executive and Sales Office, 1475 BROADWAY, NEW YORK CITY 18





ARMY E NAVY

Erco TYPE 137-TR

"The Itinerant"

RADIO - TELEPHONE

At your service . . . A compact combination transmitter-receiver that is "going places." It's self-contained and has *everything*. Name your use for low power radio telephone and it will very likely meet your need.

Available for 6, 12 and 32 volt DC or 110 volt 50/60 cycle AC . . . Expected range under average conditions, up to 200 miles or more . . . Power output 18 to 22 watts in the 3 to 6 MC band.

The 137-TR is pretuned and fully crystal controlled . . . Push to talk operation with hand microphone or handset . . . Absolutely foolproof; does not require expert knowledge to set up or operate . . . Altho inexpensive, it is built to the high standards of ERCO quality.

Small airports can use it for traffic control . . . and large ones, too, as emergency equipment. Provides ideal ship-to-shore communication and essential contact in forest, mining, oil producing or other remote areas where point-to-point communication is vital . . . Tell us your requirement and we will give you all particulars.

ERCO

ERCO RADIO LABORATORIES INC

HEMPSTEAD, NEW YORK

Manufacturers of CUSTOM BUILT RADIO APPARATUS

poles in the material to be heated. The choice of frequency depends chiefly upon the ease of load matching and avoidance of standing waves in the work. The wavelength should not exceed one sixteenth the greatest dimension of the work. Dielectric constants of most materials decrease but little with increasing frequency, whereas power factors change variously. Changes of power factor during heating are the greatest load-matching complication.

High powers required for dielectric heating are available. The resnatron and magnetron extend these powers into the centimeter range.

Testing with Pulses

By H. W. LORD
Research Laboratory
General Electric Co.
Schenectady, N. Y.

ADVANTAGES of high-potential testing of motors and transformers using surges or pulses are that (1) winding stresses are similar to those due to switching surges during operation, (2) high voltages are obtainable from small equipment, and (3) shock from the pulse voltage is less dangerous than from other high voltage test equipment.

Improved surge testors can be built using techniques originally developed for radar such as hydrogen thyratrons, pulse forming networks, and pulse transformers. By using a shielded pulse transformer balanced to ground, the bulky, motor driven, synchronous switch commonly used in high voltage test sets is eliminated. In addition, fault display on the oscilloscope screen is made simpler and more sensitive, because a bridge circuit giving zero voltage at balance can be used instead of direct comparison of two high voltages.

A laboratory surge tester suitable for testing fractional horsepower motors and radio transformers was demonstrated.

Radar

Radar Systems Considerations

By D. A. QUARLES
Bell Telephone Laboratories, Inc.
New York, N. Y.

RADAR DESIGN has quickly passed into specialists' field. There has been full interchange of technical information

Specify C-D MICABOND

The power that drives a Diesel Locomotive is Electricity! Electricity generated by huge Diesel Driven Generators . . . generators that depend on C-D MICABOND insulation to stand the high heat and vibration of continuous operation. The small armature illustrated separately is used in your automobile generator . . . it too must give long-dependable service . . . furthermore it must also be economical to produce so it is built on a fast moving assembly line. Accuracy in dimensions is essential in both these uses of C-D MICABOND insulating rings and segments . . . first to insure unfailing service; secondly to facilitate fast economical assembly.

C-D MICABOND is Mica in usable forms. MICA splittings bonded together in sheets and tubes from which segments, rings and other shapes are readily and accurately fabricated. Into every shipment of C-D MICABOND goes a half century of C-D "know-how" . . . your assurance that C-D MICABOND is engineered to do the job for which it is specified.

C-D PRODUCTS

The Plastics

DILECTO—Thermosetting Laminates.
CELORON—A Molded Phenolic.
DILECTENE—A Pure Resin Plastic Especially Suited to U-H-F Insulation.
HAVEG—Plastic Chemical Equipment, Pipe, Valves and Fittings.

The NON-Metallics

DIAMOND Vulcanized FIBRE
VULCOID—Resin Impregnated Vulcanized Fibre.
MICABOND—Built-Up Mica Electrical Insulation.

Standard and Special Forms

Available in Standard Sheets, Rods and Tubes; and Parts Fabricated, Formed or Molded to Specifications.

Descriptive Literature

Bulletin GF gives Comprehensive Data on all C-D Products. Individual Catalogs are also Available.

Continental·Diamond
Engineered Dielectrics

KWC-46

BRANCH OFFICES

NEW YORK 17 • CLEVELAND 14 • CHICAGO 11 • SPARTANBURG, S. C. • SALES OFFICES IN PRINCIPAL CITIES
WEST COAST REPRESENTATIVES: MARWOOD LTD., SAN FRANCISCO 3
IN CANADA: DIAMOND STATE FIBRE CO. OF CANADA, LTD., TORONTO 8

SEE OUR CATALOG IN SWEET'S

Continental-Diamond FIBRE COMPANY

Established 1895 . . Manufacturers of Laminated Plastics since 1911—NEWARK 16 • DELAWARE

between workers both here and in England so that each has used the building blocks of the other. In designing radar, the antenna is the essential element. Used both for transmission and reception, it provides the required illumination pattern which can be specially directed into narrow, fan shaped, or other contoured beams depending upon the intended use of the system.

Angular resolution and range discrimination are limited by a volume of confusion, the cross section of which is determined by beam cross section and whose depth is determined by pulse length. To obtain a narrow beam, high frequencies are necessary in limiting the antenna to physically realizable dimensions. Since the beginning of the war radar has advanced from one meter to one centimeter. Pulses have also become shorter. The figure of confusion has been reduced to about one fifth its earlier volume. However, as shown in the accompanying figure, moisture absorption of these short waves appears to limit the useful radio spectrum at the high frequency end. The spectrum seems to have been explored and is rapidly being conquered and settled.



Moisture absorption of radio waves in the centimeter region is appreciable, also absorption bands from molecules (not shown) are encountered at these short wavelengths

Production of pulses is done commonly by electronically shorting a storage transmission line by such means as the hydrogen thyratron. The produced pulse is coupled to the r-f tube, usually a magnetron delivering megawatts of instantaneous output to the antenna. Where revolving antennas are used, discontinuities that vary with angular posi-

AN ASSEMBLY JOB

That Requires Many Parts and Important Operations

The great assembly floor at Astatic's main plant, Conneaut, Ohio, hums with an ever-increasing activity, these days, as every effort is put forth to meet production quotas for radio, phonograph manufacturer and parts jobber demands. The assembling of Astatic Microphones, Phonograph Pickups, Cartridges and Recording Heads, requires skill obtained from careful training and long experience in handling the many small parts required for these products. That they shall meet Astatic's high standards of operating efficiency, all operations are closely supervised and each product individually tested before released for shipment.

THE Astatic CORPORATION
ASTATIC
CONNEAUT, OHIO
IN CANADA: CANADIAN ASTATIC LTD., TORONTO, ONTARIO

Steel Sheets Thinner Than a Human Hair?

Yes . . . and they'll soon have a lot to do with many electrical products manufactured for home, farm and industry.

These special electrical sheet steels — thinner than this sheet of paper — are being made on the Armco precision cold strip mill pictured above.

During the war they were used in combat walkie-talkies and radar equipment. Now these ultra-thin steels are going into high-quality radio sets, television sets and other electrical devices.

This is one of the latest examples of research by Armco.

Other kinds of ARMCO Electrical Steel Coils and Sheets are ready for your new products, too. You'll find a correct Armco grade for every need. And you'll get steel that is flat, clean-surfaced and ductile — steel of top magnetic properties and with consistently low core loss and exceptional permeability.

For detailed information about specific applications, just address The American Rolling Mill Company, 1251 Curtis Street, Middletown, Ohio.

Export: The Armco International Corporation

The American Rolling Mill Company

ELECTRICAL ARMCO SHEET STEELS

Kester has the
RIGHT FLUX
for Every Solder Job . . .

• You can always get the right flux, from Kester. . . . a flux you *know* will properly clean, prevent oxidation, make way for a tight bond that will resist shock, vibration or bending as desired, and eliminate soldering failures.

• During Kester's 47 years of experience, hundreds of Kester flux formulas have been time-tested in laboratory and industry, to establish exact specifications for every flux need. Among them is the ideal flux formula for you.

• Write us, and Kester engineers will consult with you, without obligation.

KESTER SOLDER COMPANY
4204 Wrightwood Ave., Chicago 39, Illinois
Eastern Plant: Newark, N. J. Canadian Plant: Brantford, Ont.

KESTER
Cored Solders
STANDARD FOR INDUSTRY

tion tend to pull the magnetron frequency. The impedance irregularity is increased by long transmission paths, thus careful design is required.

The receiver, protected during transmitter operation by a gas filled, TR duplexer tube, receives the reflected pulse. The first design problem is to maintain frequency tracking with the transmitter. Beating oscillators are used. In the microwave range, single cavity, reflex, velocity-modulated tubes are common. Their frequencies are



Reflex, velocity modulation, beating oscillator shown full size.

stabilized by either controlling the repeller voltage or thermally tuning the cavity. Crystal detectors whose noise closely approximates their theoretical resistance over the spectrum are used as converters in preference to vacuum tubes whose noise factors increase with frequency.

Although early practice was to design the narrowest i-f band consistent with pulse width, experience has indicated that, although noise increases with bandwidth, the increased resolution of the amplified pulse and smaller grain size of the noise from wideband channels gives a clearer picture. Bandwidths up to

DeJUR

BUILDS GREAT LITTLE METERS

The precision-built DeJur 1½" Meters are doing a man-sized job on many applications where space must be conserved.

DeJur EXTERNAL PIVOT construction gives maximum accuracy — reduces pointer-rocking, and wear on bearing surfaces —greatly lengthening the life of the instrument.



The DeJur Model 120 Miniature (1½") Meter

Compact, Trouble-Free Modern Design



External Pivot (As Used by DeJUR) — Internal Pivot (Not Used by DeJUR)

DeJUR RHEOSTAT – POTENTIOMETERS ARE PRECISION BUILT...



Send details of your requirements to DeJur. Our engineers will gladly advise the correct instrument to meet your needs.

in a wide line of models for many electronic and general electrical applications. They are electrically and mechanically engineered to meet the precise requirements of electrical manufacturers.

The 11 Watt Model 275 (illustrated) is typical of DeJur Potentiometers. Rugged yet light in weight, it is built to give outstanding service under the most severe operating conditions.

WRITE FOR THE LATEST DeJUR CATALOG

DeJUR U.S.A.

DeJUR-AMSCO CORPORATION

LONG ISLAND CITY 1, N. Y.

AMMETERS . . . VOLTMETERS . . . POTENTIOMETERS



Required:

Battery charger to maintain, fully charged at all times, the 12 volt 6 cell heavy duty battery; to rapidly recharge at 12 ampere rate and to automatically reduce to trickle rate at proper time.... Source of power—115 volts AC 60 cycle power line.

We solved this problem by designing the necessary rectifier power pack (to convert the AC to DC)—the heavy duty transformer to step this power down to 12 volts—the automatic charge rate control—and the heavy duty, weatherproof steel housing ... We had designed and built another rugged, first quality B-L Rectifier Power Pack unit.

Why a *metallic* rectifier? Because the B-L Rectifier is outstanding in:

1. *Durability.*
2. *Trouble-free long life.*
3. *The elimination of current reversals during primary power supply failures.*
4. *Freedom from atmospheric damage.*

What is your problem?

SELENIUM B-L METALLIC RECTIFIERS COPPER SULPHIDE

THE BENWOOD-LINZE COMPANY

1815 LOCUST STREET ST. LOUIS 3, MO.

Long Distance Telephone CEntral 5830

Designers and Manufacturers of Selenium and Copper Sulphide Rectifiers, Battery Chargers and DC Power Supplies for practically every requirement.

ten megacycles at either 30 or 60 megacycles are used.

The results are displayed by methods now familiar to all. Cathode-ray focusing by permanent magnets instead of electromagnetic focusing is used, thereby reducing power supply requirements and stabilizing the focus. Techniques are much like those of television with the addition of means to expand portions of the display and to distinguish between fixed and moving objects.

In military applications for precise target location, lobe switching and conical scanning combined with servo tracking are used. Computing systems use the tracking motion to anticipate future target positions. The art has been adequately treated elsewhere.

Marine Radar for Peacetime Use

By L. H. LYNN and O. H. WINN
General Electric Corp.
Schenectady, N. Y.

EXPERIMENTS ON A Great Lakes ore boat using a modified military shipborne search radar indicated the increased navigational safety and saving of shipping time especially during periods of low visibility. However, the merchantman can not economically carry the large, highly trained personnel required to operate military radar. Therefore a simpli-



Antenna pedestal houses r-f circuits and scanning mechanism of the simplified maritime radar



PROBLEMS

(MAYBE YOURS)

HAVE ANSWERS (MAYBE OURS) ■ ■ ■

if you know where to look!

Special problems of lubrication, parting, coating and impregnation are all about us in the electronics field. Those emphasized above are just a few—typical of the "lesser" vexations with "major" consequences.

Our first job is to *spot* such problems. Our second is to *solve* them.

To help do both, Acheson Colloids Corporation has just published a new 16-page treatise on the *versatility* and the *usefulness* of that unique material with so many unique properties—"dag" colloidal graphite. It gives properties and applications. It contains dozens of illustrations and columns of data. It covers dispersions in water, oil, volatile hydrocarbons, glycerine, alcohol, resins, waxes and other carriers.

Send for it. It may open your eyes—both to *problems* which are costing you money, and to their *answers*. JMLco A-D1

ACHESON COLLOIDS CORPORATION, Port Huron, Michigan

Write for our new bulletin on the Versatility and Usefulness of dag COLLOIDAL GRAPHITE

Dept. DD-5
Gentlemen: Please send your new Bulletin No. 460
NAME_____
POSITION_____
FIRM_____
ADDRESS_____
ZONE No._____ STATE_____
OUR PRESENT OIL SUPPLIER IS_____
(Lubricants containing "dag" colloidal graphite are available from major oil companies.)

1917 1946

MODERN COIL WINDINGS

We'll Stick to Coil Windings

The pressure of wartime production forced many manufacturers into strange paths . . . . we were fortunate that all of our increased facilities could be devoted to coil windings.

Experience has proved to us that superior coil windings result only from continuous attention to their design and production.

We are determined that our reputation for windings of highest quality . . . a reputation earned during 29 years of service to industry . . . . shall be maintained.

That's our business and we're going to stick to it.

COTO-COIL CO., INC.

COIL SPECIALTIES SINCE 1917

65 PAVILION AVE. PROVIDENCE 5, R. I.

fied unit has been developed for merchant marine use.

Because of the simplicity of interpreting the indications, a plan position type indicator is used. Controls are reduced to those necessary to adjust the instrument, select range, and take bearing. Others are available only for installation and service adjustment. The equipment is housed in two units, one in the pilot house, the other at the antenna location. A motor-generator supplies power from the ship's mains.

Airborne Radar for Navigation and Obstacle Detection

By R. C. JENSEN and R. A ARNETT
General Electric Co.
Schenectady, N. Y.

PUBLICITY RECENTLY given radar by newspapers and technical magazines has caught the public imagination. Stimulated by aviation accidents, people have proposed radar for navigation and obstacle detection by aircraft. However limitations to present radar restrict its application.

For observing the ground, as in military applications for bombing, the optimum radiation pattern is one for which the intensity reaching the ground follows the squared cosecant of the angle from the beam axis. However, the display from such a pattern fails to indicate relative heights of objects. Other beams can be used, each with its particular inadequacies.

Sharp beams are necessary to provide adequate resolution of objects. The navigational necessity of scanning a wide area with a narrow beam cannot yet be solved within the carrying capacity of the plane. Before the equivalent three dimensional resolution and range accuracy that is now possible for plan position radar can be achieved with lightweight airborne equipment, many electrical and mechanical engineering problems are to be overcome.

Shoran Precision Radar

By STUART W. SEELEY
Radio Corp. of America
New York, N. Y.

FOR NAVIGATION at short range, shoran is more accurate than loran. Used initially to guide bombers and reconnaissance planes over Europe,



TO THE MOON AND BACK...VIA BLAW-KNOX

Because we have been a confidential advisor to the Army Signal Corps since long before World War II it was only natural that Blaw-Knox should, in a special way, participate in the sensational earth-to-moon contact... The 100 ft. tower, which carries this double 64 dipole antenna, is a Blaw-Knox product.

BLAW-KNOX DIVISION
OF BLAW-KNOX COMPANY
2077 Farmers Bank Building, Pittsburgh, Pa.

BLAW-KNOX
VERTICAL RADIATORS
FM & TELEVISION TOWERS

Seven Blaw-Knox plants have been awarded the Army-Navy "E", and have regularly received renewal stars for continued high achievement in the production of war material.

VALPEY FREQUENCY CONTROL

Valpey Crystals .... the Heart of Modern Communication

DEPT. OF CONSERVATION . . .

CIVILIAN AIRCRAFT . . .

Finer, longer lasting, lower cost crystals than ever before. We solicit inquiries from "hams" —write for distributor's name in your vicinity.

VALPEY CRYSTAL CORPORATION
HOLLISTON, MASS.

AMATEUR . . .

MARINE AND POLICE . . .

Valpey CRYSTALS

CRAFTSMANSHIP IN CRYSTALS SINCE 1931

shoran can provide precise navigational fixes close to the base stations. The principle of operation is that of measuring the interval between transmission of a pulse by the plane and the return of echoes from fixed reradiation stations. There is no signal coordination between stations. The fixed transmitters are triggered by the pulse radiated from the plane. By determining the roundtrip transmission interval between each of two stations, the navigator locates his position in systems of circular coordinates with the fixed stations as centers. Pulse transmitting equipment, receivers, and timing circuits are similar to those of other pulse signaling equipment.

Microwave Testing

By E. I. GREEN, H. J. FISHER and J. G. FERGUSON
Bell Telephone Labs., Inc.
New York, N. Y.

TECHNIQUES AND FACILITIES developed for microwave radar testing are applicable in the r-f range from 500 to 25,000 mc, and at intermediate frequencies for communication by pulse, frequency, and amplitude modulation from both audio and video signals. In addition to checking circuit and system operation common to communication and radar, radar testing also includes measuring the accuracy of the indicated target location. Equipment of the types familiar at lower frequencies have been developed.

In the uhf range, coaxial r-f circuits are used; in the shf band, wave guides are used. Standard signal generators have high frequency stability, can be tuned over an appreciable frequency range, incorporate attenuator pads and power measuring circuits (usually calibrated in dbm, that is db from a milliwatt reference level), and f-m sweeps and pulse modulation.

Either coaxial or wave guide wavemeters are common, although a combination of the two called transition wavemeters, are also used. Coaxial resonators are such that only the coaxial mode ($TM_{0,0,n}$) can exist. Cylindrical cavities are excited in their dominant mode ($TE_{1,1,n}$) to avoid spurious resonances from other modes, although for higher selectivity the circular electric mode ($TE_{0,1,n}$) can be used. For variable

SHEET



TUBE

WIRE

HERE MAY BE

The Solution

TO YOUR METAL PROBLEM . . .

LAMINATED CONTACT BUTTONS



CONTACTS



INLAY METALS



THERMOSTAT METALS

General Plate Laminated Metals

General Plate Laminated Metals . . . permanently bonded combinations of precious metals to base metals or base to base metals . . . can provide the solution to your performance or design metal problems whether the product be a peanut radar tube, an electrical contact or a giant turbine.

These versatile laminated metals . . . in sheet, wire, tube — or as fabricated parts . . . give you high electrical performance, corrosion resistance, workability, mechanical and structural properties not found in single solid metals — and best of all, at a fraction of the cost of solid precious metals.

Investigate General Plate Laminated Metals today. Find out how their unusual performance and cost-cutting advantages can help increase production . . . improve your product . . . and save money, too.

Our engineers will gladly help you with your metal problems. Write for their services.

Check these General Plate advantages:

- Corrosion Resistance
- Workability
- Ease of fabrication
- Long life
- Ease of soldering
- Economy
- Electrical Performance

GENERAL PLATE DIVISION

of Metals & Controls Corporation

50 Church St., New York, N. Y.; 205 W. Wacker Drive, Chicago, Ill.; 2635 Page Drive, Altadena, California
Grant Bldg., Rm. 603, Pittsburgh, Pa.

ATTLEBORO, MASSACHUSETTS

MR. RADIOMAN: CREI Training Can Equip You To Step Ahead of Competition and Gain the Confidence Born of Knowledge! . . .

Will You Be Ready

CREI Can Prepare You Now for a Better Job and a Secure Career in RADIO-ELECTRONICS

CREI technical home study training prepares you for the secure radio jobs that pay good money for ability.

You can be ready to enjoy the security of an important engineering position and take advantage of new carreer opportunities . . . if you prepare yourself now.

Join the ambitious radiomen who are assuring themselves of secure good-paying jobs with a planned program of advancement made possible by CREI home study training in Pactrical Radio-Electronics Engineering.

You can study at home—in your spare time—develop your technical ability—increase your knowledge to keep pace with important developments now taking place in the industry. CREI courses are constantly being revised and kept up-to-date with the rapid developments.

By adding CREI training to your present radio experience, you can safeguard your future and have a thorough knowledge U.H.F. Circuits, Cavity Resonators, Pulse Generators, Wave Guides, Klystrons, Maguetrons and other tubes. *Are you equipped to handle them?* CREI is equipped to help *you*, by providing the know-how and the ability that is required.

Act now! Get underway today. It costs nothing but a moment's time to send for complete details—without obligation—and it costs nothing but a moment's time.

Just Off the Press!

WRITE FOR FREE 36-PAGE BOOKLET

"Your Opportunity in the New World of Electronics"

If you have had professional or amateur radio experience and want to make more money, let us prove to you we have something you need to qualify for a better radio job. To help us intelligently answer your inquiry — PLEASE STATE BRIEFLY YOUR BACKGROUND OF EXPERIENCE, EDUCATION AND PRESENT POSITION.

CAPITOL RADIO ENGINEERING INSTITUTE

HOME STUDY COURSES IN PRACTICAL RADIO-ELECTRONICS ENGINEERING FOR PROFESSIONAL SELF-IMPROVEMENT

Dept. E-4, 3224-16th Street, N. W., Washington 10, D. C.

Contractors to U. S. Navy — U. S. Coast Guard — Canadian Broadcasting Corp.
Producers of Well-trained Technical Radiomen for Industry

Member: NATIONAL COUNCIL OF TECHNICAL SCHOOLS

frequency cavities, the TE modes are preferred because of their zero current at the inner walls, thus simplifying design of moving contacts.

Power measurements for signal generator outputs, detecting resonance of wavemeters, and measuring transmitter output, and circuit gains and attenuations are all basically the same. Crystal rectifiers, necessitating protection from overloads and stubbing to provide d-c returns from the indicating instrument, and thermistors, platinum wires or thermocouples, placed directly in the field to be measured, are used. These latter, being sensitive to temperature, require care in use.

Standing wave ratios, indicative of impedance mismatch, can be measured in several ways. A traveling probe in the coaxial line or wave guide can directly detect the standing wave. The standing wave can be made to move past a fixed probe by changing the electrical length of a section of a wave guide by squeezing it, or the reflected energy from a mismatch can be separated from the incident energy by a hybrid T.

Another method of measuring standing wave ratio, also used to separate transmitter and receiver power within a radar antenna feeder, is the directional couple. Because of the quarter-wave spacing of the two pickup probes, energy passing in one direction cancels itself within the directional couple and energy from



Directional couple for measuring energy passing in only one direction in a wave guide can be used for detecting impedance mismatches

the other direction reinforces itself. In this way energy reflected either from a target or from an impedance discontinuity can be measured.

Wideband amplifiers and high speed, linear sweeps have been developed for oscilloscopes. Accurate timing circuits, triggering circuits, and pulse generators carry accuracies to better than plus or minus two hundredths of a microsecond.

What Do You Want in a Relay?..
CLARE Will "Custom-Build" It
...*Exactly*

Clare puts the designer in the driver's seat. Clare Relays permit a flexibility of plan unheard of with ordinary relays.

The secret? There isn't any. It's just that Clare "custom-building" makes it possible for you . . . with the utmost economy . . . to have a relay exactly suited to your specific requirements.

Clare doesn't design and manufacture a new relay for you from the ground up. There would be no economy for you in that. Clare "custom-building" selects the proper combination of Clare features for the job and includes them in a standard basic frame that is ideal for the requirement at hand.

Clare "custom-building" is a method of construction. It permits a wide range of contact ratings . . . five different contact forms or any combination of them . . . either flat or hemispherical contacts which may be of rare metals or special alloys . . . coil windings to match the circuit and application.

Clare Relays are built for applications where precise performance, long life and dependability are prime requisites. Thousands of users attest to the value of Clare Relays and the Clare "custom-built" principle.

To "custom-build" a relay for you Clare engineers must know all the facts surrounding the requirements. Clare has sales engineers in all principal cities to show you how Clare "Custom-Built" Multiple Contact Relays are the effective answer to modern design problems.

Send for the new Clare Engineering Data Book with its full information on the full line of Clare Relays and allied control apparatus. Address: C. P. Clare & Company, 4719 West Sunnyside Avenue, Chicago 30, Illinois. Cable address: CLARELAY.



Contacts are welded to nickel silver springs by a special process. May be of precious metals or alloys in 12 different standard or special types and sizes.



Coil core of a.c. relays is of thin laminations of silicon steel, riveted together. This reduces hysteresis and eddy current losses, gives large amount of power with small heat losses.

High voltage spring pile-up insulators of special heat-treated Bakelite. Have minimum cold flow properties, low moisture absorption content. Permit punching without cracks or checks.



Double arm armature assembly with stainless steel shaft, operating in a marine brass yoke. Heelpiece, core and armature assembly of magnetic metal

CLARE RELAYS

"Custom-Built" Multiple Contact Relays for Electrical and Industrial Use

NEW PRODUCTS

New materials, new components, new assemblies; new measuring equipment; new technical bulletins, and new catalogs

1

Noise and Field Intensity Meter

STODDARD AIRCRAFT RADIO CO., 6644 Santa Monica Boulevard, Hollywood 38, Calif., is now releasing the Model NMA-4 noise. and field intensity meter heretofore available only to the Navy.

It is useful in locating and indicating in microvolts, the amplitude of noise causing disturbance to radio reception in aircraft, and in other receiver locations; in determining the effectiveness of filtering and shielding electrical apparatus which produces radio noise at ultra-high frequencies; for indicating and recording in microvolts per meter the field intensity of a-m, f-m and television transmitters.



The r-f amplifier, mixer and oscillator circuits use butterflies which vary capacitance and inductance simultaneously, offering noiseless tuning from 100-400 mc.

These circuits maintain a high degree of stability and nearly constant value of resonant impedance which provides for substantially uniform calibration. Stability of calibration is affected by shot noise developed in the plate circuit of the r-f amplifier.

The voltage range is 1 to 100,000 microvolts. The field intensity range is 5 to 100,000 microvolts per meter. Performance and construction specifications are in accordance with acceptable government requirements. Designed for portable or laboratory use at 105-125 v a-c, the unit is 15 3/16 in. high, 21½ in. wide, 14 5/16 in. deep. Weight is 56 lb. Accessories are provided for various types of measurements.

2

Packaged Magnetron Oscillator for Radar

DE MORNAY BUDD, 475 Grand Concourse, New York 51, N. Y., has available in its line of microwave equipment a packaged r-f radar unit. The magnetron oscillator is capable of delivering 20 kw peak power at 9,375 mc. Two local oscillators, two t-r tubes, crystals, and a narrow-band directional coupler for measurements are included, as well as a beacon cavity and crystal mount for future beacon use.



3

Amplifier-Voltmeter

INSTRUMENT ELECTRONICS, 253-21 Northern Boulevard, Little Neck, L. I., N. Y. The Model 45 logarithmic voltmeter has an accuracy of ±2 percent over its range from 0.0005 to 500 v at frequencies from 7 cps to 1.6 mc. It is useful in vibration studies, audio measurements and in broadcast and carrier frequency communications work. Power consumption is 30 w from a 117-v, 60-cps line. The table model is 7½ x 8¾ x 10½ in. and the price is $185.



4

Vibrating Reed Pickup

FRANK RIEBER, INC., 11916 West Pico Blvd., Los Angeles 34, Calif. The Caltron lateral reproducer is a generator operating by virtue of a vibrating reed moving in a magnetic field. Designed particularly for reproduction of commercial pressings, the pickup is housed and mounted in



HARVEY OF CAMBRIDGE....YOUR BEST Source of Supply for REGULATED POWER SUPPLIES

If you operate equipment requiring a constant, regulated source of laboratory D.C. power — Amplifiers, Pulse Generators, Constant Frequency Oscillators, Measurement Equipment and the like — you'll find there's a HARVEY Regulated Power Supply that will suit your every requirement to a "T". As the products of pioneers in the development and manufacture of Regulated Power Supplies, HARVEY Units offer the latest and best in design, performance and dependability.

The HARVEY Regulated Power Supply 106-PA meets every need for a controllable, dependable source of laboratory D.C. power between 200-300 volts. Operates from 115 volts A.C. . . . output remains constant even though line voltage varies between 95 and 130 volts. Ripple content is better than 10MV . . . two separate filament voltages available . . . 6.3 volts, 5 amps. each . . . paralleled operation possible making 6.3 volts at 10 amps. available. D.C. voltmeter for measuring output.

The HARVEY Regulated Power Supply 206-PA operates precisely and efficiently in the 500 to 1000 volt range. It provides a regulated flow of D.C. power in two ranges: 500 to 700 volts at ¼ amp; 700 to 1000 volts at ⅕ amp. Ripple content 1/10 of 1% or better at any voltage . . . 300MV at 1000 volts or better. Output is constant within 1% from no load to full load in each range; regulation 1% or better.

For complete specifications on the HARVEY 106-PA, write for Bulletin No. 25; on the HARVEY 206-PA, Bulletin No. 26. We'll be pleased to send you either or both. Write:

HARVEY RADIO LABORATORIES, INC.

459 CONCORD AVENUE · CAMBRIDGE 38, MASSACHUSETTS



Typical HARVEY products: Above left: The HAR-CAM Visual Alignment Signal Generator Model 205 TS; center: The HARVEY Marine Radio Telephone Model M-25; right: The HAR-CAM Model MFT-25 FM Transmitter. Write for Bulletins



such a way as to be mechanically interchangeable with most crystal pickup cartridges. The hum-bucking coil is seen above the pickup coil in the phantom drawing.

5

Frequency Converter

THE HALLICRAFTERS Co., Chicago 16, Ill., provides a means of converting f-m broadcast receivers now tuning between 42 and 50 mc for reception



of signals on the new band, 88 to 108 mc, in the CN-1 kit. The new circuit components are mounted in a box 6 x 4 x 4 in. which weighs 7 lb. The price is $15.

6

Heavy Turntable

ROBINSON RECORDING LABORATORIES, 35 South Ninth St., Philadelphia 7, Pa., is now manufacturing a new, heavy, belt-drive turntable equipped with a lever shift from 78 to 33⅓ rpm. The chassis bed plate is 20 x 24 in. and mounts in an opening 19 x 23 in. It can be supplied without pickup for $295. Console is $75 extra.

7

Circuit Breaker

HEINEMANN CIRCUIT BREAKER Co., 97 Plum St., Trenton, N. J., is now manufacturing a three-pole breaker which opens all circuits when an

overload occurs in any one leg. It is designed for 120/230 v a-c or 250 v d-c use at 50 amp maximum. Overall dimensions are 5¼x2¼x3 in.

8

Vacuum Relay

MONITOR CONTROLLER Co., Baltimore 2, Md. is manufacturing a spst vacuum relay which operates on 35 ma at 120 v d-c and will make or break a d-c circuit carrying 2 amp at 5,000 v. The Type RC 9972 sells for $47.

9

Communications Receiver

THE HAMMARLUND MFG. Co., 460 W. 34th St., New York 1, N. Y., is once again manufacturing a Super-Pro



receiver for civilian use. The new Series 400 model operates either between 0.54 and 30 mc or 1.25 and 40 mc with five amateur bands spread substantially over the dial of the latter (SP-400-SX) model. The receiver is equipped with crystal filter, avc, noise limiter, S meter, and has a built-in power supply.

10

Shaded-Pole Motor

ALLIANCE MANUFACTURING Co., Alliance, Ohio, has designed a 1/30 hp shaded-pole motor which will operate



fans or do intermittent duty in other services. It has a 4½ in. outside diameter and operates at 50 or 60 cps on voltages of 220 or less.

11

Industrial Counter

POTTER INSTRUMENT Co., 136-56 Roosevelt Ave., Flushing, N. Y. The dual predetermined electronic counter is proving valuable in such in-



dustrial tasks as the counting and packaging of small items. Employing four-tube counter decade circuits



we believe in uniformity

don herold

SPECIALISTS IN THIN GAUGE PAPERS

Even through the war years, when conditions were difficult, we were able to maintain the uniformity of our thin gauge papers for important military equipment. We continue this ability for you for peace time products, including capacitors, coils, transformers and other insulating purposes, requiring thin gauge papers. Our grades range in thickness from .00025″ to .004″ with extremely low tolerance limits. Specify Schweitzer for thin gauge paper.

SCHWEITZER PAPER CO.

182 CORNEILSON AVE., JERSEY CITY, N.J.
Plants: Jersey City, Mt. Holly Springs, Pa.
Research Laboratories:
Chrysler Bldg., New York, N. Y.

arranged to give two independent predetermining channels, any number from 0 to 10,000 may be set up by manipulating rotary switches. Operating power is from 110 v 60 cps lines.

12

Sound Projector

ATLAS SOUND CORP., 1449 39th St., Brooklyn 18, N. Y. The Atlas HU-15 weather-proof loudspeaker can be positioned for optimum coverage in

any direction and then locked in place. Voice coil impedance is 8 ohms, input power 12 w. Bell diameter is 8½ in. as is the overall depth. It weighs 6 lb and lists for $30.

13

Precision Resistors

RESISTANCE PRODUCTS CO., 140 South Second St., Harrisburg, Pa. have begun to market a new line of wire-wound precision resistors designed to meet the requirements of JAN specification R-93, RB10 through RB14. The non-inductive windings



are made on steatite forms, covered with an electrical varnish and baked. Tolerances are normally ±1 percent but resistors within ±0.1 percent can be furnished on order. Mounting is by means of a 6-32 machine screw through the center hole. The largest unit with a resistance of 2.75 meg is ⅞ by 2 1/16 in. exclusive of lugs.

14

Wire Stripping

FAIRCHILD CAMERA & INSTRUMENT CORP., Jamaica, N. Y., is now licensing the use of its chemical solution for quickly and harmlessly stripping all modern types of synthetic covered wires, no matter how small. After nearly two years of use, it has been found non-toxic to the worker and in no way chemically harmful to the product.

15

Alnico II Components

STACKPOLE CARBON CO., St. Marys, Penna., announces a line of sintered



Alnico II parts and an engineering service for production of special components.

16

V-t Volt-Ohmmeter

CLIPPARD INSTRUMENT LABORATORY, 1440 Chase Ave., Cincinnati 23, Ohio, is now producing the Model 406 electronic volt-ohmmeter.

A-c potentials are measured by means of a small-diameter high-impedance pen-type dual-diode probe on a 36-in. detachable shielded cable. A convenient ground terminal near the end of the probe provides minimum lead length for maximum accuracy of a-c measurements in all frequency ranges.

Full-scale sensitivity of 0-1, 0-3, 0-10, 0-30, 0-100, 0-300 and 0-1,000 a-c and d-c; 0-1,000 megohms in seven ranges with ample overlap to eliminate guess work and a db scale of —20 to +51 is provided on a large square-faced D'Arsonval type meter of 200 microamp sensitivity. The instrument is housed in an oak case with folding leather carrying handle. Detachable 36-in. d-c probe, ground cable, ohms probe and fused power supply cable are also standard equipment.

Input impedance of the meter is less than 7μμf, 7 megohms a-c, 28

megohms d-c, assuring accuracy of readings through all ranges with minimum circuit disturbances.

Tube complement consists of one 6X5GT rectifier, and two 6SN7GT dual-purpose tubes chassis-mounted and one 6AL5 dual diode in shielded probe. The instrument is calibrated to 2 percent accuracy in all ranges with 5 percent accuracy guaranteed in the field.

17

Decade Inductors

NEW YORK TRANSFORMER CO., 62 William St., New York 5, N. Y. is manufacturing a series of inductance decades for use in bridge and low-level filter circuits. They range from the Model 211, 0.11 henry in steps



Where There is Horsepower . . .

THERE IS WIRE

Coal . . . Water . . . Oil . . . these are our sources of power. Our early use of each of them was crude and localized and wasteful—before the time of electrical wire.

Now, wire harnesses horsepower. Wire traps it at its birth—even bringing about its generation. Wire packages power and brings it into our homes. Wire transforms power into a thousand different characters. Wire focuses—diffuses—interrupts—intensifies—splits—graduates power; transmuting one energy to many other forms: to heat—to light—to sound—or back again to whirling motion. Wire guides and controls power and makes it universally useful.

The use of horsepower is a many-sided science, now that wire is here. Each specialized application has its specialized wire counterpart. The development of these wires is in itself a scientific undertaking . . . a challenge . . . an achievement . . . a source of pride for the wiremakers among whom a pioneering leader is Belden Manufacturing Company.

Belden

WIREMAKER FOR INDUSTRY

HUBBA, HUBBA, HUBBA!

(East Indian for "there's no substitute"... it's tops)

Of course we've heard the popular expression, "hubba, hubba, hubba!" — and perhaps Micah is only kidding when he tells us it's East Indian for "there's no substitute".

Hubba, hubba, hubba, or not, there is no substitute for mica where mica is needed. Nothing else possesses the high dielectric properties of mica, nothing else lasts so long. And while you're getting mica, there's no reason why you shouldn't get the best — for *Macallen Mica* costs no more.

When you think of MICA think of MACALLEN

the Macallen Company

16 MACALLEN STREET - BOSTON 27

CHICAGO: 332 W. Washington Blvd. CLEVELAND: 3268 Lander Bldg.



of 0.001 h to Model 214 with a total of 110 h in steps of 1.0 h. The former has a Q of about 43 at 4,000 cps, dropping to 15 at 400 and 15,000 cps. The latter has its maximum Q at about 200 cps.

18

Ionization Lamp

AMGLO CORPORATION, 4234 N. Lincoln Ave., Chicago, Ill. produces a lamp which gives light produced by the direct ionization of inert gas when a concentrated electron stream

is directed through a closely wound spiral having an open end. When used as a photoflash lamp, it is said to produce a light one hundred times brighter than the sun for 1/10,000 second.

19

Electrocardiograph

ELECTRONIC CORPORATION OF AMERICA, 45 West 18th St., New York 11, N. Y. The Cardiotron makes it possible to record on paper the minutest heart action or variation. Speed of the recording tape can be varied in order to expand or compress the graph. An amplifier magnifies heart

. . . this greatest of test instruments has been tested into top ranking reputation

The Simpson 260 has out-sold and out-performed every other even remotely similar test instrument in the electronic and electrical fields ever since its introduction in 1939. Through the ensuing seven years, covering the War period, circumstances gave it a gruelling test for accuracy never visioned by its makers. It stands today as irrefutable proof that Simpson design and Simpson quality produce accuracy that *stays* in an instrument year after year.

The demand for the 260 from men who first used it in the Armed Services (in laboratories of 300 government agencies and universities, and on the battlefields the world around) has now been added to its enormous popularity among radio servicemen. The Simpson 260 is easily the world's most popular high-sensitivity set tester for television and radio servicing.

The basic reason for this out-selling and out-performing by the Simpson 260 is this: It out-values every other similar instrument in the field. You cannot touch its precision, its useful ranges, or its sensitivity in any other instrument selling for the same price or even substantially more.

SIMPSON ELECTRIC COMPANY
5200-5218 W. Kinzie St., Chicago 44, Ill.

Simpson

SIMPSON 260, HIGH SENSITIVITY SET TESTER FOR TELEVISION AND RADIO SERVICING

Ranges to 5000 Volts—Both A.C. and D.C.
20,000 Ohms per Volt D.C.
1000 Ohms per Volt A.C.

At 20,000 ohms per volt, this instrument is far more sensitive than any other instrument even approaching its price and quality. The practically negligible current consumption assures remarkably accurate full scale voltage readings. Current readings as low as 1 microampere and up to 500 milliamperes are available.

Resistance readings are equally dependable. Tests up to 10 megohms and as low as ½ ohm can be made. With this super sensitive instrument you can measure automatic frequency control diode balancing circuits, grid currents of oscillator tubes and power tube, bias of power detectors, automatic volume control diode currents, rectified radio frequency current, high-mu triode plate voltage and a wide range of unusual conditions which cannot be checked by ordinary servicing instruments. Ranges of Model 260 are shown below.

Price, complete with test leads.....$33.25
Carrying case 4.75

Volts D.C. (At 20,000 ohms per volt)	Volts A.C. (At 1,000 ohms per volt)	Output
2.5	2.5	2.5 V.
10	10	10 V.
50	50	50 V.
250	250	250 V.
1000	1000	1000 V.
5000	5000	5000 V.

Milli-amperes D.C.	Micro-amperes	Ohms	
10	100	0-1000	(12 ohms center)
100		0-100,000	(1200 ohms center)
500		0-10 Megohms	(120,000 ohms center)

(5 Decibel ranges: —10 to +52 DB)

ASK YOUR JOBBER

FIVE YEARS FROM TODAY, will you be in the knee-pants era of radio or will you be "up and on to" every new development? The matter is as pointed as that. True, most receivers cannot reproduce the full range of FM broadcasts yet. But soon they will.

MODERNIZE! Start now to monitor your full FM range with the Altec Lansing Loudspeaker System. Make your improvements — your refinements — now. So when tomorrow comes, you will not just be growing up to standards, you will be *setting* them. See your dealer.

THE ALTEC LANSING DUPLEX LOUDSPEAKER SYSTEM

Both high and low frequency units are combined in one horn, reproducing the entire FM range, from 50 to 15,000 cycles, without intermodulation effects or distortion.

ALTEC
LANSING CORPORATION
1161 N. Vine St., Hollywood, Cal.
250 W. 57th St., N. Y. 19, N. Y.



action 14,000 times. The equipment is portable, housed in a case 15¾ x 11½ x 9¼. It weighs 34 lb. Built to operate on 115 v a-c, it can be used on d-c,. if provided with a converter.

20

Shock Mount

ROBINSON AVIATION INC., Teterboro, N. J. announces a new type of anti-vibration mounting unit which includes a damping system, a snubbing system and electrical bonding. Three

standard sizes are available for loads varying from ½ to 45 lb. The illustration shows the effect of a vibrating test stand on two units, the one to the left mounted on conventional shear-type unit.

21

Production Heater

MARION ELECTRICAL INSTRUMENT CO., Manchester, N. H. The bench-type induction heater now in pro-



SIGMA
Relays
for precision, sensitivity and ruggedness



TYPE 4F

Series 4 design characteristics are compactness (1 5/8" x 1 3/8" x 1 5/32"), speed 2 - - 3 milliseconds, medium sensitivity (10 milliwatts minimum - - 30 to 50 milliwatts for aircraft performance) and precision. Moderately low cost.

TYPE 5F

Series 5 relays are 1 3/4" x 1 3/8" x 1 7/16", extremely sensitive (.0005 watts minimum - *operation on input from thermocouple)*— maximum resistance to shock and vibration — precise in operation.

Both Series available with enclosures and plug-in bases, and in hermetically sealed enclosure.

Other Sigma relays in production, and still others under development, include both more specialized and complicated types, as well as simpler and more economical designs for both A. C. and D. C. operation.

Our Sales and Engineering Departments are at your service.

Sigma Instruments, INC.
Sensitive **RELAYS**
62 Ceylon St., Boston 21, Mass.

CIRCUIT PRINTING with *Metapaint**

*(*Metaplast Silver Conductive Paint*)



Metaplast Company, pioneers in metal coatings on non-conductive surfaces, announces a great war-time development now available for general peace-time use.

USES FOR *Metapaint*

- To print electrical circuits of low current-carrying capacity, for connecting circuit elements
- To print coils for FM and television circuits
- To print shields
- To spray shields

METHODS OF APPLICATION

- Screen printing
- Spraying
- Painting

Order by the troy ounce. Immediate shipment.

Metaplast COMPANY
205 W. 19 St., N. Y. 11, N. Y.

METAL PLATING ON PLASTICS

California 1027 N. Seward, Los Angeles 38 — ENGLAND · FRANCE · CANADA · ARGENTINA · BRAZIL · AUSTRALIA

Our 24th year of dependable service to American industries

Use a solder that will contribute to the excellence of your product

No matter what you manufacture, the all-around excellence of your product depends on the quality of the materials you put into it.

Because solder is so extensively used in the manufacture of radio sets, instruments for radar, relays, tubes, transformers etc., it is important to select a brand of known quality and proven dependability.

In every department of the Electronic and Radio fields, Glaser Plastic Rosin Core Solder has given conclusive proof of its outstanding quality — during war and peacetime years.

More and more of the leading manufacturers throughout the country have adopted Glaser Solders as standard. Make Glaser Plastic Rosin Core Solder a contributing factor to the built-in perfection of *your* product.

Specify "Glaser", the name that means everything you can ask for in Solders and Fluxes.

Glaser Plastic Rosin Core solders exceed Government specifications in purity and are guaranteed to conform with A.S.T.M. Class A specifications.

OTHER GLASER PRODUCTS

Silver Brazing Solder and Flux
Fluxes for every purpose
Lead Products of every description
Lead Lining of acid and plating tanks

Consult our Engineering Department on your Soldering and Flux problems.

GLASER LEAD CO., INC.

31 Wyckoff Avenue, Brooklyn 27, N. Y.

The Quality Line

Glaser SOLDER PRODUCTS

duction is useful for small-parts industrial soldering. Work coils for the most common types of job can be made up without involved calculations or need for retuning. The equipment is contained in a cabinet 15¾ x 21½ x 15 in. and weighs 150 lb. It operates from a 115-v 60-cps line, drawing 775 w. The price is $360.

22

Recording Turntable

PRESTO RECORDING CORP., 242 W. 55th St., New York 19, N. Y. The new 14-A turntable for commercial use is directly gear-driven at either 78.26 or 33.33 rpm. Mechanical vibration is minimized by the use of mas-



sive parts and care in damping. The motor, gear box and transmission shaft, for example, are mounted on a separate base, the whole assembly weighing 160 lb. The cutting head mounting can be used for either vertical or lateral recording at any one of five pitches.

23

R-f Voltmeter

BALLANTINE LABORATORIES, INC., Boonton, N. J. The Model 300 electronic voltmeter can be used from 30 cps to 5.5 mc with accuracies ranging between 3 and 5 percent. The voltage range is from 0.001 to 1 v in three decade ranges and is extended to 10 and 100 v by multipliers. Input impedance is equal to a resis-



the new electronics BUYERS' GUIDE

A SEPARATE ISSUE COMING JUNE 1946

A NEW PLAN has been adapted for the 1946 Buyers' Guide. For the Subscriber; it will be an additional, bonus issue of ELECTRONICS containing news and vital information of year-round value, plus the most authentic, comprehensive listing of products ever attempted. For the Advertiser; its twelve-month usefulness assures complete readership by the largest buying audience ever assembled.

CLOSING DATES

Copy to prepare: All details must be in our New York office not later than March 15th. *Copy to set:* April 1st, no proofs April 10th. *Complete Plates:* May 1st. Rates and detailed information can be obtained from the ELECTRONICS representative in your territory, or send for the 12 page descriptive folder illustrated below.

Contents were determined by questionnairing a cross-section of the many types of people who will use the Guide. They indicated the information they want, need and use, suggested important listing breakdowns and were enthusiastic about its vital usefulness. That's why we KNOW the Guide will be read . . . it's being "tailored to known needs".

Listings will provide authentic, easy-to-find buying reference. All items will be indexed with classifications broken down where necessary for complete clarification to quickly answer the question, "Who makes it and where can I buy it?" Advertisers' names and page numbers will be flagged in bold type as the source of necessary data on which to base purchases or make direct inquiry.

Advertising space used in the Buyers' Guide should come out of Catalog Budgets. It is the year-round opportunity to promote ALL your products, NOT JUST ONE. Expose them all to the buyers who will use this Guide. Purchases will be based on the data your ads contain, and *remember* advertisers' names and page numbers will be flagged to secure immediate attention. Use the Guide as your Salesman-In-Print to reach, daily, the buying readership assured this valuable engineers' data book. You can't afford to miss it!



ABC **electronics** ABP

330 West 42nd St. • Established 1930 • New York 18, N.Y.

From Design to Delivery
PEERLESS
Does it Better!
A complete transformer service—from engineering design to correctly cased unit. Peerless transformers, windings, reactors, and fluorescent ballasts are available or can be produced in sizes and capacities to meet your needs. Write for new catalog.
Prompt Delivery If You Order Now!
PEERLESS
ELECTRICAL PRODUCTS CO.
6920 McKINLEY AVENUE
LOS ANGELES 1, CALIFORNIA
Choice territories open for qualified representatives

CHASSIS • CABINETS • PANELS • RACKS
Skill in METAL
PAR-METAL . . . a specialized manufacturing plant employing modern high speed methods. Nevertheless, Par-Metal products have a definite quality of Craftsmanship—a "handmade" quality born of genuine skill and long experience. Write for Catalogue.
PAR METAL ELECTRONIC HOUSINGS
Serving the Electronics Field Exclusively
PAR-METAL PRODUCTS CORPORATION
Export Dept
32-62—49th STREET . . . . LONG ISLAND CITY, N. Y. 13 E. 40th St., N. Y. 16, N. Y.

tance of 1 meg shunted by a capacitance of 9 $\mu\mu$f. Seven tubes are used. The self-contained power supply operates on 110-120 v 50-60 cps. The meter is 5 x 6¼ x 11⅛ in and weighs 10 lb.

24

Mike Stand

UNIVERSAL MICROPHONE Co., Inglewood, Cal., is producing a new type A31 microphone desk stand with a die-cast base and wooden handle



which is demountable. The microphone is attached to a threaded brass ferrule at the top of the handle. The stand lists at $3.

25

R-F Contactors

MONITOR CONTROLLER Co., Baltimore 2, Md. The r-f contactors, Types RC 5710 through RC 5780 operate on 220 v 60 cps and carry up to 2-mc circuits with currents as high as 15 amp and voltages to 10,000. Prices run from about $42 to $59 for various contact arrangements. The Type RC

METAL ASSEMBLIES AND COMPONENTS
FOR
ELECTRONIC AND MECHANICAL DEVICES

- ENGINEERING
- DEVELOPING
- FABRICATING
- ELECTRO-FORMING
- PLATING
- FINISHING

BERNARD RICE'S SONS
INCORPORATED

MANUFACTURERS OF QUALITY METAL PRODUCTS SINCE 1867

OFFICE: 325 FIFTH AVENUE, NEW YORK 16, N. Y.

WORKS: 139-145 NORTH TENTH STREET, BROOKLYN 11, N. Y.

Crystalab
TRADE MARK REG. U. S. PAT. OFF.
SPECIALISTS IN SPECIAL CRYSTALS
MYCONS
F. M. and Television Components to your specifications—
Write now!
PRECISE BUTTON MICA CONDENSERS
CRYSTAL RESEARCH LABORATORIES INC.
29 ALLYN ST., HARTFORD, 3, CONN., PHONE 7-3215

7680 transfer switch can be used at 1 mc and carries 75 amp at 15 kv. It measures 12 x 14 x 15 in. The Type RC 5980 can be used at 30 mc, carrying 30 amp and 3,500 v. It is 5 x 8 x 13½ in.

26

A-m Transmitter

RAYTHEON MANUFACTURING CO., 60 E. 42nd St., New York 17, N. Y. The first item of broadcast equipment in a contemplated series is a 250 w a-m transmitter with a flat frequency response from 30 to 10,000 cps. Low-



power stages are tuned by a low-speed, motor-operated clutch mechanism. The final amplifier has a broad frequency response and does not require care in tuning. Air-cooled triodes are used throughout.

27

Aircraft Range Receiver

MAGUIRE INDUSTRIES, INC., 500 5th Ave., New York 18, N. Y. The first item in a line of aircraft radio equipment to be manufactured by this company is the Model ARR-1 range receiver to cover the 190-420 kc frequency band. A filter can be switched in during the reception of voice an-



Automobile With Wings

THIS COMFORTABLE 3-wheel sedan is garaged at home ready for everyday use. For flight, its easily and quickly attached wings and tail surfaces are garaged at the airfield.

Delicate instruments, controls and devices that make such conveniences a fact are entirely dependent upon parts of highest precision.

Producing parts for all types of close-tolerance requirements has been our business here at Ericsson for close on to 35 years. We are glad to consult with manufacturers whose new designs are more effectively marketed with close-tolerance parts produced economically.

• • •

(*Below*) Some of the many thousands of our precision parts that helped "Keep 'em flying and fighting."

ERICSSON
ESTABLISHED 1911

ERICSSON
SCREW MACHINE PRODUCTS CO., INC.
25 LAFAYETTE STREET, BROOKLYN 1, N.Y.

G-E LAMINATED PLASTICS

FABRICATED TO YOUR SPECIFICATIONS

YOU GET ACCURATELY FINISHED PARTS MADE OF THE RIGHT MATERIAL READY FOR THE JOB

G-E Textolite sheets, tubes and rods are fabricated in an almost unlimited variety of sizes and shapes, and the General Electric Company has the necessary equipment to do this rapidly and economically—lathes, saws, shears, punches, hobs and mills . . . . even specially designed machinery to speed up and lower the cost on large production runs.

And because there are over 50 grades of G-E Textolite to select from, each having an individual combination of properties—electrical, mechanical, chemical, thermal—you get a grade that fits your needs.

Correctly machined and made of the right material for your application, you can be assured that when G-E Textolite fabricated parts reach you they will do the job.

Let us know your requirements. Write to Section S-2, General Electric Co., Plastics Divisions, One Plastics Ave., Pittsfield, Mass.

G-E Textolite tubing is shown being threaded to exacting mechanical and electrical specifications for radio coil forms.

G-E TEXTOLITE IS SUPPLIED IN THE FOLLOWING FORMS:

Sheets, Tubes, and Rods	Molded Laminated Parts
Fabricated Parts	Post-Formed Laminates
Nameplates	Translucent Laminates
Low-Pressure Molded Parts	

CD-46-E2

"everything in Plastics"

GENERAL ELECTRIC

"Radio Today Is So Technical An Engineer Welcomes SIMPLICITY"

SUN RADIO Makes It EASY For You To Buy Parts

And here's how

Our only address! The entire 3rd floor at 122-124 Duane Street, New York City. 6,000 square feet. More room, more parts, more service.

Simpler to Buy

A half million feet of shelves — with radio components of every leading manufacturer.

Simpler to Select

One phone call, one letter, or one visit gets exactly what you need — the FIRST time.

Simpler to Order

Call SUN First — It's Simpler

FREE OFFER

Condensed chart of Graphical Symbols for Electronic Diagrams as standardized by the RMA (includes those until recently kept secret). Just ask for it on your letterhead. Address Dept. R, D.

SUN RADIO & ELECTRONICS CO., Inc.
122-124 Duane St. NEW YORK 7, N. Y.



PLASTIC KNOBS

for the Electronics Industry

IN the complete line of General Electric phenolic plastic knobs, you will find a wide variety of shapes and sizes to blend in with practically any type of equipment design.

Ruggedly constructed for the hard and constant use that knobs receive, these black phenolic plastic types will not only prove more than satisfactory but will also add a distinctive touch to the appearance of any unit. Write:

Electronics Department
General Electric Company
Syracuse, N. Y.

GENERAL ELECTRIC

nouncements. Operated entirely by dry batteries, the set weighs a little over 3½ lb and measures 4⅛ x 4½ x 6¾ in. Without batteries or headphones it sells for $29.

28

Aircraft Radio

BENDIX RADIO, Baltimore 4, Md. The PATR-10 is a five-channel vhf transmitter combined with a range and broadcast receiver and is designed for the private flier. The transmitter section is crystal controlled,



using only 131.9 and 131.7 mc at this time. The addition of a loop antenna will allow using the receiver unit as an aural-null direction finder. Powered by a 12- or 24-volt battery, the equipment consumes 42 w. It measures 5 x 7 x 7 in. and weighs 7 lb.

29

Flash Capacitor

TOBE DEUTSCHMANN CORP., Canton, Mass. The "N-Erg-Y" capacitor has a storage capacity of 100 watt-seconds at a peak rating of 2,500 v d-c and has been designed for portable flash units. Instantaneous currents

ANSONIA BUILT A GREAT NEW FLEXIBLE CABLE FOR NAVY RADAR

For use on radar and gunfire control, the Navy needed a specialized high frequency cable. It had to feature:

(1) flexibility
(2) extreme low dielectric loss factors
(3) serviceability under extreme weather conditions.

WANTED—High Frequency Transmission Problems, for M-I-29 . . . a new flexible cable featuring extremely low loss and high conductance. For use where coaxial characteristics are required in a flexible cable.

In cooperation with Navy Engineering, Ansonia helped develop a cable answering these requirements — M-I-29—available now, to you!

To the Navy this cable represented high fidelity radar images and dependable service under severe operating conditions. To you, it may mean clearer television, truer FM radio tone or the solution of a problem in transmitting ultra high frequency power with low loss, since it approaches coaxial cable in dielectric qualities yet is completely flexible.

Insulated with ANKOSEAL thermoplastic insulation, M-I-29 can be engineered and supplied to meet special dielectric characteristics and operating conditions. "Yankee Ingenuity" displayed in the creation of this cable is ready now to help make it meet your particular needs.

This is one of a complete line of *job - engineered* cables made by Ansonia. For details on this or other cables, write Dept. AL The Ansonia Electrical Company, Ansonia, Conn.

Why ANKOSEAL *solves cable problems*

Ankoseal, a thermoplastic insulation, can help solve many electrical engineering problems, now and in the future. *Polyvinyl* Ankoseal possesses notable flame-retarding and oil resisting characteristics; is highly resistant to acids, alkalies, sunlight, moisture, and most solvents. Polyethylene Ankoseal is outstanding for its low dielectric loss in high-frequency transmission. Both have many uses, particularly in the radio and audio fields. Ankoseal cables are the result of extensive laboratory research at Ansonia—the same laboratories apply engineering technique in the solution of cable problems of all types.

THE ANSONIA ELECTRICAL COMPANY

Specializing in "Ankoseal" a Thermoplastic Insulation

ANSONIA CONNECTICUT

A Wholly-Owned Subsidiary of

NOMA ELECTRIC CORPORATION

GENERAL OFFICES • NEW YORK, N. Y.

Makers of the famous Noma Lights—the greatest name in decorative lighting. Manufacturers of fixed mica dielectric capacitors and other radio, radar and electronic equipment.

..tagged for the big jobs!

HEXACON SOLDERING ELECTRIC IRONS

RCA

Western Electric

KAISER

Bendix

Westinghouse

TYPE P-150
This production iron provides a large reserve of heat at the right temperature for sustained production.

Follow the leaders — and you'll use HEXACON! For rugged, heavy duty work or for light, intricate work . . . for continuous production or hard-to-get at work . . . here's the answer. One reason is "Balanced Heat" — dissipating excessive element-imparing heat—and minimizing element burn-outs and tip replacements. Another, is their light weight, efficiency and dependability.

LITERATURE AVAILABLE — The complete HEXACON line of screw tip and plug tip irons from 40 to 700 watts, and with tip diameters ranging from ¼" to 1¾", is fully illustrated and described. Write today; no obligation.

HEXACON ELECTRIC CO.
130 W. CLAY AVENUE, ROSELLE PARK, N. J.

HEXACON
HIGH-QUALITY, LONG-LASTING SOLDERING IRONS

as great as 1,250 amp are possible for more than 10,000 charge-discharge cycles. The steel housing measures 6½ x 4⅝ x 3¾ in. and the unit weighs 6¼ lb.

30

Hydrogen Thyratrons

SYLVANIA ELECTRIC PRODUCTS INC., 500 Fifth Ave., New York 18, N. Y. The Type 4C35 and 5C22 hydrogen thyratrons now available for communications and industrial applications are designed to include low deionization time, rapid switching

rates, high peak currents, high plate voltages, moderate trigger requirements and operation at zero bias. The tube illustrated has the following characteristics: heater, 6.3 v, 9.6 amp; peak anode, 16 kv, 325 amp; average anode d-c current, 200 ma; bulb size, T-20; overall length, 10 in.

31

Breaker Switch

AIREON MFG. CORP., Kansas City, Kansas, has designed a series of circuit breaker switches for protection of circuits drawing 15 to 35 amp, suitable for a-c or d-c use. The units can be furnished in water-tight and explosion-resisting enclosures.

32

F-m Broadcast Transmitter

RADIO ENGINEERING LABORATORIES, INC., 35-54 Thirty-Sixth St., Long Island 1, N. Y. recently exhibited a 1 kw f-m broadcast transmitter designated the Model 518-DL. The interior of the power amplifier cham-

for Measuring Complex Waveforms



THIS analyzer offers the simplest, most accurate and most direct method of measuring the amplitude and frequency of the components of any complex electrical waveform.

It is ideally suited to hundreds of harmonic-distortion measurements on such equipment as any type of audio apparatus; broadcast receivers and transmitters; telephone and public address systems, oscillators, amplifiers and other vacuum-tube circuits; hum measurements in a-c operated communication equipment; harmonic studies of electric power systems and electric machinery; induction studies on telephone lines.

In its essentials this analyzer consists of a heterodyne-type vacuum-tube voltmeter with a highly selective filter using three quartz crystals. At only 60 cycles from resonance the attenuation is down by 75 decibels, yet tuning is very easy by virtue of the 4-cycle flat top characteristic at resonance. Standards for both voltage and frequency are built into the analyzer and can be used to check its calibration at any time.

The frequency range is 20 to 16,000 cycles and the voltage range 300 microvolts to 300 volts full scale. The instrument is completely a-c operated and has no pickup from external magnetic fields.

TYPE 736-A WAVE ANALYZER $640.00

WRITE FOR COMPLETE DATA

GENERAL RADIO COMPANY

Cambridge 39, Massachusetts

90 West St., New York 6 — 920 S. Michigan Ave., Chicago 5 — 1000 N. Seward St., Los Angeles 38

INSTRUMENT PARTS
of
Exceptional Accuracy

Let us do that difficult job on our PETERMANN automatics, supplemented and supported by the finest Swiss and American machines for maintenance and second operations.



TAKE advantage of our long experience in producing parts of exceptional accuracy and finish, in our fully equipped factory, manned by highly skilled operators.

We will be glad to discuss your requirements or quote from your blueprints

INSTRUMENTS PARTS CORPORATION

TELEPHONE: OSSINING 2220

OSSINING, NEW YORK

ber is shown in the illustration. The Armstrong dual-channel modulator is at the left and the power and control section to the right. The equipment is designed for operation on the new 88-108 mc band.

33

Miniature Meters

THE MB MANUFACTURING CO., INC., 331 State St., New Haven 11, Conn., has available two series of small meters; the No. 102 mounts through a 1-in. hole and the No. 152 through



a 1½-in. opening. These meters are sealed, have an accuracy of 2 percent of full-scale deflection at any point and embody the features found in larger meters of the same general type.

34

Metal Sorter

CONTROL EQUIPMENT CO., 547 Brushton Ave., Pittsburgh 21, Pa. The apparatus used for determining the composition of various metals operates on the principle of a voltage

THE NC-46

The new National NC-46 Receiver is a fine performer at a moderate price. Ten tubes in an advanced superheterodyne circuit provide excellent sensitivity throughout the receiver's range from 550 KC to 30 MC. Circuit features include an amplified and delayed AVC, series valve noise limiter with automatic threshold control, CW oscillator and separate RF and AF gain controls. The push-pull output provides 3 watts power, and the AC-DC power supply is self-contained.

ARMY E NAVY

ARMY E NAVY

NC —NATIONAL COMPANY, INC., MALDEN, MASS.

Designed for

Application



No. 33446 — Cavity Socket Contact Discs

Now that the Secret classification has been lifted from the General Electric type GL496 or "Lighthouse" ultra high frequency tube, we can list the cavity contact discs we have been furnishing to authorized customers during the past few years. This set consists of three different size unhardened beryllium copper multifinger contact discs. Heat treating instructions forwarded with each kit for hardening after spinning or forming to frequency requirements.

JAMES MILLEN MFG. CO., INC.

MAIN OFFICE AND FACTORY

MALDEN

MASSACHUSETTS

being generated when dissimilar metals are rubbed together. Reference standards are compared with unknowns and determinations are made at the rate of 30 a minute in production. There is no destruction of finished parts. The sorter requires less than 100 watts at 115 or 230 v, 25 to 60 cps. It weighs approximately 30 lb.

35

Magnet Charger

RADIO FREQUENCY LABORATORIES, INC., Boonton, N. J. The first commercial version of an instrument magnet charger developed during the war is now coming on the market. Useful on production lines or in repair shops, it operates by the sudden discharge of a capacitor through a



current transformer. A pushbutton control fires an ignitron-type tube to discharge the capacitor. Secondary currents exceed 15,000 peak amp. There are no exposed high-voltage terminals. The unit measures 7 x 13 x 17 in. and weighs 75 lb. It operates from 100-120 v, 50-60 cps lines, consuming 25 w. Price is $490 f.o.b.

36

Production Counter

THE AUTOTRON CO., Danville, Ill. The Shadowcount will count up to 1,000 items a minute by means of the interruption of a light beam received by a photoelectric tube. Parts drop through a chute past the light beam and need not necessarily be spaced in order to resolve the num-

American Beauty

ELECTRIC SOLDERING IRONS

are sturdily built for the hard usage of industrial service. Have plug type tips and are constructed on the unit system with each vital part, such as heating element, easily removable and replaceable. In 5 sizes, from 50 watts to 550 watts.

TEMPERATURE REGULATING STAND

This is a thermostatically controlled device for the regulation of the temperature of an electric soldering iron. When placed on and connected to this stand, iron may be maintained at working temperature or through adjustment on bottom of stand at low or warm temperatures.

Write for Catalog Sheets 110-1

AMERICAN ELECTRICAL HEATER COMPANY

DETROIT 2, MICH., U. S. A.

FINGER TIP CONTROL



with S.S.WHITE FLEXIBLE SHAFTS

Finger tip control of cylinder speed for regulating voice pitch is provided by means of an S.S.White Remote Control flexible shaft in the Edison Miracle Secretarial Ediphone. Although the shaft makes a 90° bend in a short radius, a quick, sensitive adjustment of the fly-ball governor is made by the typist with a minimum effort of thumb and finger tips on the knurled knob. In the words of the chief engineer, "this application provides a smooth range of speed control with facility of adjustment equal to that of a micrometer."

Where smooth, accurate control is needed in electronic and related equipment, an S.S.White Remote Control flexible shaft is a simple, easily applied way to get it. It will pay every engineer to be familiar with the wide range and scope of S.S.White flexible shaft applications.

FREE HANDBOOK FOR ENGINEERS

Full details of S.S.White Flexible Shafts and their application are contained in the 256-page Flexible Shaft Handbook. A free copy will be sent to any engineer who writes for it on his business letterhead and indicates his position.

S.S.WHITE INDUSTRIAL DIVISION

THE S. S. WHITE DENTAL MFG. CO. — DEPT. E, 10 EAST 40th ST., NEW YORK 16, N. Y.

FLEXIBLE SHAFTS • FLEXIBLE SHAFT TOOLS • AIRCRAFT ACCESSORIES
SMALL CUTTING AND GRINDING TOOLS • SPECIAL FORMULA RUBBERS
MOLDED RESISTORS • PLASTIC SPECIALTIES • CONTRACT PLASTICS MOLDING

One of America's AAAA Industrial Enterprises



The nameplate that identifies your product should reflect the quality you build into it.

Recognizing this, manufacturers all over the country have made Sillcocks-Miller their source for nameplates fabricated of plastic. These companies know that quality is a tradition here at Sillcocks-Miller . . . that every job must conform to our rigid standards of accuracy and perfection.

From long experience, our engineers can readily meet your nameplate requirements. There is no lost motion, no delays to you because of "trial and error" production.

That's what we mean when we say it costs you *less* to pay a little more for Sillcocks-Miller quality.

Write for complete details

THE SILLCOCKS-MILLER CO.

10 West Parker Avenue, Maplewood, N. J.
Mailing Address: South Orange, N. J.

SPECIALISTS IN HIGH QUALITY, PRECISION-MADE PLASTICS FABRICATED FOR COMMERCIAL, TECHNICAL AND INDUSTRIAL REQUIREMENTS.

ber of objects. Several types and accessories are available to convert the basic counting mechanism to special tasks. The cabinet size, not including hoppers or other external feeding apparatus, is 10 x 12 x 9 in.

37

Mixer Control

CINEMA ENGINEERING CO., 1510 W. Verdugo Ave., Burbank, Calif., has designed a new mixer control which is said to reduce contact noise to a low order. It uses a wedge-shaped

roller riding on a plastic arm to make contact between the resistance wire and a metal track. Models No. 3182 and 1047 ladder-type attenuators are provided with this mechanical improvement.

38

Exposure Control

SIDWARD PRODUCTS CO., 261 Broadway, New York 7, N. Y., produces an integrating light intensity control weighing 6 lb which measures exposures from ½ sec to 45 min. The

INTER-COMMUNICATION AND PAGING SYSTEMS

For Every Requirement

With its reputation for quality earned over the years, and more recently its importance in war, specification of BOGEN inter-communication and paging equipment is your guaranty of functional efficiency and dependability.

The BOGEN line is diversified and complete, with units and systems to meet every particular need; economy features—including installation, maintenance, and service—assure self-amortization in a short time. Investigate BOGEN today; complete details on request.

Address inquiries to Department D

TYPE A COMMUNO-PHONE



Inter-communication system comprises Master Unit and up to 18 remote stations. Two way talk and call. Volume control. Remotes can reply at distance of 20 to 30 feet from their unit. No need to interrupt routine or work. Other models provide group and all call features.

THE STANDARD OF PERFORMANCE
db
Bogen Sound Systems
David Bogen CO. INC.
663 BROADWAY, NEW YORK 12, N.Y.
BOGEN SOUND SYSTEMS · AMPLIFIERS
COMMUNO-PHONES · ELECTRONIC EQUIPMENT

They wanted a metal to pull an *Electronic Trigger*

In developing the Proximity Fuse, *Problem One* was to design a 5-tube radio transmitter and receiver small enough to fit into a shell nose. *Problem Two* was to engineer the unit to withstand physical shocks and strains never before encountered.

There was the smashing impact of the initial discharge. There was an accelerating force greater than 15,000 times gravity. There was the terrific centrifugal force imparted by barrel rifling.

Yet . . . aside from size, the tiny tubes that formed the "brains" of the fuse did not differ much from those used in home radios.

As in conventional tubes, most had elements of Nickel.

The low gas content of Nickel meant easy evacuation and no impairment of vacuum during use. *(An important feature with so little surface area available for "getter" action.)*

In addition, Nickel could resist deterioration in fabrication and withstand high evacuation temperatures without distortion.

Moreover, Nickel supplied all the required electronic and electrical properties.

Finally, and of very great importance, Nickel could be worked in the extremely small sizes needed.

When you have a metal selection problem, investigate Nickel and high-Nickel alloys. They are workable metals offering a hard-to-find combination of properties for electronic applications. Write for the new "Inco Nickel Alloys for Electronic Uses" which gives you the data you want on the composition and characteristics of 13 Nickel alloys to solve electronic problems.

THE INTERNATIONAL NICKEL COMPANY, INC.
67 Wall Street, New York 5, N. Y.

After leaving the gun, the Proximity Fuse begins to send out a tulip-like pattern of radio waves.

As target enters wave field, the waves are reflected back to the fuse where they release the electronic detonating trigger.

Photo courtesy of Sylvania Electric Products, Inc.

Here's *one of the tiny tubes for the radio in the Proximity Fuse. In most of the tubes used, all elements are made of pure Nickel. Some tubes, depending upon design, use Nickel-molybdenum alloys in addition to Nickel.*

Nickel NICKEL INCO TRADE MARK ALLOYS

MONEL* • "K" MONEL* • "S" MONEL* • "R" MONEL* • "KR" MONEL* • INCONEL* • NICKEL • "L" NICKEL* • "Z" NICKEL*

*Reg. U. S. Pat. Off.

LARGEST AND MOST COMPLETE STOCKS... *Under One Roof*

You'll find this new Buying Guide extremely helpful and valuable today! Places over 10,000 items at your finger tips—for research, maintenance and production. Includes parts, tubes, tools, books, test instruments, public address and communications equipment. Concentrates all leading makes here in one large central stock to give you faster, more efficient, more complete service—saves you time, work and money. Whatever you need . . . it pays to check with Allied. *Write, wire or 'phone Haymarket 6800.*

Everything in Radio and Electronics
ALLIED RADIO CORP.
833 W. Jackson Blvd., Dept. 24-D-6, Chicago 7, Illinois

FREE
Send for it
NOW

unit can also be made to actuate a camera shutter. Twenty watts of power at 115 v 60 cps is required to operate the equipment which measures 8 x 8 x 8 in. The phototube housing is 1½ x 1½ x 4 in.

39

Coil Mounting

TINNERMAN PRODUCTS, INC., 2106 Fulton Road, Cleveland 13, Ohio, has just announced a new secure mounting for coil forms in radio chassis



assemblies. The fasteners are available for mounting $\frac{5}{32}$ and $\frac{3}{8}$ in. forms to panels of various thicknesses. Samples are available.

40

Control Relay

ALLIED CONTROL CO., INC., 2 East End Ave., New York 21, N. Y. The type CR relay is light in weight but has contacts capable of carrying 15



amp at 24 v d-c or 110 v a-c, noninductive. The single-pole unit is $1\frac{31}{32}$ x $1\frac{5}{16}$ x $1\frac{31}{32}$ in. and weighs 3 oz. A variety of contact combinations is available.

41

Miniature Transformers

UNITED TRANSFORMER CORP., 150 Varick St., New York 13, N. Y. Now

USE STANDARD PARTS—SAVE TIME AND MONEY



SAVE

For many years
Automatic has manufactured
Coils and Trimmers for manufacturers.

Our mass-production methods
will save you money and headaches.

Order your Coils and Trimmers from
people who "know how".

ARMY E NAVY

AUTOMATIC MANUFACTURING CORPORATION

MASS PRODUCTION COILS & MICA TRIMMER CONDENSERS

900 PASSAIC AVE. EAST NEWARK, N. J.

A major advancement in the recording blank field . . .

10 Year

GUARANTEE

GOULD-MOODY

"Black Seal"

ALUMINUM RECORDING BLANKS

. . . at no increase in price!

After prolonged research and experimentation, we have introduced technological improvements into "Black Seal" blanks that not only increase life span, but materially enhance the other finer characteristics of these blanks. And so positive are we of the worth of these perfected "Black Seals" that we're offering them to you on an unconditional ten-year guarantee basis.

You can't afford to be a recording isolationist . . .

"Black Seal" blanks will not rip up, disintegrate or powder after the first playing if kept in storage for any long period of time. You are in no danger of losing valuable recordings in what, up until now, you have considered your safe library of recording blanks. No matter how well you may be satisfied with your present blanks, you can't afford to be a recording isolationist. Try "Black Seals"—if, for any reason whatsoever, you aren't satisfied, return them at our expense.

THE GOULD-MOODY CO.
Recording Blank Division
395 BROADWAY NEW YORK 13, N. Y.

available is a new series of Sub-Ouncer transformers so far used only in military equipment. Coils are uniform layer-wound of Formex wire on a molded nylon bobbin. Re-



sponse of standard types is within ±3 db from 200 to 5,000 cps. The five types available immediately measure $\frac{9}{16}$ x $\frac{5}{8}$ x $\frac{7}{8}$ in. and weigh $\frac{1}{3}$ oz.

42

Jewel Bearing

MARION ELECTRICAL INSTRUMENT Co., Manchester, N. H., has developed a new jewel-bearing assembly for D'Arsonval instruments. It con-



sists of a metalized boro-silicate glass V jewel which is induction-soldered into position to replace the conventional screw setting and jewels. The new, simplified assembly is shown at the left.

43

Conductivity Cell

INDUSTRIAL INSTRUMENTS, INC., 17 Pollock Ave., Jersey City 5, N. J. The type CEL-F wand-type cell can be safely immersed in a vat or tank and withdrawn after the reading is

Electronics

NEW IMPROVED AND STANDARD MICROPHONE JACKS AND PLUGS



Model M-151
Improved and Standard Type Microphone Jacks and Plugs
Solid, silver plated contact coupling can be unscrewed completely for soldering.

Model M-161
Chassis mounting, solid silver plated contact. Milled flat prevents turning.

Model M-170
Mates with Model M-151 and M-150 standard solder contact.



Model M-160
Chassis mounting standard. Solder contact.

Model M-150
Standard solder contact. Mates with Models M-170, M-161, and M-160.

PRICE AND DELIVERY UPON REQUEST
SEND FOR OUR LATEST BROCHURE.

KINGS ELECTRONICS CO.
372 CLASSON AVE., BROOKLYN 5, NEW YORK

Always Reliable-All Ways!



SEEBURG RECORD CHANGERS

MINIMUM FRICTION • SILENT • CONSTANT SPEED
LONG LIFE • TROUBLE-FREE OPERATION

RELIABILITY of operation is the prime requisite of a good record changer. New and more efficient features have been added to the complete line of SEEBURG RECORD CHANGERS . . . but only after these features were given exhaustive laboratory and field tests . . . for **RELIABILITY** is the quality that is built into all SEEBURG RECORD CHANGERS. Years of trouble-free operation in actual use is the best proof that SEEBURG RECORD CHANGERS are Always Reliable—All Ways!

SEEBURG *Wire* RECORDER

An Electronic Engineering Achievement

The SEEBURG WIRE RECORDER is a revolutionary new recording and reproducing instrument. The versatility of the SEEBURG WIRE RECORDER readily lends itself to practical uses in the commercial, legal and entertainment fields. One simple control knob operates the SEEBURG WIRE RECORDER to record and reproduce speeches, plays, meetings, music, radio programs, etc. There are no needles or discs used.

IT WILL BE NECESSARY...

for radio manufacturers to make provisions in their circuits to accommodate the SEEBURG WIRE RECORDER. We therefore invite prompt inquiries from interested radio manufacturers.

Seeburg

DEPENDABLE MECHANISMS 1946

J. P. SEEBURG CORP., CHICAGO

INDUCTOR HEADQUARTERS

B&W

Midget Coils for Dozens of High-Frequency Uses

MINIATURE R-F INDUCTORS

B & W MINIDUCTORS meet the fast-growing need for finely-made miniature coils for modern high-frequency services. Standard diameters range from ½" to 1¼". AIR-WOUND construction assures an amazingly high Q characteristic. Miniductors are supplied in any length and for any type of mounting. Coupling links and other features as required. Write for Bulletin.



GENERAL PURPOSE ROTARY COILS

From midget sizes only a few inches long with dual opposed windings or other special features to giant units for transmitting, dielectric heating or other uses B & W Rotary Coils providing continuous adjustment throughout the entire length of the winding, are supplied in a wide variety of types. Submit details of your application for recommendation by B & W engineers.

EDGE-WISE WOUND INDUCTORS



Furnished in diameters from 1¼" to upward of 10". Minimum size of copper strip 3/16" x .050"; maximum 1" x .250". Inside or outside mountings available, plain or tapped coil styles. Rotary or continuously adjustable units supplied with either inside or outside contacts. Write for details.

WE'LL MATCH ANY INDUCTOR REQUIREMENT

ARMY E NAVY

BARKER & WILLIAMSON

Dept. E-46, 235 Fairfield Avenue
Upper Darby, Penna.



determined from an associated conductivity bridge. It takes the form of a Pyrex wand measuring approximately 1 in. outside diameter by 20 in. long.

44

Cardioid Mike

ELECTRO-VOICE, INC., 1239 South Bend Ave., South Bend 24, Ind. The Model 950 Cardax microphone has a dual frequency-response selector and an on-off switch. Its cardioid response allows greater gain to the loudspeakers of a public address system without feedback. Equipped with a built-in connector, ⅝ in.-27 thread and 20-ft cable, the new mike lists at $37.

Literature

45

Dry Plate Rectifiers. Selenium Corp. of America, 1719 West Pico Blvd., Los Angeles 15, Calif. Catalog B presents a fairly complete sketch of selenium rectifiers from the discovery of the basic metal in 1817 up to a summary of new developments on page 34. The pages between are full of circuits, specifi-

What type of STAINLESS FASTENER do you need?

Prompt delivery from the largest stock in the nation!

Screws . . . nuts . . . washers . . . pins . . . Allmetal carries the largest stock in the country of stainless steel fasteners and screw machine parts. We also have facilities for heading, tapping, drilling, reaming, slotting, turning, stamping, broaching and centerless grinding . . . and we work not only with stainless and monel, but also with duralumin, aluminum, brass, bronze, or any other non-corrosive metal. All parts produced to close tolerances. Write for our catalog today. Allmetal Screw Products Co., 33 Greene St., New York.

Send for FREE CATALOG

This new, 63-page catalog helps you select the correct size and type of non-corrosive fastening device for any particular job. Includes stock sizes, specials that can be made, engineering data, etc. Make request on company letterhead.

ALLMETAL SCREW PRODUCTS CO.

33 Greene Street, New York 13

SPECIALISTS in STAINLESS FASTENERS



The RADACOR TUNER

● Typical example of Micro-Ferrocart's precision-engineering is the Radacor Model T11 Tuner shown here. Sturdily constructed, simply designed, this highly efficient component was evolved to help solve your present-day problems of procurement and engineering.

● If you are interested in this newest of Micro-Ferrocart components, or if you contemplate the manufacture of any product that involves electronic or mechanical powder metallurgy, why not write to us today. The engineering skill that has created for Micro-Ferrocart its reputation for "quality in production" is at your service.

ELECTRONIC & MECHANICAL POWDER METALLURGY

MICRO-FERROCART PRODUCTS DIVISION

MAGUIRE INDUSTRIES, INC., 375 FAIRFIELD AVE., STAMFORD, CONN.

BIG AND IMPORTANT

The new Gothard Indicator Light Assemblies Catalog is bigger and better than any similar catalog ever published. It offers a wealth of scientific data, which will greatly aid you in selecting the right assembly for your industrial, household appliance, radio or other applications. It also illustrates and describes the largest selection of Underwriters approved assemblies fot any voltage and style of miniature lamps and built-in resistor assemblies for neon lamps. Here is the latest data published on Indicator Light Assemblies—ask for your copy immediately.

Gothard MANUFACTURING COMPANY
2114 CLEAR LAKE AVENUE, SPRINGFIELD, ILLINOIS
EXPORT DIVISION: 25 WARREN STREET • NEW YORK 7, N. Y.

FIBRE FABRICATION TECHNICAL DATA FREE

WRITE FOR BULLETIN 120

Baer
PHENOL AND VULCANIZED
FIBRE
FABRICATIONS
FOR
INDUSTRY

Design short-cuts- cutting engineering and assembling time

Time saved in preliminary planning is directly proportionate to efficiencies effected in the blueprint stage. By designing-in BAER fibre fabrications—whether your product is instrument, machine, appliance or equipment—the utmost in production stream-lining is assured. Further, the inherent advantages of the material—accurately machined, stamped, punched, drilled, milled or sawed by BAER craftsmen—adds a full measure of dependability under varying service conditions.

N. S. BAER COMPANY, 9-11 MONTGOMERY ST., HILLSIDE, N. J.

cations, and descriptions of uses to which cataloged items can be put.

46

News Digest. General Electric Co., Schenectady, N. Y., publishes a quarterly News Digest reporting activities and developments in the company; not a technical publication.

47

Nickel. International Nickel Co., Inc., 67 Wall St., New York 5, N. Y. List A contains an index of current papers on the uses and properties of metals, including one of interest to the ceramic industry.

48

Components. Aircraft Radio Corporation, Boonton, N. J. In addition to preliminary data on microwave components and aircraft communications equipment, bulletins are available covering fasteners, multi-con-



tact plugs and receptacles, switches, d-c relays, sealed capacitors, chokes and transformers and variable air capacitors suitable for transmitting or receiving equipment.

49

Direction Finders. Sperry Gyroscope Co., Inc., Great Neck, N. Y. Publication 15-43 describes an aircraft radio direction finder, listing specifications and tests taken by CAA approved methods.

50

Nomographs. Federal Telephone and Radio Corp., Newark 1, N. J. A folder containing technical data in the form of single sheets will be found useful to engineers interested in determining such information as

Industry's New World

High Vacuum offers to industry a vast new area, virtually unexplored. No one knows its extent or its resources. No one can say what opportunities are there for your industry. No one can tell you, but National Research Corporation can help you find out as it has helped many others. It can furnish the technology and equipment as it did for the wartime production of Magnesium.

In 1938 the United States produced 2,400 tons of Magnesium while Germany made six times as much. As the war progressed, the demand for aircraft and incendiary bombs increased. Magnesium had become a fighting metal.

As this country became increasingly involved in war, Magnesium became a strategic material that must be produced in quantity — at any cost. There was no time to debate processes. From 1940 to 1942 OPM and WPB built 14 plants using four basic methods never before tried in this country. In 1943, 185,000 tons of Magnesium were produced.

While three of the new processes struggled with problems of large-scale production, WPB turned to the National Academy of Science for further recommendations and was directed to the Canadian National Research Council and the Dolomite-Ferrosilicon process, then developed on a laboratory scale by Dr. Lloyd M. Pigeon.

In this process Magnesium is vaporized from briquettes at temperatures from 1100° to 1150° C. and pressures of about 10^{-2} mm. Hg. The vaporized metal is crystallized in cooled cylinders. While the process appeared to be the simplest of all the methods, it was, in practice, harassed by grave difficulties, not the least of which was the maintenance of high vacuum on an industrial scale, hitherto undreamed of.

At the request of WPB, National Research, under a DPC research contract (Plancor 708), was given the task of solving this vacuum problem, then the largest industrial project involving pressures in the micron range.

Six weeks after receiving the assignment we had a pilot plant in operation. During the following four months we designed large diffusion pumps to improve the yield and shorten the cycle, developed recording gauges for process control and evolved vacuum engineering techniques of value in the design of the larger plants.

Deliveries of equipment were made for a full-scale plant already building in Canaan, Connecticut, for the New England Lime Company. Of all the Magnesium plants begun in wartime, some completed before we were given our assignment, this was the first to be in production. Later equipment was supplied to others, including Ford at River Rouge.

It has been said of the Dolomite-Ferrosilicon process that it was "the most spectacular development of the war" and "the primary candidate for postwar scrapping". Whatever its fate, we are proud of the work that we did in making it quickly practical. This is typical of the sort of engineering that N.R.C. has to offer — the sort of service that you may expect from us when you explore the new world of high vacuum.

NATIONAL RESEARCH CORPORATION, Boston 15, Massachusetts.



We engineer plant installations and manufacture High Vacuum Gauges, Valves, Seals, Diffusion Pumps, Stills, Furnaces, Coating Equipment and Dehydration Equipment.

HIGH VACUUM FOR INDUSTRY

NATIONAL RESEARCH CORPORATION

Vacuum ENGINEERING DIVISION

HARVEY

is now delivering reasonable quantities of

ALTEC LANSING

FM MONITORING EQUIPMENT

and

RECORDING AMPLIFIERS

Designed in the famous Altec Lansing Hollywood laboratories for film recording. Takes the guess work out of FM . . . the only equipment of its kind. HARVEY'S experienced staff can answer technical questions and advise on installation.

604 DUPLEX SPEAKER

. . . combining high and low frequency units in one horn, eliminating intermodulation effects and distortion through FM range, 50 to 50,000 cycles. With Dividing Network, $250.00

A-323 AMPLIFIER

. . . compact, 6-tube, 18-watt linear amplifier, designed for operation with the Duplex speaker from low level phonograph pick-ups, microphones or radio tuners.

Without input transformer; high impedance input $118.00

With input transformer; 30, 250 and 500 ohms impedance.....$158.00

Telephone LOngacre 3-1800

hrc HARVEY RADIO COMPANY

103 West 43rd St., New York 18, N. Y.

the attenuation in square wave guides, power dissipated in water-cooled devices, and paint requirements for various shaped pieces.

51

Limit Bridge. Freed Transformer Co., 72 Spring St., New York 12, N. Y., has a brochure available for the



new No. 1010 comparison and limit bridge useful in production testing of components. The instrument sells for $150.

52

Temperature Control. H-B Instrument Co., 2519 N. Broad St., Philadelphia 32, Pa. Catalog No. 14 contains 16 pages of illustrations and details of temperature control for ovens, heating baths and refrigerants.

53

Ceramic Capacitors. Electrical Reactance Corp., Franklinvile, N. Y., has just published a bulletin to describe, according to JAN specifications, its line of type CN capacitors with parallel leads.

54

Marine Electronic Equipment. General Electric Co., Schenectady 5, N. Y., will send a non-technical 16-page buletin about electronic aids to navigation to anyone interested in depth finders, direction finders or radar-type lookout.

55

Antennas. Insuline Corp. of America, 36-02 35th Ave., Long Island City, N. Y., has published its 1946



THERE IS NO SUBSTITUTE FOR EBY SPRING BINDING POSTS

From the product designer through to final assembly and use in the field, the Eby Spring Binding Post line offers top service based on dependability.

The spring binding post offers unique advantages that can't be duplicated:

1. No screw cap to tighten or come loose with vibration.
2. Constant, even pressure on the wire at all times in all positions.
3. Easy one-hand feeding of wire into the post.
4. Corrosion - resistant, long-life springs.
5. Complete range of sizes, stem lengths, and accessories for every application.

Replace with Eby Spring Binding Posts — Write today.

HUGH H. EBY INCORPORATED 10 W. CHELTEN AVE. PHILADELPHIA, PA.

MINIMUM SIZE IN METERS

...FOR "VEST-POCKET" PORTABILITY



ACTUAL SIZE

MB MINIATURES HAVE A 1-INCH MOUNTING DIAMETER

A *big* fact to remember, when designing portable products for compactness, is this: *MB precision meters are the smallest made today.* Their use in many testing devices adds "carrying-convenience"... an influential sales factor.

It's one good reason for putting MB miniatures to work in equipment like photographic exposure meters, electrical tachometers, and other important instruments. In the many unusual applications for which MB meters are now being specified—pocket voltmeters to test hearing aid or flashgun batteries, for example—the equipment takes no more space than a matchbox or watch.

But, in addition to unmatched size, MB instruments offer precision performance. Response is fast . . . and accurate to the ±2% AWS specification, giving reliable readings on the well-defined scales. Damping characteristics are excellent. The lightweight moving element, in anodized aluminum housing, resists damage from shock and vibration . . . assures long, dependable service life. In short, MB meters can be used in both precision industrial testers and those for consumer use with equal advantage.

Write for information on the complete line of MB 1-inch and 1½-inch meters. These models, available in both round and square shapes, are adaptable to many special purposes. An MB engineer will be glad to work out the details with you.

THE MB MANUFACTURING COMPANY, INC.
331 East Street, New Haven 11, Conn.

INSTRUMENT DIVISION

MINIATURE ELECTRICAL METERS FOR ANY PURPOSE

CHECK THE PATENTED FEATURES AND GREATER ECONOMY OF DRAKE LIGHT ASSEMBLIES



You'll lower production costs yet increase quality and efficiency with DRAKE Socket and Jewel Pilot Light Assemblies. Get the benefit of our patented features . . . of high speed precision methods and machinery developed thru 15 years of specialization. Every conceivable type offered in standard and special designs. Refer to the newest DRAKE catalog for complete information. Do you have a copy?

DRAKE

SOCKET AND JEWEL LIGHT ASSEMBLIES

DRAKE MANUFACTURING CO.

1713 W HUBBARD ST CHICAGO 22 ILL

antenna catalog including information on f-m and television, auto-radio antennas and a complete line of parts.

56

Electronic Education. General Electric Co., Thompson Road Plant, Syracuse, N. Y. is distributing booklet EBR-28 which describes the role of electronics in education. A list of publications bearing on this subject is included.

57

Research Organization. Polytechnic Research & Development Co., Inc., 66 Court St., Brooklyn 2, N. Y., has a brochure describing the services it intends to make available to industry in the field of applied physics. The organization is an outgrowth of P. I. B. Products, Inc.

58

Tubes. Eithel-McCullough, Inc., San Bruno, Cal. has available a non-technical booklet picturing its line of tubes, vacuum pumps and vacuum capacitors together with a price list.

59

Microwave Apparatus. Sperry Gyroscope Co., Inc., Great Neck, N. Y. A new catalog in three parts pictures some of the latest equipment available for civilian use in the



microwave region of the radio spectrum. Microwave measurements, klystrons and wave-guide components are included. The Model 127 30-mc variable attenuator is illustrated.

60

Tube Characteristics. Sylvania Electric Products Inc., Emporium, Pa. Characteristics of radio tubes,

WEILINE

POSITIVE PRINT PAPERS

MAKE POSITIVES DIRECT

From Drawing

With Weiline you skip many time-consuming steps in print-making. You get perfect work prints in a fraction of the time. True-to-scale prints because dry-developed. No wet chemicals used. No washing. No curling. And a variety of sensitized papers give you the choice of several types of prints.

BLUE • RED • SEPIA

- You can have all-purpose prints with *Blue lines*, or *Red lines*, on white background.
- This is useful in distinguishing prints from different depts., or to tell checked from unchecked prints.
- *Sepia Transparentized Prints* can be made the same rapid way, for use as Intermediate Originals.
- These can replace valuable originals in print making, or can be used to speed up print production.
- Or, to save *draftsman's time* retracing when making design changes.

Write for Free Sample Book and Full Information

It's easy to adopt Weiline in any Engineering dept. Let us tell you how. Write Dept. D.

J. H. WEIL & CO.

1315 CHERRY STREET

PHILADELPHIA 7, PA.

DRAFTING MATERIALS
SENSITIZED PAPERS
ENGINEERING INSTRUMENTS

FOR TROUBLE-FREE WIRE PERFORMANCE

125 Permanently Insulated ROCKBESTOS Wires, Cables and Cords

From the three basic designs illustrated Rockbestos has developed a complete line of 125 failure resisting wires, cables and cords, a few of which are described. All have the same performance guaranteeing characteristics detailed below. Write for information, samples.

Rockbestos Permanent Insulation Insures Long-Lived Service

1. A tough impregnated asbestos braid, resistant to heat, flame, moisture, oil, grease, alkalies and corrosive fumes.
2. Felted asbestos insulation impregnated with heat, flame and moisture resistant compounds will not dry out with age, burn, or bake brittle under high temperatures.
3. Lubricated varnished cambric for high dielectric strength and added moisture resistance — protected from heat, flame and oxidation by felted asbestos walls.
4. Impregnated asbestos insulation that withstands heat of overloads and aging and won't become brittle, crack, rot or burn.
5. Conductors are perfectly centered in helically applied non-flowing insulation and will always remain so.

ROCKBESTOS FIREWALL RADIO HOOKUP WIRE

Sizes No. 22 to 4 AWG in 1000 volt rating, and No. 12, 14 and 16 AWG in 3000 volt insulated with high dielectric synthetic tape, impregnated felted asbestos and covered with color coded lacquered glass braid.

Originally designed to meet the demand of airborne radio equipment manufacturers for a flame and heat resistant wire and widely used since in ground, marine and mobile communications systems, electronic devices and apparatus. Operating temperature range 125° C. to minus 50° C. Ideal for wiring harnesses in compact apparatus and small motor, coil, transformer and dynamotor leads. Also available in twisted pair, tripled, or cabled multi-conductor constructions.

ROCKBESTOS FIREWALL MULTI-CONDUCTOR INSTRUMENT CABLE

This unusually small, light weight, high-dielectric No. 26 AWG three conductor cable, with individuals insulated like our hookup wire, was designed for use where space is at a premium and dependable performance is essential. Made to a nominal diameter of .125″ it is smaller than a No. 14 AWG Hookup Wire. Also in 4, 5 and 6 conductor in sizes No. 26 to 20 AWG.

ROCKBESTOS THERMOSTAT CONTROL WIRE

Sizes No. 14, 16 and 18 AWG in two to six conductors with .0125″, or .025″ or (for 115 volt service) .031″ of impregnated felted asbestos insulation and steel armor.

A multi-conductor control wire for low voltage inter-communicating, signal, and temperature control systems. Lifetime heatproof, fireproof insulation and rugged steel armor give trouble-proof circuits.

ROCKBESTOS A.V.C. 600 VOLT SWITCHBOARD WIRE

(National Electrical Code, Type AVB)

Sizes No. 18 to No. 4/0 AWG with varnished cambric and impregnated asbestos insulation and gray, black, white or colored flameproof braid.

Combine fire insurance and fine appearance in your switchboards with Rockbestos Switchboard Wire. It is fireproof and will not dry out under heat. Sharp, clean bends can be made without cracking as the asbestos wall acts as a cushion under the braid. Rockbestos A.V.C. Hinge Cable and Switchboard Bus Cable have same fireproof and heatproof characteristics.

ROCKBESTOS ALL-ASBESTOS LEAD WIRE

Sizes No. 8 to 20 AWG solid or stranded copper, monel or nickel conductors insulated with .031″ or .040″ of impregnated felted asbestos in black, white or colors.

Resistant to heat, flame, oil and grease this wire won't dry out, crack, flow, swell or rot. For higher dielectric strength and moisture resistance specify Type CA Lead Wire with synthetic tape next to the conductor.



ROCKBESTOS ALL-ASBESTOS 600 VOLT FLEXIBLE CORD

Sizes No. 10 to 18 AWG with two or three conductors insulated with impregnated felted asbestos and covered with asbestos braid.

This heavy duty heat-resisting flexible cord is ideal for leads on instruments and apparatus that develop heat in operation or may be used in hot locations. For moisture resistant type specify Rockbestos A.V.C. construction described below.

ROCKBESTOS A.V.C. 600 VOLT FLEXIBLE CORD

Sizes No. 10 to 18 AWG with two or three conductors insulated with impregnated felted asbestos, varnished cambric, felted asbestos covered with heavy impregnated asbestos braid.

For applications such as mentioned above in which heavy duty, high-dielectric, heat and moisture resistant flexible cord is required we recommend this construction with individual conductors insulated exactly like Rockbestos A.V.C. Motor Lead Cable.

ROCKBESTOS 300 VOLT HEAT RESISTING DUPLEX FLEXIBLE CORD

(Underwriters' Type AFPD)

Sizes No. 10 to 18 AWG stranded plain copper conductors insulated with impregnated felted asbestos, polarized, twisted together and covered with a cotton braid.

This heat-resisting flexible cord made of two Type AF fixture wires covered with braid is approved by the Underwriters' Laboratories for fixture wiring. Also recommended for apparatus leads where moisture resistance is not required.

SHIELDED ROCKBESTOS FIREWALL HOOKUP WIRE

Sizes No. 22 to 4 AWG in 1000 volt rating and 12, 14 and 16 AWG in 3000 volt insulated with synthetic tape and impregnated felted asbestos, covered with color-coded lacquered glass braid, and shielded with a tinned copper braid.

High in dielectric strength and resistance to heat, flame, moisture, oil, grease, gasoline and cleaning fluids like unshielded Rockbestos Firewall Hookup Wire, this construction protects performance in radio equipment and communications systems. 1000 volt type also made in twisted pair, tripled and various multi-conductor constructions.

ROCKBESTOS APPARATUS HEATING CABLE

No. 19 AWG nickel-chromium resistance wire insulated with .040″ of impregnated felted asbestos and covered with 4/64″ waterproof lead sheath.

Manufacturers of devices requiring the controlled distribution of a mild heat can use this pliable cable to advantage. It can be easily bent and formed to fit in or around irregular shaped objects to put heat where you want it.

ROCKBESTOS A.V.C. 600 VOLT MOTOR LEAD CABLE

(National Electrical Code, Type AVA)

Size No. 18 AWG to 1,000,000 CM insulated with two walls of impregnated asbestos and a high-dielectric varnished cambric insert, with a heavy asbestos braid overall.

Use this apparatus cable for coil connections, motor and transformer leads exposed to overloads or high ambient temperatures. It makes a permanent installation as it is resistant to heat, flame, oil, grease and moisture.

ROCKBESTOS ASBESTOS INSULATED MAGNET WIRE

Round, square and rectangular asbestos insulated conductors finished to meet varying winding conditions and coil treatment requirements. Designed for Class B windings, the insulation is non-checking and not affected by heat or aging.



ROCKBESTOS PRODUCTS CORP.
434 NICOLL STREET, NEW HAVEN 4, CONN.

ROCKBESTOS

The Wire with Permanent Insulation

The trend toward **compactness** in much of today's industrial construction is well met by this **accurate** H-B Midget Thermometer. It **fits snugly** into spaces where clearances must be measured in fractions of an inch. If heavy vibrations or shocks are to be encountered, its sturdy armor gives **added strength** and **longer life.** Made in both straight and angle types, weighing but 5 and 7 ozs. respectively; and in standard ranges from minus 30 to plus 750° F., and special ranges can be had in both Fahrenheit and Centigrade scales in almost any desired temperature range level. Straight type, 9 in. overall. **Easy to read** because of lens-front and yellow back with scale engraved on glass. For details, write to—H-B Instrument Company, 2524 N. Broad Street, Philadelphia 32, Pa.

THERMOMETERS
HYDROMETERS
THERMOSTATS RELAYS
THERMO-REGULATORS

DOUBLE H B DIAMOND



D.C. to A.C. by JANETTE

UP TO 3.2 K.V.A.

D.C. TO A.C. CONVERTERS

Electronic and Gaseous Tube Devices can be operated from direct current power by means of a rugged Janette converter. When used with sound devices, specially designed filters discriminating enough to filter out unwanted noises and to minimize conducted radio noise voltage, can be furnished.

For nearly a quarter of a century Janette converters have given dependable service under varied climatic conditions in all parts of the world.

If you have a D.C. to A.C. requirement and want a reliable, high quality converter you can safely specify a Janette.

Janette

Ask for Bulletin 13-25

Janette Manufacturing Co. 556 W. Monroe St. Chicago 6, Ill.

cataloged in both numerical and alphabetical order, are given in an 18-page booklet recently published.

61

Mobile Radiophone Service. American Telephone and Telegraph Co., 195 Broadway, New York 7, N. Y., is issuing two booklets describing a proposed mobile service and one type of mobile equipment.

62

Measurement Equipment. Boonton, Radio Corp., Boonton, N. J., has just issued a supplement to its Catalog C covering precision signal generators, a mica tester and a spark coil test set.

63

Mica Ceramic Insulation. Electronic Mechanics, Inc., 70 Clifton Boulevard, Clifton, N. J. Bulletin No. 104 gives suggestions for use of Mykroy insulating material in the fabrication of sockets and terminal supports.

64

Radio Teletype. Globe Wireless Ltd., Chrysler Bldg., New York 17, N. Y., has a non-technical booklet describing applications and operation of the Radiotype system.

65

Induction Heating. Lepel High Frequency Laboratories Inc., 39 W. 60th St., New York 23, N. Y. A 31-page booklet illustrates the manifold uses of induction heating in the industrial field. Soldering, brazing and gear hardening are all possible on the same equipment with a proper choice of work coil for the individual job.

66

Small Switches. Mu-Switch Corp., Inc., Canton, Mass. has evolved an interesting catalog with split pages making it easy to refer to the various switch types and at the same time thumb through a secondary cataloging of their characteristics. There are more than 19 pages of photographs, specifications and prices.

STUDIO AMPLIFIERS

Engineered for High Quality Performance and Dependable Service



AT LEFT: Two Langevin Type 111-A Dual Pre-Amplifiers and one Langevin Type 102-A Amplifier on a Type 3-A Mounting Frame. This unit provides four pre-amplifiers and one line amplifier, or three pre-amplifiers, one booster amplifier and one line amplifier, all occupying 10½ in. of rack mounting space. An external power supply, the Langevin 201-B Rectifier, as shown below, is required. The Type 3-A Mounting Frame can be housed in a Type 201-A Cabinet, for wall mounting, if desired.



The Type 106-A Amplifier is a two-stage, fixed medium gain, low noise pre-amplifier, or booster amplifier, for use in high-quality speech input systems. The Type 106-A can be mounted on one-third of the space available on a Type 3-A Mounting Frame in combination with two Type 111-A Pre-Amplifiers, or in any similar combination.



The Type 201-B Rectifier supplies plate and filament power for the Langevin Types 102, 106, 111 and similar amplifiers from a 105-125 volt, 50-60 cycle AC source. The ripple voltage of the 201-B Rectifier is 0.04% at full power output 75MA and 0.02% at a drain of 30 milliamperes.

Langevin Audio Transmission Facilities are designed and built to have the extended frequency response, noise and distortion levels required in the F.C.C. Regulations for FM transmission.

In complying with these regulations too much emphasis cannot be placed on the quality of the transformers that are a part of the audio system. Noise, for instance, is largely associated with the input transformers—distortion, with the output transformers—and frequency response with both. Therefore, the transformers in Langevin equipment are manufactured by us—and are held to a specified tolerance—so that frequency response, noise and distortion levels of the entire system are well within requirements.

"Worthy of an Engineer's Careful Consideration"

The Langevin Company

INCORPORATED

SOUND REINFORCEMENT AND REPRODUCTION ENGINEERING

NEW YORK
37 W. 65 St. 23

SAN FRANCISCO
1050 Howard St.

LOS ANGELES

NEWS OF THE INDUSTRY

Reports on German industry; CAA vhf radio; Lanac; telediffusion in Sweden; guided missile project; wireless television camera; RMA Spring Meeting

War Department Unveils 18,000-tube Robot Calculator

VIRTUAL ELIMINATION of computing time in the solution of mathematical problems is just one of the amazing achievements of the Eniac, an 18,000-tube electronic computer revealed Feb. 15 by the War Department. For problems ranging from prediction of electron paths of nuclear physics to the trajectories of guided missiles and the orbits of planets in cosmic space, this world's largest and most intricate electronic device provides on a printed sheet in a few hours, with up to six carbons, numerical tables that have heretofore required as many as 100 man-years of computed time.

The Eniac (Electronic Numerical Integrator and Computer) was designed and constructed for the Army Ordnance Department at the Moore School of Electrical Engineering, University of Pennsylvania, Philadelphia to break a mathematical bottleneck in computing lengthy and complicated firing and bombing tables for vital ordnance equipment.

Ballistic Applications

For each angle of elevation at which an artillery piece is fired, a different trajectory has to be calculated, embracing such factors as muzzle velocities, powder temperatures, projectile weight, range, time of flight, point of fall, and atmospheric conditions. In addition, such matters as ballistic coefficient and drag function must be taken into account. It takes a skilled computer about three days to compute one such trajectory with the aid of an ordinary desk calculating machine. After the trajectories are calculated, the angles of elevation for many different ranges, using varying conditions of muzzle velocity, density of air, wind, etc. are computed. This part of the work usually takes about three months by a large staff of trained computers. The Eniac will do both sections of the job in from one to two days.

Industrial Uses

The new robot calculator will solve equally complex peacetime problems in electronics, electrical engineering, aerodynamics and scientific weather prediction. In industry, it is believed that better, more scientific design will now be possible as a result of the new machine's ability to handle hundreds of different factors in one computation. Much lengthy and costly design experimentation, often involving the construction of a series of expensive models, a common practice in airplane design, might also be eliminated. Such trial-and-error methods would not suffice to deal with complex phenomena arising, for instance, from the blast of an atomic bomb.

General Details

The original idea for the Eniac was that of Dr. John W. Mauchly, of the Moore School faculty. Captain Herman Goldstine, mathematician and ballistic expert for Army Ordnance, enthusiastically promoted development of the Eniac.

Administrative supervision of the project was assumed by Dr. J. G. Brainerd of the Moore School, and J. Presper Eckert, Jr. took charge of the technical and engineering activities.

The Eniac is a digital or discrete variable computing machine, as opposed to continuous variable types such as differential analyzers. If used to complete capacity, the Eniac will carry out in five minutes more than ten million additions or subtractions of ten-figure numbers. The machine performs a single addition in 1/5000th of a second and can do a number of distinct additions simultaneously.

The Eniac occupies a room 30 by 50 feet in size, weighs 30 tons, and has 100 feet of panels arranged in a large U, with 16 of the panels on each leg and 8 panels on the end. Power consumption is 150 kw, of which 45 kw goes to a bank of 28 power supplies that provides the 88 d-c voltages required.



Setting up the Eniac for a problem takes far more time than is required for the machine to punch out the answers on the IBM machines at the right. Power supply panels are across the open end of the U, behind the camera used in taking this photograph

Operating Procedure

The general method of handling a problem is as follows: First, the scientist must write down mathematical equations that express the phenomena involved. Second, he must break down the mathematical formulation into a sequence of additions, subtractions, multiplications, divisions, square rootings and transfers from

COMPLETE

FIXED-FREQUENCY COMMUNICATIONS SYSTEMS

AM or FM

TRANSMITTERS — RECEIVERS — ANTENNAS

- FIRE and POLICE WORK
- FORESTRY
- TELEVISION RELAYS
- INDUSTRIAL APPLICATIONS

Custom-built for ANY FREQUENCY between 100 and 3000 MC's for...

Regardless of the type of communications system you have in mind . . . private, municipal or industrial . . . LAVOIE can supply all necessary equipment to do the job clearly, efficiently and economically. LAVOIE VHF and UHF equipment won widespread acceptance in the U. S. armed forces during the war, and this same precision manufacture and efficient operation is found in LAVOIE fixed-frequency equipment.

If you will state the general nature of your requirements, we will recommend and quote on a system best suited for your needs.

FREQUENCY METERS
FREQUENCY STANDARDS

TRANSMITTERS
RECEIVERS, ANTENNAS, ETC.

Lavoie Laboratories

RADIO ENGINEERS AND MANUFACTURERS
MORGANVILLE, N. J.

Specialists in the Development and Manufacture of UHF Equipment

PRECISION PARTS

•

SPINNING THE THREAD OF THE FUTURE



Spinning spindles, whirring bobbins, the shuttling back and forth of warp and woof . . . these are sweet sounds to the ears of a textile-starved America. Spindles that spin so speedily have to be built with fine-spun accuracy, and the incredible accuracy Ace built into parts for guns and engines, radar and radio, is now being built into parts for the machines of peace.

This slender spindle, a very essential part of a textile machine, is a perfect example of the ability of Ace to do fine precision-work on a mass-production basis. Twenty-four different operations were performed to produce its 22 dimensions . . . dimensions that had to be held to a tolerance of .0005" . . . roughing, heat-treating, straightening, finishing. Two finishing-operations were done by centerless grinding, seven by cylindrical grinding, producing tapers and radii where required. Periodic inspections kept overall straightness within .002".

Incredible accuracy on a mass-production basis . . . that's the story of Ace. For small parts and assemblies that require stamping, machining, heat-treating, and grinding . . . all under a single roof, single responsibility . . . it will pay you to have an Ace up your sleeve. Send us a sample, sketch or blueprint for quotation.

This free booklet describes facilities available.

ACE
TRADE MARK

ACE MANUFACTURING CORPORATION

for Precision Parts

1255 E. ERIE AVE., PHILADELPHIA 24, PA.

unit to unit of the Eniac. Finally, program switches must be set, numbers must be put into the function table memory by setting the switches, and connections must be established between units of the Eniac for the communication of programming and numerical information.

There are three basic elements in the Eniac: arithmetic elements, memory elements and control elements. There is also magnitude discrimination, which partakes of both arithmetic and control characteristics and consists of comparing the size of two numbers. On the basis of such comparison, the machine determines which of two computational courses is to be followed.

Arithmetic Elements

The arithmetic elements include 20 accumulators, 1 multiplier and 1 combination divider and square rooter. The accumulators provide means for storing numbers computed in the course of a problem, and also permit addition or subtraction of a second number to or from the stored number. The accumulators



Rear view of two of the accumulator racks of the Eniac. In the upper portion, each vertical row of 28 tubes is mounted on a separate plug-in chassis that can be removed quickly and replaced with a spare unit in case of trouble. In the lower group, banks of 12 tubes are removable. The entire machine is constructed in this manner, and trouble can be isolated to the defective chassis simply by running a selected test problem through and comparing the result with a correct solution kept on file for this purpose

RESISTANCE WIRE

ALLOY "A": Nickel-chromium alloy, resists oxidation at extreme temperatures. Essential for operating temperatures up to 2100° F. Also used for cold resistance. Resists chemical corrosion by many media. Non-magnetic; specific resistance, 650 ohms/C.M.F.

C. O. JELLIFF MFG. CORP.
123 PEQUOT AVE. • SOUTHPORT, CONN.

RESISTANCE WIRE

ALLOY "C": Nominally contains 60% nickel, 15% chromium, and balance iron. High resistance to oxidation and corrosion. Widely used in resistances for radio and electronics, industrial, and domestic equipment. Operating temperature up to 1700° F. Specific resistance 675 ohms/C.M.F.

C. O. JELLIFF MFG. CORP.
123 PEQUOT AVE. • SOUTHPORT, CONN.

RESISTANCE WIRE

ALLOY "180": Nickel-copper alloy with resistivity of 180 ohms/C. M. F. Widely used for resistor elements up to 750° F. (400° C.). For radio controls, magnets, rheostats and voltage control relays.

C. O. JELLIFF MFG. CORP.
123 PEQUOT AVE. • SOUTHPORT, CONN.

RESISTANCE WIRE

ALLOY "45": Alloy of 55% copper, 45% nickel with a constant electrical resistance over wide range of temperatures. Specific resistance 294 ohms/C.M.F.; temperature coefficient 0.00002 ohms per degree F; 32 to 212 degrees range. Used in winding of precision resistors.

C. O. JELLIFF MFG. CORP.
123 PEQUOT AVE. • SOUTHPORT, CONN.

RESISTANCE WIRE

KANTHAL: Exclusive manufacturers of KANTHAL, an outstanding achievement in resistance - wire development. Now available—complete data upon request.

C. O. JELLIFF MFG. CORP.
123 PEQUOT AVE. • SOUTHPORT, CONN.

Note: All alloys are produced in high-frequency type furnaces, and are furnished bright, dull or oxidized finish, also with enamel, silk, or cotton insulation.

New reference guide for Capacitors

TO assist you in properly meeting your capacitor requirements, Magnavox has prepared this handy reference guide. Specifications, accessory and technical data for the full line of Magnavox Electrolytic Capacitors are given in complete detail.

Magnavox Capacitors, produced expressly for the manufacturing trade, are built to meet severest operating conditions. Containers are standardized into eight sizes to simplify your design and assembly problems.

Economy in size and cost, long life, and efficient and trouble free operation are features Magnavox Electrolytic Capacitors can promise—and deliver. Mechanically, electrically and chemically they reflect years of research and experience. They have earned and won the confidence of the leading engineers.

Write today for this handy reference guide—and when you need the best in electrolytic capacitors—specify Magnavox. There is no substitute for experience! The Magnavox Company, Components Division, Fort Wayne 4, Indiana.

Magnavox
RADIO PHONOGRAPH

MAGNAVOX HAS SERVED THE RADIO INDUSTRY FOR OVER 35 YEARS

WORKS LIKE A SCREW DRIVER

Speeds Production!

Standard
Sizes, Hex,
Square or Knurled,
Chuck Type with many
Tools for many uses
Radio and Electrical Shops
Need them



SPINTITE
T-8 SET With Stand
7 Popular Sizes
Plastic Handles

Send for Catalog No 141 picturing a full line of Automobile, Aircraft and Radio Tools.

WALDEN WORCESTER WRENCHES

STEVENS WALDEN, INC.
468 SHREWSBURY STREET
WORCESTER, MASSACHUSETTS

are capable of performing these operations on numbers having as many as ten decimal digits, and indicate the associated plus or minus sign. The multiplier can find the product of two decimal numbers, each having as many as ten digits. The combination divider and square rooter can find the quotient of two nine-digit decimal numbers or the square root of a nine-digit decimal number.

Memory Elements

Memory elements of the machine include internal memory devices, of limited capacity, and external memory devices in the form of punched cards having unlimited capacity. Communication between the internal and external memory takes place at speeds which are set by the mechanical punch card devices.

Internal memory can be further subdivided in three ways. First, there are accumulators for numerical data calculated in the course of the computation and which must be available for other portions of the

Three of the power supply panels of the Eniac. Xenon-filled 4B24, 4B25 and C6J gaseous rectifier tubes, operating with red-hot plates, provide the 88 d-c voltages required by the robot calculator

computation. Second, empirical data known before the machine is started can be remembered by setting switches on the function tables. Third, there is a memory for instructions. This causes transfer between the various memory and arithmetic units and causes the arithmetic units to perform desired operations on the numbers. Setting of program switches permits program input signals to be received in one or more units, thus causing the unit or units

DRIVE AHEAD WITH

Smooth Power



• **You'll travel the roads to future markets faster and easier when you standardize on General Industries *Smooth Power* motors. Quick starting, uniform speed and quiet performance have for years made these motors leaders for phonographs, recorders and record-changers. From the GI complete line, select the proper motor for your new design. *For smooth performance, standardize on Smooth Power.***

The General Industries Company
DEPT. M · ELYRIA, OHIO







The COX Type 2 AMPLIFIER

... A MULTI-PURPOSE PRECISION INSTRUMENT FOR DEPENDABLE AMPLIFICATION AND MEASUREMENT IN THE FIELD OR LABORATORY

SPECIFICATIONS

Number of Stages	3
Overall Gain	80,000
Gain (2nd Stage Input)	1850
Frequency Response (5%)	1-15000 cps
Input Range (1st Stage)	.1-250 mv
Input Range (2nd Stage)	5-1000 mv
Input Impedance	
1-A (1st Stage)	.5 meg
1-B (1st Stage)	100 meg
2 (2nd Stage)	.5 meg
Output Impedance	50,000 ohms
Output Voltage (RMS)	70
Calibration Voltage	0-1000 mv
Harmonic Distortion (At .5 mv Input)	Max 3%
Power Supply (Regulated) 105-130 Volts	50-60 cps
Marker Input	4.5 Volts
Weight	30 lbs

APPLICATIONS

- DYNAMIC PRESSURES
- TORSIONAL VIBRATIONS
- LINEAR VIBRATIONS
- SOUND MEASUREMENTS
- MILLIVOLT MEASUREMENTS
- ALL PURPOSE VOLTAGE AMPLIFIER

BALANCED ELECTRONIC INSTRUMENTS NOW AVAILABLE FOR MEASURING:

PRESSURES — Pressure-Time or Rate-of-Change-of-Pressure Diagrams

TORSIONAL OR LINEAR VIBRATIONS — Displacement; Acceleration; Velocity; Frequency

ELECTRONICS DIVISION

COMMERCIAL RESEARCH LABORATORIES, INC.

Master Instrument Craftsmen Since 1912

20 BARTLETT AVENUE **DETROIT 3, MICH.**

IN·RES·CO RESISTORS
For super-performance in critical circuits...
Supplying low-cost wire wound resistors to meet critical circuit requirements is our business. Manufacturers of television, radar, radio or other equipment who require fast delivery on resistors of proven superiority are invited to investigate the low cost and diversified types available from IN-RES-CO. A completely illustrated catalog is available on request. Detailed and informative, it includes inductive, non-inductive types for every application need.
Type BLN: 4 watt, moisture proof, non-inductive resistor. Max. res., 20,000 ohms, dia. 7/16", length 1½" long.
INSTRUMENT RESISTORS CO.
IN·RES·CO
INSTRUMENT RESISTORS CO.
25 AMITY STREET, LITTLE FALLS, NEW JERSEY

to function within themselves and, on the completion of this internal functioning, to emit program output signals to cause other units to function. The master programmer coordinates this kind of memory function for the entire machine.

Control Elements

The control elements include the initiating unit, concerned mainly with starting and stopping the Eniac, and the cycling unit which generates the fundamental signals. The cycling unit contains an oscillator which generates electrical pulses at the rate of 100,000 per second and can do one basic operation every 20th pulse or a total of 5,000 additions, subtractions, multiplications or divisions per second.

When all controls have been set and cards have been punched for the external memory section, the cards are dropped into the IBM reader section and a starting button is pressed. If the machine is operated at full speed, the numbered neon lights on the panels blink 5,000 times per second and the entire panel appears to give one quick glow before the lights settle down at the final answer. Generally, however, the machine must be slowed down to the rate at which answer cards can be punched mechanically. The punched cards are then run through an IBM machine that prints the answers automatically on a sheet of paper.

Though a calculator can carry out numerous logical operations, it cannot do creative thinking. The mathematician, physicist or engineer is still needed—in fact, more than ever, to analyze the problem mathematically and set up the sequence of operations in the machine. It is expected, however, that machines of this type will bring a greater mathematics consciousness to engineering and production.

Army Seeks Technicians

TO CIVILIANS skilled in the maintenance and repair of radio, radar, telephone, and electric power equipment, and willing to replace enlisted technicians now stationed in the Philippines, Japan, and Korea, the Signal Corps is offering attractive jobs. The appointments, for a minimum of one year with transportation furnished both ways, carry salaries

Here's How It Works . . . . .



Sorensen A. C. Voltage Regulator

The impedance of saturable core reactor T2 determines what part of the input voltage is impressed across auto-transformer T1.

Impedance of the reactor is varied in accordance with changes in output voltage so as to restore output voltage to within 0.2% of its previous value.

The "heart", T3 and diode V1, control reactor impedance by varying the plate current of V2 thru the saturating winding.

The above extreme accuracy of voltage control is possible because of the almost infinite gain realized from the compensating action obtained from T3 and V1.

General Characteristics of Sorensen Regulators

Constant output voltage to with 0.2% with input variations 95 to 130 volts.
Voltage not affected by variations in LOAD, FREQUENCY or lagging POWER FACTOR.

No hash or interference generated—gas tubes not employed.
Low wave form distortion—average less than 5% (Special models available with less than 2% distortion guaranteed).

Write us about your A. C. Voltage or Current regulation problems. Ask for bulletin giving full schematic and other info. about various models, capacity 25 to 15,000 V. A.

SORENSEN & COMPANY, INC.

AIRBORNE ELECTRONICS — STAMFORD, CONN.

Tracing cloth that defies time



● The renown of Imperial as the finest in Tracing Cloth goes back well over half a century. Draftsmen all over the world prefer it for the uniformity of its high transparency and ink-taking surface and the superb quality of its cloth foundation.

Imperial takes erasures readily, without damage. It gives sharp contrasting prints of even the finest lines. Drawings made on Imperial over fifty years ago are still as good as ever, neither brittle nor opaque.

If you like a duller surface, for clear, hard pencil lines, try Imperial Pencil Tracing Cloth. It is good for ink as well.

IMPERIAL TRACING CLOTH

SOLD BY LEADING STATIONERY AND DRAWING MATERIAL DEALERS EVERYWHERE

ranging from $1.50 to $1.70 per hour for a 40-hour week, with provisions for overtime and night work differential. Quarters and subsistence will be provided by the Army at a cost not to exceed $40 a month. Benefits include annual and sick leave, necessary medical care, hospitalization, and compensation for service-connected injuries. Those interested should apply to their nearest USES office, or to the Office of the Chief Signal Officer, Pentagon, Washington 25, D. C.

German Technical Data

WEEKLY BIBLIOGRAPHIES of both technical and nontechnical reports on scientific and industrial information, mostly obtained in Germany and German-occupied countries, are being made available at the Government Printing Office for a nominal price. The lists also will contain titles of reports on U. S. Government-sponsored research (ORSD, Army and Navy), although only a comparatively few have been released to date.

The reports listed in the weekly bibliographies are grouped according to subject matter, serial number, price and length, with a brief description of report content. Materials, manufacturing processes, products, developmental work, and other scientific and technical matters are discussed in the reports.

Approximately 2,000 reports have been listed previously by the Office of the Publication Board, Department of Commerce. This same listing will be duplicated by the Government Printing Office in its weekly bibliographies until such time as the listing reaches the same point as OPB's lists. Then OPB will devote its full time to checking the various reports, having them photostated or microfilmed and sent to various government repositories in Washington. Complete reports should be ordered from OPB.

The Superintendent of Documents will accept $10.00 as approximate payment for a yearly subscription to the weekly bibliographies and will notify subscribers if additional remittance is required. Single copies may be purchased at varying prices. The first bibliography is priced at 15¢. Orders for these weekly lists should be accompanied by check,

Attention GI JOE!

Here's Your Opportunity to be First to

Start Your Own RADIO SERVICE SHOP

Complete Starting-in-Business Package Stocks of

TEST EQUIPMENT TUBES, PARTS, TOOLS $350 up

Act quickly! Meet the pent up demand for radio service. Turn your special service training into a profitable business of your own. No fuss. No worry. Here's everything you need—$350 up. Details upon request! Write, wire or phone

RCP 448

"POCKET" VOM
A.C.-D.C. Volts
0-5-50-250-1000
D.C. Mills
0-.5-10-100-1000
Ohms
0-2,000-20,000-200,000-2 Meg.
Size 3"x5⅛"x2¼"

$24.50 net



RECORD CHANGERS

UTAH-DETROLA #550C	$18.27
WEBSTER-CHICAGO #56	27.20

HALLICRAFTERS SX-28A $223



SUPER DEFIANT	SX25	$94.50
SKY CHAMPION	S20R	60.00
SKYRIDER MARINE	S22R	74.50
S40 NEW MODEL	Approximately	79.50
SKYRIDER JR. S41		33.50

HAMMARLUND HQ-129-X $129

TRIPLETT 625-N

20000 ohms per volt D.C.
10000 ohms per volt A.C.
5" Scale-TOPMOST QUALITY
(12) D.C. Volt Ranges to 5000
(6) A.C. Volt Ranges to 5000
(3) OHM Ranges 0-400-50000-10 Meg.
(5) D.C. Current Ranges 1 Ma. to 10 Amp.
PLUS OUTPUT and DB. RANGES

$45.00 with test leads.

PHILCO BEAM OF LIGHT
Selenium Cell only, no holder 1.80

20% deposit required on all C.O.D. orders. 2% transportation allowance on orders of $25.00 or more accompanied by payment in full.

RADIO SUPPLY & ENGINEERING CO., Inc.
127 SELDEN AVE DETROIT 1 MICH

Write for FREE CATALOG

CML

New DEVELOPMENTS BY THE DESIGNERS OF FAMOUS ROTOBRIDGE . . .



1 CML 1800: A-F FREQUENCY METER AND TACHOMETER

Measures frequency of a-c voltages 10 cycles to 20,000 cycles in 6 ranges independent of wave form. With "photo-beam converter" Model 1800 serves as an accurate electronic tachometer for measuring speeds of rotating or reciprocal mechanisms. Accuracy better than 1% at full scale. Scores of applications for laboratory and production control operations. Rugged Navy-type construction assures continuous, trouble-free operation.



2 CML 1210: PORTABLE STROBOSCOPE

Employs novel circuit, using self-blocking oscillator. Rotary or vibratory motion can be "stopped" when moving object is examined with stroboscopic light source. Valuable for slow-motion study, observation of stresses and strains under dynamic conditions. Light probe and 4-foot cable housed in handle of cabinet. Extremely compact; weighs only 19½ lbs. complete.

3 CML 1115: DUAL POWER SUPPLY

Provides independent "B" and "C" voltages. "B" supply furnishes continuously variable voltage from 150 to 300 v. d-c at 70 ma with 4 mv ripple. "C" supply furnishes continuously variable voltage from 0 to 65 v. d-c with 1 mv ripple. Panel controls provide for adjustment output through indicated range. Independent insulated panel connectors supplied for high-voltage units.

DESCRIPTIVE BULLETINS AVAILABLE — WRITE TODAY

COMMUNICATIONS MEASUREMENTS LABORATORY

120 GREENWICH STREET · NEW YORK 6

CML

CARDWELL

ANNOUNCES A NEW ADVANCED

HIGH FIDELITY

AUDIO AMPLIFIER



MODEL CE-25

- 25 watts undistorted output.
- Three High Impedance Inputs—Two for microphone and one for phonograph.
- Individual bass and treble boosting controls.
- Dynamic audio compensation circuit on phonograph channel.
- Ultra-modern cabinet styling with recessed control panel edge lighted.
- All aluminum construction combines durability with light weight.
- New vane type construction assures good ventilation and low operating temperature.
- Concealed hand holds for easy portability.

SPECIFICATIONS

POWER OUTPUT: 25 watts undistorted.

GAIN: Microphone 135 db. Phonograph 85 db.

FREQUENCY RESPONSE: Response at 50 cycles controllable from −15 to+17 db. Response at 10,000 cycles controllable from −15 to +22 db. In addition, Audio Compensation is used on the phonographic input which boosts bass as the volume level is reduced. This compensation is effective over a 40 db range in volume level and results in exceptional tone balance.

POWER REQUIRED: 115 watts at 105-125 volts 60 cycles AC.

DIMENSIONS: Length 15½ in., Depth 10¼ in., Height 8⅝ in.

CONTROLS: Two microphone volume controls and one phonograph volume control. One bass boost and one treble boost control.

TUBES: (2)—6SJ7, (3)—6SL7GT, (2)—6L6G, (1)—5U4G.

OUTPUT IMPEDANCES: 2, 4, 8, 16, 250, and 500 ohms.

INPUT IMPEDANCES: Microphone channels—10 megohms. Phonograph channel—500,000 ohms.

WEIGHT: 26 lbs. All aluminum case.

WATCH FOR THE
NEW CARDWELL COMMUNICATIONS
RECEIVER TO BE ANNOUNCED SOON

Introducing new and unusual
mechanical and electrical features

THE ALLEN D. CARDWELL
MANUFACTURING CORP.

MAIN OFFICE: 81 PROSPECT ST., BROOKLYN 1, N. Y.

FACTORIES: PLAINVILLE, CONN.—BROOKLYN, N. Y.

money order or Superintendent of Documents coupons and should be addressed to Superintendent of Documents, Government Printing Office, Washington 25, D. C.

Among the mimeographed reports on electronic subjects that can now be ordered from Office of the Publication Board, Department of Commerce, Washington, D. C., are the following:

No. 386—Electronic test instruments; spark and flash discharge photographic equipment, Phillips, Eindhoven—12 pages, $.50.

No. 421—Manufacture of metallized paper fixed capacitor units by the Robert Bosch Co. (description of manufacturing process and metal vaporizing machine)—9 pages, $.10.

No. 1027—German magnetic tape recorder, Tonschreiber models b and b1—24 pages, $.50.

No. 1292—Specialized ceramic products—their use in German communication equipment—37 pages, $.50.

No. 1571—Enemy tube data (German, Japanese, and Italian)—11 pages, $.50.

No. 1585—Technical report on UKW PE e 1 direction-finding receiver used for radiosonde—6 pages, $.50.

No. 1586—German vibration detector—7 pages, $.50.

No. 1587—Technical report on German infrared (night driving equipment, rifle sighting mechanism, and aircraft experimental model)—20 pages, $.50.

No. 1588—Technical report on uhf direction-finding receiver FUMB4—11 pages, $.50.

No. 1589—Technical report on Strassburg-Kehl radio-controlling system for bombs and rockets—23 pages, $.50.

No. 1591—Technical report on decimeter radio equipment for controlling bombs and rockets—12 pages, $.50.

No. 1597—Report on Drahtfunk system (wired wireless)—24 pages, $.50.

CAA Promises Gradual Change to VHF Facilities

THE CHANGE FROM low frequency to very high frequency radio for aircraft communications and signals will be gradual, all existing equipment will continue in use and retain its value, and there will be an interim period in which both vhf and low-frequency equipment will be in use, according to T. P. Wright, Administrator of Civil Aeronautics. Eventually, after a matter of several years, all communications along the airways and all signals for radio navigation will be in the vhf bands, which will be better in all respects than that in use today. In particular, they will be beyond the static belt.

Today, the private flier transmits to CAA ground stations on 3,105 kc and listens to traffic control towers on 278 kc. This equipment represents thousands of dollars investment, and will not be disturbed. The CAA will continue to operate these services on these frequencies. In addition, the existing low-frequency ranges will be available for use by the private flier, since his receiver covers the 200-400 kc band.

Anticipating the crowding of radio

BRADLEY

COPPER OXIDE RECTIFIERS

Coprox Model CX-9C2B.

A plastic-sealed rectifier for high frequency applications, conservatively rated 4½ volts A.C., 3 volts D.C., 1 milliampere D.C.

All Bradley rectifiers have special features that give long life, make easy assembly, and assure accurate performance. Bradley's application experience can be called upon for the development and production of special rectifiers for special jobs.

Illustrated literature, available on request, shows more models of copper oxide rectifiers, plus a line of selenium rectifiers and photocells. Write for "The Bradley Line."

BRADLEY LABORATORIES, INC.

82 Meadow St. New Haven 10, Conn.

channels by the 400,000 to 500,000 airplanes predicted within the next 10 years, the CAA has made plans for eventual and complete change to vhf equipment. Already, transmitters are installed on the ground which can be used by planes fitted with vhf equipment. This equipment gives better results, and also relieves the 3,105-kc band which, in congested areas, is already crowded.

Radio manufacturers plan to build a five-channel transmitter covering the 131-mc band. Originally, only two frequencies will be covered in this transmitter, 131.9 kc for communication from plane to traffic tower, and 131.7 kc from plane to airways station. Later, as these channels become crowded, three other channels can be made operative by the simple addition to the transmitter of one crystal for each one.

On the ground, vhf transmitters for talking to planes will be in the 118-mc band. Transmitters already are installed at CAA towers, and are being used to communicate with planes in congested areas in order to relieve the low-frequency tower channels. At CAA airway stations, there will be transmitters on 111.1 mc.

An important advantage in the use of vhf is that 90 channels are available for aviation compared to 60 at low frequency, and these channels can be repeated more often within continental United States without interference. As far as the average pilot is concerned, however, vhf will be most welcomed for its freedom from static, a fault of the low-frequency transmission that makes it uncomfortable, uncertain, and sometimes dangerous.

New Range Beacons

The whole airway range system of the country is to be converted to vhf. The two-course aural and visual vhf range has been developed to the point where it is now installed on certain airways in the country, and plans have been completed for putting it in on all airways.

Engineers found that conversion of the aural-visual range to the omni-directional range employed the same equipment and was relatively inexpensive to do. Thus, in the middle of the vhf program, the plan has been modified to include omni-directional ranges. This type of range simplifies flying for the private flier, either on or off the airways, and still

READY NOW

A NEW LINE OF

CARDWELL

MIDGET CONDENSERS

for

U. H. F.



PL-6113
(Type ER-14-BF/SL)
Range: 14-11 mmf. (approx.)
(Minimum capacity loaded by circular rotor plates—for a High "C" circuit.)



PL-6076
(Type ER-6-BF/S)
Range: 6-2. 5 mmf (approx.)

The "Butterfly" rotor plates with 90 degree stators insure:

ELECTRICAL SYMMETRY
LOW DISTRIBUTED INDUCTANCE

Features

- Circular plates for low loss fixed minimum permits adjustable band spread.
- No moving contacts.
- Plates easily removed to change capacity range.
- Isolantite Insulation.
- Single Hole Mounting.
- Small size—made to fit standard Cardwell Trim-air hardware.

Other sizes available. Inquiries will be promptly answered.

THE ALLEN D. CARDWELL MFG. CORP.

Main Office: 81 Prospect Street, Brooklyn 1, N. Y.

Factories: Plainville, Conn.—Brooklyn, N. Y.

PRECISION CRYSTALS

SINCE 1934

TYPE Z-1

THE NEW STANDARD CRYSTAL UNIT FOR ALL HIGH FREQUENCY SERVICE

FREQUENCY 1.5 TO 10.5 MC.

TEMPERATURE COEFFICIENT LESS THAN 2 CYCLES PER MC. PER DEGREE CENTIGRADE

CALIBRATION ACCURATE TO WITHIN .005% OF SPECIFIED FREQUENCY

MADE BY

PETERSEN RADIO COMPANY
COUNCIL BLUFFS, IOWA



Instant Power for Your **MOBILE TRANSMITTER**

Send today for latest free catalog of CARTER Rotary Products.

Only CARTER gives you instant power when you press your transmitter microphone switch. 600 volt plate power in less than 350 milliseconds!! Actual laboratory tests prove this unequalled starting performance, so important for instant communications. Remember, only the CARTER ORIGINAL GENEMOTOR gives you truly instant power.

1606 MILWAUKEE Avenue

Carter Motor Co.

Cable Genemotor

Now available—
Your guide to precise usage in working with ELECTRONICS terms

6500
CLEAR-CUT DEFINITIONS AND REFERENCE DATA



HERE is the book that every electronics and radio man has been looking for—an up-to-date, comprehensive dictionary covering all the terms used in electronics and its extensive practical applications, radio, television, communications, and industrial electronics.

For clear, precise definitions, accurate usage, well-illustrated descriptions, and for standardized spelling, abbreviating, and hyphenating policy, this book will be a constant aid to everyone working with electronics and radio engineering—whether student or engineer, editor, or engineering secretary.

Just Published!

ELECTRONICS DICTIONARY

By NELSON M. COOKE, *Lt. Com. U.S.N.*
Executive Officer, Radio Materiel School
Naval Research Laboratory, Washington, D. C.

and JOHN MARKUS
Associate Editor, *Electronics*

433 pages, 5¾ x 8¼
over 600 illustrations, $5.00

NOW at last here is an authoritative work to clarify and define the myriad new terms that have come into usage with the vast growth of electronics and electrical engineering. Nowhere else will you find a dictionary comparable to this in scope and timeliness. Nowhere else will you find such a thorough, extensive, generously illustrated compilation.

This glossary fully covers terminology, principles, processes, equipment, abbreviations, and colloquialisms in

Radio
Television
Facsimile
Sound recording
Communications
Medical electronics
Electronic heating
Electronic welding
Photoelectric controls, safety devices, and intrusion detectors
Industrial electronics
Electronic motor control
Long-distance telegraph and telephone

This excellent dictionary should be of constant usefulness both to the technician and to the most advanced electronics engineer, for its definitions are exceptionally precise and accurate, and in most cases, each is complete in itself. Invaluable for its consistent abbreviating and hyphenating policy.

Send for a free-examination copy

McGraw-Hill Book Co.,
330 W. 42 St., N. Y. 18

Send me Cooke and Markus' ELECTRONICS DICTIONARY for 10 days' examination, on approval. In 10 days I will send $5.00, plus few cents postage, or return book postpaid. (Postage paid on cash orders.)

Name .....
Address .....
City and State .....
Company .....
Position .....L. 4-46

In Canada: Mail to Embassy Book Co.
12 Richmond St E, Toronto 1

gives the airline pilot the kind of guidance he needs. In addition, a grid of ranges similar to the transoceanic type eventually will be spotted throughout the country for transcontinental great circle flights at high altitudes. Airliners on such flights will be able to fly the shortest routes without regard to the present irregular airway courses between cities, for they always will be within the sound of these high-powered direction-finding facilities.

Blind Landing Systems

Instrument landing equipment is being installed by the CAA at nearly 100 airports throughout the country. This is the three-element system developed by the CAA, consisting of the localizer, glide path and marker beacon. Although the Army and Navy did remarkable things with radar in instrument landing during the war, the pilots of the airlines, the technical men of the airlines and CAA radio engineers all agree that considerable development work will be required before radar is safely applicable to commercial use.

Of the three elements of the CAA landing system, the marker beacon is considered fully developed. The localizer, heretofore operated on a basis of amplitude comparison, with 90 cycles transmitted on one side and 150 cycles on the other of the line to define the course along the runway, has been improved by using phase comparison instead of amplitude comparison. Now the course is defined by comparing the phase of two 60-cycle signals. This change has resulted in a considerable simplification of the equipment required in the transmitter on the ground, and

COAXIAL CABLE PROGRAM



Status of AT&T coast-to-coast coaxial network. Some sections will be radio relay within the next few years. About 700 miles of coaxial toll cables were placed in 1945, and some 2,100 miles is scheduled for 1946. The recently completed New York-Washington link has already been used successfully for television programs

Complete Facilities-

- Engineering-Design & Development
- Laboratory & Model Shop
- Tool & Die Making
- Coil Winding
- Impregnating
- Blanking & Annealing of Core Steel
- Fabrication of all Mounting Parts
- Complete Assembly
- Compound Filling
- Inspection & Testing



devoted to One Primary Purpose

—the manufacture of transformers to fit the specialized requirements of the Electronic Industry

CHICAGO TRANSFORMER

DIVISION OF ESSEX WIRE CORPORATION

3501 ADDISON STREET · CHICAGO, 18

A Name to Look for on Electrical COILS and Transformers

GRACOIL

"One Good Turn - or a Million"

Famous for years as COILS by DOYLE

LAYER-WOUND COIL



LOW VOLTAGE TRANSFORMER

RELAY COIL

GENERATOR FIELD COIL

Be sure that the coil you buy bears the trademark name — "GRACOIL", for only then can you know that you have the best in electro-magnetic windings. Every "GRACOIL" is wound to the specified number of uniform turns from precision-gauged wire. Every "GRACOIL" is fully insulated, thoroughly impregnated, and properly laminated when supplied as a complete transformer. The most rigid inspections and tests make sure that each "GRACOIL" is worthy of the name it bears.

If your design calls for a special electro-magnetic application, let competent "GRACOIL" engineers make specific recommendations for you. Write today!

THE GRAMER COMPANY

Electrical Coils and Transformers

2736 N. PULASKI RD., CHICAGO 39, ILL., U. S. A.

ZOPHAR

Waxes, Compounds and Emulsions

ZOPHAR MILLS — QUALITY AND SERVICE — 100 YEARS — EXPERIENCE

Materials for potting, dipping or impregnating all types of radio components or all kinds of electrical units. • Tropicalized fungus proofing waxes. • Waterproofing finishes for wire jackets. • Rubber finishes. • Inquiries and problems invited by our engineering and development laboratories.

Zophar Mills, Inc. has been known for its dependable service and uniformity of product since 1846.

ZOPHAR MILLS, Inc.

ESTABLISHED 1846

117 26th STREET, BROOKLYN, 32 N. Y.

PREMAX

For Commercial Installations



It's Premax

Premax Tubular Steel and Aluminum Vertical Antennas and Mountings are in widespread use on Fire, Police, Public Utility and other emergency vehicles. They give universal satisfaction because they get the signals and can withstand the severe road shocks. Undoubtedly there is a standard Premax design that will fill your needs. Write for Bulletin.

Premax Products

Division Chisholm-Ryder Co., Inc.

4611 Highland Ave., Niagara Falls, N. Y.



..for exacting needs!

Facilities for rapid production of all screw machine parts. Close tolerance work a specialty. Expanded modern facilities permit fast delivery. All tools, jigs, fixtures produced on premises for precision and economy.

INQUIRIES INVITED

THE ENGINEERING CO.

DANIEL KONDAKJIAN

27 WRIGHT ST., NEWARK, N. J.

a lightening and simplification of the airborne receiver. A straight-line glide path has been developed as an additional improvement of the landing system.

The CAA is cooperating with the Army in service testing of its automatic instrument landing system. In this, the indications of the cross-pointer instrument by which the system is flown are connected to a standard automatic pilot, and the airplane is flown to the point of contact with the ground without human hands on the controls.

Telediffusion in Sweden

By LEONARD SILK

McGraw-Hill World News
Stockholm, Sweden

A FIGHT is in progress here between supporters of telediffusion or wired wireless and technical experts favoring frequency modulation as the solution of Sweden's broadcasting difficulties. Telediffusion is being considered not because mountains make reception in valleys poor, but because of the great distances to the relatively few wireless transmitters which it has been possible to install in Sweden owing to the lack of wavelengths, and perhaps even more important, because of the severe electrical interferences in many areas here.

People living along the railroad tracks in Sweden find it impossible to use their radios at certain hours during the day, since the Swedish railroads are largely electrically-powered. Besides disturbances from high-tension power lines and contact wires for the railways, there are those from electric plants in factories, hospitals, and office buildings. Those listeners are worse off who are resident in certain districts of Värmland, Dalsland, Bohuslän, Smaland and certain communities along the railways. In almost every case, these are not mountainous areas. In the North, however, some interference is experienced from ionospheric disturbances.

According to an over-all estimate made by the Radio Bureau of the Telegraph Administration, even if existing broadcasting stations had been expanded to the fullest possible extent, about 600,000 subscribers to the broadcasting network could not get satisfactory reception. This figure is fantastically large, since the

Announcing 2 NEW
CONCORD
RADIO CATALOGS

Ready Soon! The presses are roaring now, pouring out the thrill-packed pages of the first great, post-war COMPLETE CONCORD Catalog—featuring

RADIO SETS
AMPLIFIERS
RADIO PARTS
Electronic Equipment

Soon it will be in your hands, presenting the *complete line of brand new postwar-designed CONCORD Radio Receiving Sets and Amplifiers*—incorporating a host of new improvements, new developments, modern cabinets, and superb quality throughout—plus page after page of nationally-known standard, top-quality radio and electronic equipment, supplies and amateur equipment. Mail the coupon below NOW—to be sure your FREE copy will be mailed to you as soon as off the press.

Ready Now! **New CONCORD Bargain Book of**
RADIO PARTS
SUPPLIES • EQUIPMENT

Just off the press! The newest, latest Concord Bargain Book listing hundreds and hundreds of money-saving bargains on hard-to-get, standard-make radio parts and electronic equipment. Select your needs from the remarkable values offered in Condensers, Resistors, Meters, Transformers, Volume Controls, Relays, Switches, Generators, Microphones, Speakers, Tools, and hundreds of other items. Mail the coupon for your copy now.

CONCORD
RADIO CORPORATION
LAFAYETTE RADIO CORP.
CHICAGO 7 ★ ATLANTA 3
901 JACKSON BLVD 265 PEACHTREE ST

Concord Radio Corporation Dept. G-46
901 W. Jackson Blvd.
Chicago 7, Illinois
Please mail immediately FREE copy of the New Radio Parts Bargain Supplement—and place my name on the list to be one of the first to receive the new CONCORD COMPLETE CATALOG.

Name.....
Address.....
City.....*State*.....

The Most Indispensable Reference in Radio-Electronics

Electronic Engineering Master Index



Cloth
7½" x 10½"
320 pages

A master compilation of over 15,000 titles, articles and texts selected for their value to the research engineer, this INDEX covers the years 1925-1945 and enables you to survey twenty years of research literature on any subject in a matter of minutes!

Vitally Needed in Every Laboratory and Library

COMPLETE IN ONE VOLUME

PART I	PART II
January 1925 to December 1934	January 1935 to June 1945

★

PARTIAL LIST OF PERIODICALS INDEXED:

Bell Laboratories Record
Bell System Technical Journal
Communications
Electrical Communication
Electrical Engineering
Engineering
Electronics
Electronic Industries
Jour. of Applied Physics
Journal of I.E.E.
General Electric Review
Physical Review
Proceedings I.R.E.
Transactions of A.I.E.E.
Transactions of A.S.M.E.
Radio News
R.C.A. Review
Wireless Engineer

A $500 Reference Library in One Volume for $17.50

Descriptive circular on request.

ELECTRONICS RESEARCH PUBLISHING COMPANY

2 West 46th Street **New York 19, N. Y.**

CUSTOM MOLDED

PLASTICS PARTS

FOR THE ELECTRONICS INDUSTRY



Compression Molded **..to meet specific requirements... by an experienced organization ...tooled for the production of plastics parts for electrical or general applications. Inquiries acknowledged promptly.**

Midwest Molding and Manufacturing Co.

335 NORTH WHIPPLE ST. • CHICAGO 12, ILL.

APPROVED

Leakproof

ENAMELED MAGNET WIRE

● Much of the success of this Hudson Wire product is due to a new coating method that gives a smooth, permanently-adherent enameling. Mercury-process tests guarantee perfect uniformity; great tensile strength assures perfect laying even at high winding speeds. Especially adaptable for reduction in coil dimensions without sacrificing electrical values.

Our engineering and design facilities are at your disposal—details and quotations on request.

HUDSON WIRE COMPANY

Winsted Division

WINSTED CONNECTICUT

HOW TO BUILD

LAMP ANNUNCIATORS

Kirkland Bulls-I-Units are ideal for this purpose. Just provide the proper size holes in the panel, then insert the Kirkland units and lock into place. Many different units to choose from. Assembly is then ready for installation. Connect incoming wires and place in service. Typical unit illustrated above made with T2 units.

KIRKLAND Pioneer

INDICATING LAMPS

TYPE T2 UNIT

Small and modern, molded of bakelite. For use with slide-base switchboard bulb (24 volts, 0.038 Max. Amp) with resistor on 120-220-440 volts. Overall dia. Lens-Cap ¾".

LIST PRICE (less bulb) 70¢.

Write Today for Catalogue

Where Quality is the Foremost Consideration

The H. R. KIRKLAND CO., Morristown, N. J.

total number of radio licensees in Sweden is 1,840,000.

Another great complaint of Swedish listeners is lack of variety in their radio diet. At present only one program is broadcast simultaneously for all of Sweden. The Broadcasting Committee's ambition is to provide three programs simultaneously.

VHF F-M Broadcasting

In searching for solutions, the Committee discovered that no new wavelengths can be obtained for Sweden in the long-wave, medium-wave and short-wave bands. There are, however, possibilities in the vhf bands, in which f-m is being considered. It would be possible here with about 150 vhf transmitters at an establishment cost of about $6,800,000 to reach about 75 percent of the present number of license holders. This method permits transmission of two programs at once. Main objection to the solution through f-m is that present radio receiving sets cannot be used for reception of f-m. Capital invested in receiving sets has been estimated at an amount ranging between $60,000,000 and $270,000,000.

Carrier, Broadcast System

The second solution (which has the support of the Committee) is using high-frequency wired wireless by which radio programs would be distributed along available telephone lines. It would thus be possible to avoid difficulties that arise due to lack of wavelengths in radio transmission, and three or four programs could be transmitted on each line. Broadcasts would be piped from Stockholm to booster stations and thence to private houses (or, in small villages, to one house which would serve as feeder for others).

It is possible to transmit programs by carrier via electric power mains, but the plant then becomes technically complicated and expensive. Something similar was tried in Germany under Hitler but for a different reason—to keep internal propaganda truly internal, and perhaps to avoid broadcast transmissions going off the air in case of air raids.

The Committee considered use of telephone lines to be preferable, especially since transmission can take place without breach of telephone secrecy. Listeners will not have to buy new and expensive receiving sets. Also, special mass-produced wired

AUDIO SIGNAL SYNCHRONIZER—
MODEL J for
Synchronization of Audio Frequencies

This instrument is essentially a dual input, sensitive vacuum tube voltmeter. In production and laboratory test procedures, typical applications are: synchronizing audio oscillators with radio WWV, calibrating modulation frequencies of transmitters, adjusting filter networks and tuned circuits —or any application where a beat must be observed down to a few cycles per second.

The usual procedure with cathode ray techniques requires considerable time for interpretation of frequency differences. The Model J will synchronize and give direct indication of frequency differences as low as one beat in 24 hours. The gain of each input, for full scale deflection on the meter, exceeds 60 D. B.

Input impedance is 500,000 ohms over the audio spectrum and is constant at any setting of the input attenuators. The inputs are isolated from each other and have no electrical effect on the signal mix. A jack is provided so that the output synchronized signal may be used to drive an oscilloscope.

Dimensions—19" L x 8¾" H x 9½" D
Furnished in oak cabinet if relay rack mounting is not desired.

Write for descriptive literature

Televiso

PRODUCTS CO.
7466 IRVING PARK ROAD
CHICAGO 34, ILLINOIS



To utilize the possibilities of new circuits for finer instrumentation.

The VX Series of sub-miniature vacuum tubes.

Measured characteristics of the VX-41 Tetrodes.

Filament current	10 M.A.
Filament voltage	1.25V
Grid current	10^{-14} amp.
Grid resistance	10^{16} ohms
Plate current	250 microamps.

If these characteristics suggest a solution to a circuit or instrument problem, consult us. A technical bulletin showing circuit applications is yours for the asking.

Available as Pentodes, Triodes, Tetrodes, Diodes.

THE VICTOREEN INSTRUMENT CO.
3800 PERKINS AVENUE
CLEVELAND 14, OHIO

The Victoreen Hi-Meg vacuum Sealed Resistor offers a new standard of precision and stability for resistance values in a range of 100 to 10,000,000 megohms. Especially needed where low operating currents require extremely high resistances. The only resistor that covers this range of values with relatively low temperature and voltage coefficients.



Write for technical data on VX Tubes and Resistors.

wireless receiving sets would be a great deal cheaper both to buy and operate than present sets.

Sweden would continue to broadcast one of its three programs on the air and would pipe that program plus two others through the wires. Major criticisms to the scheme are that a nondemocratic government could do terrible things with such a tight internal system and that it would take so long to complete (20 years). Proponents reply that the scheme could be effected immediately to give those with phone lines a variety of programs, that it is essential to get going with some scheme, and that new phone lines which must be laid are important and useful in any case.

The Committee has made additional suggestions and given prices for other means of improving Swedish broadcasting. For extension of the wireless station grid: $5,000,000. For installation of two short-wave transmitters (to beam programs to Swedes abroad): $2,400,000. For building of a Broadcasting House (huge studios) in Stockholm, on which construction will probably start this summer: $12,500,000. For wired wireless to listeners unable to get fully satisfactory reception: $42,000,000. For wired wireless to all listeners in order to provide several simultaneous programs: $94,000,000.

Lanac for Aviation

A NEW WARBORN SYSTEM for protection and navigation of aircraft while in flight has been announced by Hazeltine Electronics Corporation. It is called Lanac, abbreviation for Laminar Air Navigation and Anti-Collision system.

The basic concept of the system, developed by Knox McIlwain of the Hazeltine organization, rests upon the fact that commercial and private aircraft while in flight are restricted to certain laminae or air strata and that it is essential for these planes to know what obstacles are present in their respective strata of operation. The system makes it possible: (1) to prevent collisions between planes in the air or between planes and mountains, high buildings, or other fixed obstacles; (2) to identify individual planes while in flight as to airline and flight number; (3) to furnish direction and other data directly to the pilot without the assis-

Thermador is a name remembered when the utmost in transformer quality is desired, and when exceptional engineering skill is required.

"Seven Leagues Ahead"

THERMADOR
THERMADOR ELECTRICAL MFG. CO.
5119 District Blvd., Los Angeles 22, California

TERMINAL BOARDS

FOR

Electronic Equipment

MADE TO ORDER
IN ANY QUANTITY

•

IMMEDIATE DELIVERY

•

Send for quotation

FIVE STAR RADIO CO.
416-18 Broadway • Cambridge, Mass.

VANATTA

kwikheat

THERMOSTATIC SOLDERING IRON

A Division of
Sound Equipment Corp. of Calif. • 3903 San Fernando Rd., Glendale 4, Calif.

America's Only Soldering Iron

WITH BUILT-IN THERMOSTAT

225 WATTS POWER in a Mere 14 ozs.

UL

HOT IN 90 SECONDS

Ready for use 90 seconds after plugging in! The Kwikheat Soldering Iron cannot overheat . . . adds to life of tips . . . requires less retinning time, because Kwikheat's built-in patented thermostat maintains proper, even heat for most efficient, economical operation. Powerful—225 watts—yet light weight (14 ozs.). Well balanced with cool, protecting handle. Six interchangeable tip designs adapt the Kwikheat Iron to most any soldering job. Iron with choice of any one tip, $11.00

6 Interchangeable tip styles are available.

6 TIP STYLES · QUICK HEATING ELEMENT · BUILT IN THERMOSTAT · WELL BALANCED · LIGHT WEIGHT · COOL, PROTECTING HANDLE

FOR
INDUSTRIAL USES

BURGESS BATTERIES

RECOGNIZED BY THEIR
STRIPES • REMEMBERED
BY THEIR SERVICE

Toroids.. by DX

Doughnut Coils for electronic and telephone purposes. High Permeability Cores are hydrogen annealed and heat treated by a special process developed by DX engineers. Send us your "specs" today—ample production facilities for immediate delivery.

DX RADIO PRODUCTS CO.

GENERAL OFFICES 1200 N. CLAREMONT AVE. CHICAGO 22, ILL. U.S.A.

DX COILS

"the heart of a good receiver"

NEW MODELS
Available Now!
of ATR
QUALITY PRODUCTS

ATR "A"
BATTERY ELIMINATORS
FOR CONVERTING A.C. TO D.C.
New Models . . . designed for testing D.C. electrical apparatus on regular A.C. lines. Equipped with full-wave dry disc type rectifier, assuring noiseless, interference-free operation and extreme long life and reliability.

- Eliminates Storage Batteries and Battery Chargers.
- Operates the Equipment at Maximum Efficiency at All Times.
- Fully Automatic and Fool-Proof.

ATR
LOW POWER INVERTERS
FOR INVERTING D.C. TO A.C.
Another New ATR Model . . . designed for operating small A.C. motors, electric razors, and a host of other small A.C. devices from D.C. voltages sources.

ATR



STANDARD AND HEAVY DUTY INVERTERS
FOR INVERTING D.C. TO A.C.
Specialy designed for operating A.C. radios, television sets, amplifiers, address systems, and radio test equipment from D.C. voltages in vehicles, ships, trains, planes, and in D.C. districts.

WRITE FOR NEW CATALOG—
JUST OFF THE PRESS!

AMERICAN TELEVISION & RADIO CO
Quality Products Since 1931
ST. PAUL 1, MINN. U.S.A.

tance of a ground crew; (4) to increase the traffic-handling capacity of airways and airports; (5) to increase the safety of transoceanic and other flights far distant from ground stations; (6) to give automatic navigational aid to pilots while flying so that the possibility of lost planes is reduced to a minimum; (7) to give airports and ground check stations continuous data on the location as well as the identity of all planes.

If the Lanac system is officially adopted, every airplane will be equipped with a challenger and a replier—radar sending and receiving sets controlled by barometric devices so as to be responsive only at the altitudes for which they are set. The challenger sends out a constant series of challenges which are automatically picked up by the repliers of other planes in the same air stratum. Upon receipt of such signals, the replier automatically transmits a reply so that the presence of another plane in the same stratum is instantly known and collision can be avoided. When ascending or descending, the pilot can temporarily change the barometric range of his challenger to investigate the air layers he is approaching. Through barometric selection, a plane in normal operation is advised only of obstacles in its own stratum of flight and is not confused by a multiplicity of signals from other strata.

Mountains, high buildings, and other fixed obstacles can be equipped with permanent repliers which will be responsive to challenges transmitted by any planes flying at a dangerous altitude.

Plane identification is obtained by varying the characteristics of the reply signals transmitted by the replier of each plane, so as to reproduce in Morse code the letter designation of each individual plane. This information can be picked up by other planes and by ground stations.

For navigational purposes the pilot of a Lanac-equipped plane will be able to challenge navigational beacons on the ground and receive their replies, each so coded as to be readily identifiable. By means of these navigational fixes the pilot can establish his exact position and determine his ground speed. The plan envisages the establishment of these navigational beacons at strategic points.

The Lanac system is already in an

ELECTRICAL PAPERS
MADE TO YOUR SPECIFICATIONS

Electrical papers are different! That is why it pays to consult with specialists in determining the most efficient paper for a particular purpose. Our research department, specialists in Electrical Paper applications, will be glad to analyze your requirements and recommend papers of correct properties.

FREE BOOK

Contains data on Electrical Paper properties and a wide variety of samples.

REG. U. S. PAT. OFF.
CENTRAL PAPER COMPANY
INCORPORATED
2442 LAKESHORE DRIVE, MUSKEGON, MICH
OFFICES IN:
BOSTON, NEW YORK, BALTIMORE, BUFFALO, CLEVELAND, CINCINNATI, DETROIT, CHICAGO, ST. LOUIS, SAN FRANCISCO

Radio-Electronic Materials

• Try us for those items you need in a hurry. Our stocks are big—our service, extra-fast!

We've been at it since 1925 —and we know how!

Just Try Us

L. I. DAVIS, INC.
Wholesale Distributors
RADIO-ELECTRONIC SUPPLIES & PARTS
17 Union Square
NEW YORK 3, N. Y.
Phones: ALgonquin 4-8112-3-4-5-6-7

NEED SMALL BULBS *and* DEEP DRAWN PARTS *to* CLOSE TOLERANCES?

GOAT PRECISE-FORMED DEEP-DRAWN METAL PARTS

Improved Quality at Lower Cost!

Deep drawing, sizing and coining, in conjunction with quality control techniques devised by the Goat Company, make possible the economical production of small parts to tolerances unattainable a few years ago. The new method makes expensive annealing operations unnecessary. The use of these economically produced, *precision* parts reduces both material costs and assembly costs.

Send us your design prints for engineering recommendations

LET US REDESIGN FOR STAMPING

GOAT METAL STAMPINGS, INC.
Affiliate of The Fred Goat Co., Inc.
314 DEAN STREET BROOKLYN, N. Y.

JONES BARRIER TERMINAL STRIPS

2-142



2-142-¾W

2-142-Y

Bakelite Barriers placed between Terminals increase the leakage path and prevent direct shorts from frayed wires at Terminals. Terminals and screws are of nickel plated brass. Insulation is of BM 120 molded Bakelite.

Illustrated are three types: Screw Terminals, Screw and solder Terminals and Screw Terminal above panel with solder Terminal below. For every need.

Six series cover every requirement: No. 140 — 5-40 screws, No. 141—6-32 screws, No. 142—8-32 screws, No. 150—10-32 screws, 151—12-32 screws and No. 152—¼-28 screws.

These sturdy Terminal Strips will not only improve your electrical connections but will add considerably to the appearance of your equipment. A truly modern Terminal.

Write today for catalog No. 14 listing our complete line of Barrier Strips in addition to other Electrical Connecting Devices.

HOWARD B. JONES COMPANY
2460 W. GEORGE ST. CHICAGO 18

For COMMUNICATIONS and INDUSTRIAL Jobs



Power Transformers
(Up to 1 kw.)

Audio Transformers

High-Voltage Transformers

Filter Chokes

Coils

DINION COIL COMPANY, Inc.
CALEDONIA, N. Y.

Specialists in Difficult Designs

ectricity

ELECTRIC PLANTS
Onan

FOR RADIO AND ELECTRONIC APPLICATIONS

ONAN ELECTRIC GENERATING PLANTS supply reliable, economical electrical service for electronics and television applications as well as for scores of general uses.
Driven by Onan 4-cycle gasoline engines, these power units are of single-unit, compact design and sturdy construction. Suitable for mobile, stationary or emergency service.



Models range from 350 to 35,000 watts, A. C. types from 115 to 660 volts, 50, 60, 180 cycles, single or three-phase and 400, 500 and 800 cycles, single phase. D. C. types from 6 to 4000 volts. Also available in dual voltage and special frequency types.

Write For Folder 690-A describing complete Onan Line

Model shown is from W2C series: 2000 to 3300 watts; powered by Onan two-cylinder, water-cooled engine.

D. W. ONAN & SONS
3275 Royalston Ave. Minneapolis 5, Minn.

MANUFACTURERS OF RADIO, ELECTRICAL AND ELECTRONIC COMPONENTS

VOKAR Corporation

7300 HURON RIVER DRIVE · DEXTER, MICHIGAN

advanced stage of practical development since the whole system is based upon scientific developments worked out during the war. It is estimated that the complete equipment, including challenger, replier, and all accessories for airplane use, will weigh approximately 200 pounds and require a space, exclusive of antenna blisters, of about 4.8 cu ft.

Instrument approach can be governed by an additional position on the control switch by means of which an oscilloscope can be made to show the horizontal and vertical position of the plane with respect to a true glide-path, together with the amount of heading into the wind required to resist any existing cross-wind. The desired glide angle is obtained semi-automatically by the mere setting of a switch, after which the pilot needs only to keep certain pips in alignment on his oscilloscope.

AAF Guided Missiles Group

THE FUNCTIONS OF THE First Experimental Guided Missiles Group, established this year by the Army Air Forces with headquarters at Elgin Field, Florida, and commanded by Colonel H. T. Alness, will be development of tactics and techniques of guided missile operations, training of personnel, development of organizational and equipment requirements of the group, and demonstration of guided missiles in the AAF program.

Personnel for the group, to be composed of 715 enlisted men and 130 officers, will consist almost entirely of highly trained specialists. The men are being selected for their knowledge of radar, television, infrared, aerodynamics, control systems, and other scientific devices connected with guided missiles.

The group will not participate in origination or technical developments of guided missiles, but will develop their tactical use and determine the best methods of employing them in combat.

Guided Missile Projects

Several missiles have already been developed and are now ready for tactical experiments. The Azon bomb, a standard 1,000-pound bomb with a radio-controlled tail that can be steered to the left or right on receipt of radio signals from the plane drop-

"Alnico" permanent magnets

Specializing in the production of highest quality Alnico Magnets in all grades including new triple strength No. 5.

Production material checked to assure highest uniform quality of product.

Castings made to customer's special order on the basis of sketches or blue prints furnished.

Information and suggestions furnished on request.

GENERAL MAGNETIC CORPORATION

MANUFACTURERS OF HIGH COERCIVE MAGNETIC ALLOYS

2126 E. FORT STREET
DETROIT 7, MICHIGAN

MORE P. A's CONSULT MacRAE'S

For advertising and book rates, call your agency or write . . .

MacRae's Blue Book

A DIRECTORY OF AMERICAN INDUSTRY

29 E. HURON ST. CHICAGO 11, ILL.



Tight-Tolerance RESISTORS

★ Just turn those tight-tolerance resistor requirements of yours over to CLAROSTAT, just as other instrument-makers have been doing for years past.

Remember, CLAROSTAT specialists offer over two decades of winding experience, outstanding skill, and exclusive winding facilities. They wind all wire sizes even down to .0009" dia. Windings as fine as 600 to 700 turns per inch, on bakelite, ceramic or other material, flat or round. Also string windings in fibre glass and cord.

★ Submit your problem . . .

Solving your resistance and control problems is our business. Call on us for engineering collaboration, specifications, quotations.

CLAROSTAT Controls and Resistors

CLAROSTAT MFG. CO., Inc. · 285-7 N. 6th St., Brooklyn, N. Y.

Radio Headquarters

for 25 years

We ship at once—parts, equipment, whatever you need!

This house began its career almost as early as Broadcasting itself! Today, 25 years later, we're the world's largest radio supply house! **Standard Lines:** National, Hammarlund, R.C.A., Hallicrafters, Bud, Cardwell, Bliley, and all the others!

SUPERSPEED SERVICE Orders shipped out same day received, on most goods.

ENGINEERING SERVICE If your engineering problem requires special equipment, we'll make it

FREE!

Latest bargain flyer includes test instruments, record changers, communication receivers, ham transmitting tubes and a host of electronic items you need today.

Originators and Marketers of the Famous Lafayette Radio

Radio Wire Television Inc.

NEW YORK 13 BOSTON 10 NEWARK 2

Cut out coupon, paste on penny post card, mail today

R. W. T. Dept. ED-6
100 AVENUE OF THE AMERICAS, NEW YORK 13

Gentlemen: Send me FREE copy of your Latest Bargain Flyer C-36, packed with recent electronic equipment and components.

NAME_____

ADDRESS_____

CITY_____ ZONE_____ STATE_____

ping it, proved highly successful against bridges in India and Burma. One bridge was destroyed for each four sorties, a greatly increased efficiency percentage over ordinary bombs. A further development, completed just before the end of the war, was the Razon bomb, controllable in both azimuth and range.

Other guided missile projects include Felix, a bomb attracted to heat, and the Roc, a standard 1,000-pound bomb equipped with television to scan the target and relay vital information back to the aircraft.

Although the only fully developed American guided missiles at the present time are air-to-ground types dropped from an aircraft, extensive plans have been made for the development of ground-to-air and ground-to-ground missiles. The German V-2 rocket is an example of ground-to-ground missiles.

Further possibilities of guided missile development include retrievable missiles for reconnaissance, automatic photographic sorties, and other similar long-distance missions.

Wireless Television Camera

PEACETIME BENEFITS FROM wartime development of a television-guided bomb were described by Farnsworth Television & Radio Corp. A portable camera-transmitter unit, built originally to help bombardiers steer their missiles directly to the target, has proved adaptable to on-the-spot television news pickups. The camera is light enough to be carried in an ordinary large-sized suitcase and can be operated by battery if a power line is not available.

A main transmitter beams out synchronizing signals to lock in the signals of the portable camera-transmitter, which then sends its composite signal back to the main transmitter for broadcasting. The present range from which this signal can reach the main transmitter is about 15 miles.

The AAF high-angle television bombing technique was in its final stages when the war ended last August. The camera-transmitter unit, an 18-inch diameter cylinder having a depth of 15 inches, was shock-mounted in the nose of a 1000-pound bomb. Also in the bomb was a radio receiving unit which controlled a small gyroscopic mechanism in the tail section. After the bomb fell

SUPREME

TESTING INSTRUMENTS

AFTER A GREAT WAR RECORD

BACK AGAIN!



SUPREME MODEL 504-A TUBE AND SET TESTER

SUPREME regrets that war necessitated an interruption of service to its customers and friends. We are genuinely glad to get back into peacetime production—production for YOU.

MANY SUPREME INSTRUMENTS NOW AVAILABLE

—But not enough to take care of all orders at one time. Demand for accurate, dependable SUPREME equipment is such that we suggest you make arrangements for your needed new SUPREME models without delay.

SEE YOUR NEAREST SUPREME JOBBER NOW!

SUPREME

SUPREME INSTRUMENTS CORP.
GREENWOOD, MISS.
U. S. A.

Export Department:
THE AMERICAN STEEL EXPORT CO., Inc.
374 Madison Ave., New York 17, N. Y.

SAY MODERN METHODS SLASH SCREW COSTS 86%

KEENE, N. H. (Special)—Modern methods applied to screw manufacture were cited today as responsible for the incredible saving of 86% in screw costs for a customer of the New England Screw Company of this city. Figures show that the customer was paying $3.75 a thousand for screws from another source and that New England Screw furnished the same product for only 53c.

The customer first approached New England Screw when they became dissatisfied with deliveries and service from another manufacturer. Already far behind in production, they had little hope of catching up, much less of saving any money.

"Our delivery schedules had to be set so high," recalled the president of New England Screw, "they didn't dream we could maintain them. But we did! And saved them 86% in the bargain!"

One of the many special screws made by this firm is shown in the illustration at the left. New England Screw has been making standard and special screws and headed shanks for over 50 years, and their modern manufacturing methods are described in an interesting catalog which will be sent to any company requesting it. Engineers of any manufacturer using screws or headed shanks are invited to consult with their Engineering Department which will gladly co-operate.

NEW ENGLAND SCREW CO.
KEENE, NEW HAMPSHIRE



An Invitation to All Electrical Designers to

TRY SILVER GRAPHALLOY

for RELAYS MOTORS CONTROLS ELECTRONICS

FOR BRUSHES
High current density, low contact drop, low electrical noise, and self-lubrication are characteristics of this silver-impregnated molded graphite that may be the answer to your electrical brush problems.

FOR CONTACTS
Low contact resistance and non-welding when breaking surge currents are inherent properties of this unique combination of conductive silver and self-lubricating graphite.

SAMPLES of Silver Graphalloy will be gladly furnished for test on your applications. Silver Graphalloy is usually silver plated to permit easy soldering to leaf springs or holders. Why not WRITE NOW for your test samples?

ALWAYS SPECIFY GRAPHALLOY Trade Mark Reg. U.S. Pat. Off.

GRAPHITE METALLIZING CORPORATION
1055 NEPPERHAN AVE • YONKERS, NEW YORK

SLIP-RING AND COMMUTATOR BRUSHES AND CONTACTS

HARRIS

DUFLEX SHOCK MOUNTS

TUBULAR MOUNTS
Bonded or Torflex Type

TORFLEX BEARINGS



CONTROL VIBRATION
ELIMINATE SHOCK & NOISE

HARRIS PRODUCTS COMPANY
5106 Cowan Ave. • Cleveland 4, Ohio

NEW SOLDERING GUN

THE SPEED IRON*

Patent Applied For

100 Watts 115 Volts 60 Cycles

Soldering Heat in 5 Seconds

Wherever you have a soldered joint in radio, electrical or electronic repair and service work, the Speed Iron will do the job faster and better.

The transformer principle gives high heat—in 5 seconds—after you press the trigger switch. Convenient to hold with a pistol grip handle, the compact dimensions of this new soldering tool permit you to get close to the joint. The copper loop soldering tip permits working in tight spots. The heat is produced by the high current flowing through the soldering tip—permitting direct and fast transfer to the soldered connection.

If you want to save time on soldering jobs with a tool that is ready to use in 5 seconds, get a Speed Iron today. See your radio parts distributor or write direct.

*T.M. Reg U. S. Pat. Off.

WELLER MFG. CO.
515 NORTHAMPTON STREET, EASTON, PA.

BRADLEY

PHOTO ELECTRIC CELLS

Many Standard Mountings.

In addition to the housed model shown here, with its plug-in contacts, Bradley also offers tube socket, nut-and-bolt types and pig-tail contact mountings.

The shapes of Luxtron photocells vary from circles to squares, with every in-between shape desired. Their sizes range from very small to the largest required.

For direct conversion of light into electric energy, specify Bradley's photocells. They are rugged, lightweight and true-to-rating.

Illustrated literature, available on request, shows more models of Bradley photocells, plus a line of copper oxide and selenium rectifiers. Write for "The Bradley Line."

BRADLEY LABORATORIES, INC.

82 Meadow St. New Haven 10, Conn.

through the bay doors, the eye in its nose began to scan the terrain below, picking out roadways, bridges, buildings and even moving automobiles. The directional transmitting antenna in the rear sprayed this signal back toward the plane in a 90-degree cone.

In the plane, the bombardier picked out the target on a 5-by-7-inch monitoring screen, and guided the bomb in both azimuth and elevation by radio so as to keep the image of the target under the crosshairs.

RMA Changes Resistor Standards

IN RMA STANDARD M4-215, the markings for tolerance of fixed composition resistors have been expanded as follows:

Brown	Plus or minus 1%
Red	Plus or minus 2%
Orange	Plus or minus 3%
Yellow	Plus or minus 4%
Gold	Plus or minus 5%
Silver	Plus or minus 10%
No Color	Plus or minus 20%

The use of green for 5 percent was opposed, so as not to have two different ways of indicating the same tolerance.

In Standard M4-216, the exterior body color of insulated resistors may now be any color other than black. The preferred color is natural tan. The exterior body color of uninsulated resistors shall be black, except that in the case of unnisulated resistors with radial leads the exterior body color may be white if the resistors are color-coded in accordance with Standard M4-214B, or may be that of the color code of the first significant figure of the resistance value if resistors are color-coded in accordance with Standard M4-214A.

RMA Spring Meeting

IN TWO TECHNICAL sessions starting at 9:00 a.m. on Monday, April 29 and Tuesday April 30, 1946, eight technical papers will be presented at the Spring Meeting of the Engineering Department of Radio Manufacturers Association, to be held at the Hotel Penn-Harris, Harrisburg, Pa. At a dinner Tuesday evening R. C. Cosgrove, RMA president, will be toastmaster and W. R. G. Baker, director of the RMA Engineering Department, will speak on "The transmitter Engineer and the Electronics Industry."

The following papers are scheduled

SHORTEST LINE between DEMAND and SUPPLY

Your need for high quality radio-electronic components is satisfied quickly and on schedule when you deal with firms represented by the Henry P. Segel Co.

Our organization represents leading manufacturers of basic components, concerns with sound reputations for meeting strictest specifications and "delivering on time *as promised.*"

These are dependable sources of supply, geared to fulfill your requirements rapidly and efficiently.

For over 21 years our business has been serving manufacturers and jobbers in New England. Let us prove to you how we can help keep *your* production going at full speed. For prompt, complete information, contact us now!

HENRY P. SEGEL COMPANY

Manufacturers Representatives
Field Engineers

143 Newbury Street
Boston 16, Mass.

Tel.: KENmore 3012—6333—9755

Branch Office in
Hartford, Connecticut

Serving manufacturers, jobbers, schools and laboratories in New England

RAWSON TWIN MULTIMETER

Type 5012 Accuracy ½ of 1% DC
Size 12"x8"x6"
A Combination AC. Multimeter and DC Multimeter

Range of Measurements

DC 1 microampere to 1 Ampere.
20 Microvolts to 1000 volts.
AC (thermocouple type)
2 Milliampere to 3 Amperes.
60 Millivolts to 1000 volts.

Write for bulletin
WE ALSO SUPPLY

REGULAR DC METERS
THERMOCOUPLE AC METERS
MULTIMETERS
FLUXMETERS
ELECTROSTATIC VOLTMETERS

Special apparatus built to order

RAWSON ELECTRICAL INSTRUMENT COMPANY
111 POTTER ST. CAMBRIDGE, MASS.
Representatives
CHICAGO NEW YORK CITY

Cellusuede
FLOCK
HAS MANY USES IN RADIO

1. Coating cabinet interiors dissipates reflections and adds acoustical qualities.
2. Coating the edges of adjoining parts before assembly eliminates vibration.
3. Coating wire grills adds a smart finish at low cost.
4. Coating phonograph turntables adds a soft non-scratching cushion for records.
5. Coating cabinet bases lends a soft velvety "feel" and protection to table and desk tops.

Both Cotton and Rayon Flock are available immediately in a variety of colors.

A trial application will show you how easily this versatile material may be handled . . . how practical it is for the above mentioned uses.

Write for Booklet, Color Card, Samples and Prices

Cellusuede Products, Inc.
ROCKFORD, ILLINOIS

Find Out Now About
★STAR★ CERAMICS

There are many kinds for special uses, such as applications calling for resistance to electricity, heat, moisture, chemicals or weathering agents. There are more than a score of formulas in actual production at one time in our factory.

Send for "A Brief Survey of Technical Characteristics of Molded Ceramic Products." It is right to the point.

★

The STAR PORCELAIN CO.
Electronics Dept.
Trenton 9, N. J.

PRODUCTION WINDING FACILITIES

For all types of COIL & MOTOR WINDINGS

Wound completely to your specifications:

1 Any type of fractional horse power motors or generators, A.C. or D.C.
2 Three phase motors from 1/6 horse power to 5 horse power.
3 Shaded pole motors such as fans, blowers, etc.
4 Dynamotors or small aviation M.G. sets up to 500 watts output.
5 Solenoid coils.

IMMEDIATE DELIVERIES

Pilot ELECTRIC COMPANY
29 S. BROADWAY, LONG BRANCH, N. J.

for Radio Components....

call **NORMAN H. LAWTON**

ENGINEERING • SALES • SERVICE

NEW YORK: 1775 Broadway, 19 INDIANAPOLIS: 635 Pennsylvania St., 4

DIRECT FACTORY REPRESENTATIVE

- A. W. FRANKLIN MFG. CORPORATION—Sockets . . . Terminal Strips . . . Plugs . . . Assemblies.
- ELECTRO-MOTIVE MFG. CORPORATION—Moulded Mica Capacitors . . . Mica Trimmer Capacitors Fused Plugs . . . etc.
- F. W. SICKLES COMPANY (Eastern Representative)—I. F. Transformers . . . Antenna Loops . . . Trimmer . . . Condensers (mica and air dielectric) . . . Tuning Units
- QUAKER CITY GEAR WORKS—Precision Gears for Industry.
- UNITED TRANSFORMER COMPANY—Transformers
- MICA PRODUCTS COMPANY—Mica Sheets and Fabricated Parts

WEAR RESISTANT
NON-ABRASIVE
NON-CORROSIVE
PERMOPIVOTS
NON-MAGNETIC
SUPER-POLISHED
Yes, Extra Value!
Long after the ordinary pivot has worn out you'll find PERMOPIVOTS in the prime of life—faithfully keeping precision instruments precise! It's all due to the special PERMOMETAL tip—the ideal osmium alloy. . . . Made to your specifications.
Write for information!
PERMO
INCORPORATED
6427 RAVENSWOOD AVE., CHICAGO 26
MANUFACTURING METALLURGISTS

for the technical program:

April 29: Broadcast Transmitter Design as Detemined by Market Survey, by M. R. Briggs of Westinghouse; A 5-kw Television Tube—Design and Application, by R. B. Ayer and C. D. Kentner of RCA; A Proposed Method of Rating Microphones and Loudspeakers for Systems Use, by F. Rumanow of Bell Labs; Railway Communication, by A. V. Dasburgh of General Railway Signal Co. and E. W. Kenefake of GE.

April 30: The Hydrogen Thyratron, by H. Heins of Sylvania; Mobile Communications Range Tests, by D. E. Noble of Galvin; The Use of Intermodulation Tests in Designing and Selecting High Quality Audio Channels, by J. K. Hilliard of Altec Lansing Corp.; Navar System of Radio Navigation and Air Traffic Control, by H. Busignes and P. Adams of Federal Telephone & Radio Corp.

MEETINGS TO COME

APRIL 1; IRE-AIEE Atomic Engineering Lecture Series (members $1 per lecture; nonmembers $1.50); Mass Analysis and Isotope Separation, by J. A. Hipple of Westinghouse; 7 p.m. at Engineering Societies Building, 33 W. 39th St., New York City.

APRIL 8; IRE-AIEE; Measuring Instruments for Atomic Engineering (see April 1 data).

APRIL 10; AIEE; Applications of Servomechanisms, by S. J. Mikina; 7 p.m. at 301 Pupin Hall, Columbia University.

APRIL 15; IRE-AIEE; Medical and Industrial Applications of Atomic Physics, by R. D. Evans of MIT (see April 1 data).

APRIL 25-30; INTERNATIONAL LIGHTING EXPOSITION; Stevens Hotel, Chicago.

APRIL 29-30; RMA SPRING MEETING; Hotel Penn-Harris, Harrisburg, Pa.; chairman V. M. Graham, P.O. Box 750, Williamsport, Pa.; eight technical papers to be presented.

MAY 13-16; RADIO PARTS AND ELECTRONIC EQUIPMENT TRADE SHOW; Stevens Hotel, Chicago; inquiries to 221 N. LaSalle St., Chicago; special train for radio industry personnel leaves Grand Central Station, New York City at 4:15 p.m. May 12—

Optical Glass Specialities

Television Reflectors

Precision-polished optical face plates for cathode ray tubes

Optical lenses, prisms and flats

FS Precision-Bore Glass Tubes with bore exact within .00002"

Contact us for such requirements

FISH-SCHURMAN CORPORATION
230 East 45th St., New York 17, N. Y.

Fish-Schurman

RADEX

CHICAGO

In future peace-time production, Radex will uphold its war-won reputation by the scope and caliber of its service to the radio and electrical industries.

Radex Corporation
53 W. Jackson Blvd., Chicago 4, Ill.

Because of the 4400 volt per mil breakdown voltage of the Plasticon film dielectric, high voltage Plasticons are smaller, lighter and more economical than paper capacitors.

***Plasticons—plastic film dielectric capacitors**

Condenser Products Company
1375 NORTH BRANCH STREET
CHICAGO 22, ILLINOIS

STANDARD CRYSTALS

Send for New Catalog

STANDARD PIEZO COMPANY

Established 1936
Quartz Crystals and Frequency Control Equipment
Office and Development Laboratory

SCRANTON, PA. — CARLISLE, PA., P. O. BOX 164 — CARLISLE, PA.

Representatives

COOPER-DiBLASI
259 WEST 14th STREET, NEW YORK 11, N. Y.

HAL F. CORRY
3522 GILLON AVENUE, DALLAS 5, TEXAS

THE FOSTER COMPANY
409 LUMBER BLDG., MINNEAPOLIS, MINN.

GERBER SALES COMPANY
94 PORTLAND STREET, BOSTON 14, MASS.

A. SIDNEY HARDY
650 BOULEVARD N. E., ATLANTA, GA.

HARRY A. LASURE
2216 WEST 11th STREET, LOS ANGELES 6, CALIF.

L. D. LOWERY
1343 ARCH STREET, PHILADELPHIA, PA.

MANUFACTURERS SALES TERMINAL, Inc.
222 COLUMBIA BLDG., SPOKANE, WASHINGTON

HARRY B. SEGAR & COMPANY
ELLICOTT SQUARE BLDG., BUFFALO, N. Y.

E. J. WALL
1836 EUCLID AVENUE, CLEVELAND 15, OHIO

CHECKS - GRADES RESISTORS

100 Ohms to 100 Megohms At A GLANCE

Clippard

AUTOMATIC RESISTANCE COMPARATOR

Type PR-4

The quality inspection instrument every radio, electrical, electronics, resistor manufacturer and large parts jobber has long been looking for. Makes precision checking of incoming shipments of resistors, factory output, matching or grading to close tolerance limits, a simple production routine!

Easy to Operate

Instrument is readied for operation by snapping power switch, warming up, adjusting zero and connecting standard resistor at left. Operator places resistances to be checked across "unknown" terminals in center. Accuracy can be checked periodically by simple turn of knob at left. To change from one value resistor test to another, merely plug in proper standard. No other adjustment necessary!

Reads Percent Deviation

Face of large, easily-read meter in center illuminates when unknown is inserted, showing percent of variation from standard within limits of —25% to +30%. NO OTHER OPERATION IS REQUIRED, reducing inspection time to *absolute minimum!*

Laboratory Quality

Rugged laboratory construction and careful calibration assure accuracy of better than ±1% throughout entire range of 100 ohms to 100 megohms. Line variations, 105-125 volts A.C., automatically compensated for by special newly-developed electronic bridge circuits. An instrument that pays for itself quickly and saves you time and labor costs for years thereafter. Write for complete details and specifications, today!

SPECIAL INSTRUMENTS FOR ELECTRICAL AND ELECTRONIC TESTING

ELECTRO MAGNETIC WINDINGS

R. F. COILS **SUB-ASSEMBLIES**

Clippard INSTRUMENT LABORATORY

1440 CHASE AVE. CINCINNATI 23, O.

make reservations with Perry Saftler, 53 Park Place, New York.

MAY 15-17; NEW ENGLAND ELECTRICAL TRADE SHOW; Exhibition Hall, Boston, Mass.

MAY 20-25; NATIONAL MARITIME EXPOSITION; Grand Central Palace, New York City; inquiries to headquarters at 17 Battery Place.

JUNE 20-23; SOCIETY FOR THE PROMOTION OF ENGINEERING EDUCATION; annual meeting, Jefferson Hotel, St. Louis, Mo.

BUSINESS NEWS

GENERAL ELECTRIC Co. has set up a new industrial engineering division, to be known as the Power Electronics Division and headed by L. W. Morton.

GRIGSBY-ALLISON CO., INC., Arlington Heights, Ill., organized in late 1945 by R. J. Grigsby and K. C. Allison, will produce radio switches, tuners, and other electrical and mechanical devices in a new plant now nearing completion.

L. S. BRACH MFG. CO. celebrates its 40th anniversary by moving into its recently purchased three-story building in Newark, where they will concentrate on development and increased production of a diversified line of antennas while continuing to manufacture private-brand radio and electrical products.

PRECISION SPECIALTIES, Los Angeles, has started operation of a new radio-electronics section. Among the first products will be several models of home radios.

U. S. TELEVISION MFG. CORP. has moved to new quarters at 3 West 61st St., New York City, where they are planning for a production schedule of over 5,000 finished radios per week. Manufacture of television sets is scheduled to begin in the spring.

GENERAL INSTRUMENT CORP., Elizabeth, N. J., is installing a 1½-mile conveyor system and will soon have a total of 3,400 workers as compared to 1,100 on V-J day.

AUDIO PRODUCTS CO., Burbank, Calif., has established an electronic application division to produce various types of electronic controls.

CINCH MFG. CORP., Chicago, wholly owned subsidiary of United Carr Fastener Corp., has purchased the assets of Howard B. Jones Co., and will continue production of Jones

STANDS UP IN HARD SERVICE

IT'S ENGINEERED WITH Hi-Q COMPONENTS

Every engineer knows that failure starts with the little parts. That's why more and more development engineers place their dependence on Hi-Q Ceramic Capacitors, Wire Wound Resistors and Choke Coils. They know through their own actual tests, that Hi-Q Components stand up under every condition of temperature, humidity, vibration and shock. Test these sturdy components in your own applications. Send your specifications for samples and complete data.



CERAMIC CAPACITORS

Made of titanium dioxide (for temperature compensating types). Tested for physical dimension, temperature coefficients, power factor and dielectric strength.

WIRE WOUND RESISTORS

Immediately available in standard ratings or precision built to any tolerance or value.

CHOKE COILS

Sturdy Construction. Insulated or bare types. Quantity production available at once.

ELECTRICAL REACTANCE CORPORATION

FRANKLINVILLE, N.Y.

. . . . also pioneers in the design and manufacture of

Ceramic, Porcelain & Steatite insulators, Antennas, Hook-Up Wires, Shielded Microphone Cable and S. J. Cable.

Specify and use "Birnbach" products. Complete Stock at your jobber.

BIRNBACH

BIRNBACH RADIO CO., Inc.
145 HUDSON ST NEW YORK 13, N Y

New . . . **"DIALCO" PLN-849** *Pilot Light*

features the
New Neon NE-51 Bulb
with

BUILT-IN RESISTOR

For 110 Volts (and higher)



Patent Pending



A RUGGED UNIT. Consumes a small amount of current (under one milliampere) and has dependable long life. Note these important features of the PLN-849 Pilot Light: (1) RESISTOR INTEGRAL with socket assembly. Value to suit supply voltage. (2) Moulded Bakelite Socket. (3) Full-view Jewel Plastic Cap for visibility at all angles. (4) Rugged terminals, binding screw or permanent soldering type. (5) High resistance to vibration or shock. (6) Supplied complete with General Electric Neon NE-51 Bulbs. May also be adapted to accommodate General Electric Radio Panel Bulbs such as 47, 44, etc., for low voltage circuits. Bulbs removable from front of panel.

DIALCO

Write today for samples and prices. There is no obligation.

WRITE FOR NEW ILLUSTRATED BROCHURE

DIAL LIGHT CO. *of America, Inc.*
900 BROADWAY • NEW YORK 3, N. Y.
Telephone: ALgonquin 4-5180-1-2-3



Lavite STEATITE CERAMIC

Properties and Characteristics of Our LAVITE SI-5 Steatite Ceramic Body

Compressive Strength	90,000	lbs. per square inch
Tensile Strength	7,200	lbs. per square inch
Flexural Strength	10,500	lbs. per square inch
Modulus of Rupture	20,000	lbs. per square inch
Dielectric Strength	235	volts per mil
Dielectric Constant	6.42	Frequency of 1 megacycle
Loss Factor	2.90	
Power Factor	.446	
Bulk Specific Gravity	2.664%	
Density (from above gravity)	0.096	lbs. per cubic inch
Hardness (Mohr scale)	7.0	
Softening Temperature	2,350°F.	
Linear Coefficient of Expansion	8.13x10—6	
Moisture Absorption (ASTM D-116-42-A)	0.009%	

Design engineers and manufacturers in the radio, electrical and electronic fields are finding in LAVITE the precise qualities called for in their specifications . . . high compressive and dielectric strength, low moisture absorption and resistance to rot, fumes, acids, and high heat. The exceedingly low loss-factor of LAVITE plus its excellent workability makes it ideal for all high frequency applications.

We will gladly supply samples for testing.

D. M. STEWARD MFG. COMPANY
Main Office & Works Chattanooga, Tenn.
Needham, Mass Chicago Los Angeles

EISLER EQUIPMENT
..complete and diversified for every phase of electronic* manufacture!



(A) No. 600-KC3P, 50 KVA Press Type Spot Welder, 3 Spots, Air Operated, 18" Throat—a high production unit.

(B) No. 57-8L New Eisler 8 head type Tipless Sealing Machine. Adaptable for all types and sizes of bulbs.

(C) EISLER Special Transformers and Reactors—high or low voltage, air cooled, oil immersed or encased.

The CHAS. EISLER line of specialized electronic tools, machines and devices is complete and diversified. Included are innumerable types of welders — spot, seam, butt, rocker, arm, pneumatic and special types. Also included are hundreds of devices for vacuum tube manufacture — glass tube cutters, slicers, stem and sealing machines as well as an all-inclusive line of transformers for every industrial and general need.

*** EISLER serves 99% of American vacuum tube producers today. Write for completely illustrated catalog.**

CHAS. EISLER
EISLER ENGINEERING CO.
751 SO. 13th STREET Near Avon Ave. NEWARK, NEW JERSEY

WHAT

can be done to improve transmitting equipment?

The answer is BUD Products when precision-made coils and condensers are needed. Ruggedness and durability characterize this line.

All coils are of the air-wound type to promote efficiency. The use of a variable link to the plate tank as a means of varying the loading of an R.F. stage is effectively utilized.



This BUD condenser is the deliberate choice of many engineers for use in broadcast transmitters, high-power transoceanic communications and other types of highly specialized electronic devices.

BUD Can Supply All Your Needs . . .

. . . with the latest types of equipment including: condensers — chokes — coils — insulators — plugs — jacks — switches — dials — test leads — jewel lights and a complete line of ultra-modern cabinets and chassis.

BUD

BUD RADIO, INC.

CLEVELAND 3, OHIO

products under a new management, with Howard B. Jones being retained in a consultant capacity.

PAUL GODLEY CO., Upper Montclair, N. J., has moved its radio engineering laboratories to Great Notch, N. J., in a tranquil, close-to-nature setting at The Notch in the Watchung Mountains.

ACME ELECTRIC & MFG. CO. has a new and modern plant nearing completion at Cuba, N. Y. that will more than double its transformer



Cuba, N. Y. manufacturing facilities of Acme Electric & Mfg. Co. Noisebreaking walls will separate punch press departments from assembly lines

manufacturing facilities. One entire section will be devoted to research on transformer design and performance.

TECHNOLOGY INSTRUMENT CORP. has been established in Waltham, Mass. by H. H. Scott, R. W. Searle, and L. E. Packard, all formerly with General Radio Co. The new firm will develop and manufacture electronic and laboratory equipment. Mr. Scott, who will serve as president, was responsible for development of General Radio's present line of sound and vibration measuring equipment, f-m and broadcast station monitoring equipment, and other r-f and a-f instruments.

RCA VICTOR DIVISION has leased a plant in Chicago solely for the fabrication and assembly of auto radios, with peak employment of approximately 700 workers scheduled for June 1.

THE ELECTRODYNE CO., Boston, was formed recently to provide research and development service in electromechanics, vacuum-tube applications, and optics, as well as manufacture of electronic equipment. Bertram Wellman is president, Elek J. Ludvigh, II, is director of research, and B. J. Kaplan and Leslie G. Rathbun, Jr., are vice-presidents.

ILLINOIS INSTITUTE OF TECHNOLOGY will make available to sponsoring or-

NEW

MPB



MASTER PUSH BUTTON SWITCH

by

GENERAL CONTROL COMPANY

The new "Master" Model MPB push button switch is new from stem to stern. Its sturdy, modern construction means long trouble-free life —its fine silver contacts, rugged, non-corrosive parts, quality workmanship and only the finest materials throughout, mean customer satisfaction for you.

The new "Master" Model MPB non-locking frame includes nine switch positions — locking type frames have eight switch positions and one reset position. Any switching combination which has been set can be released by one operation of the reset button.

The new "Master" Model MPB is rated at 5 - 10 amperes, 125 volts, 60 cycles A.C. (non-inductive load). If you are a manufacturer or user of electronics and communications equipment, it will pay to investigate the new Model MPB. Further information on request.

Write for

NEW Catalog No. 200

It's just off the press!

General Control Company

1202 Soldiers Field Road

Boston 34, Mass.



HOW TO
Speed up Production
when pouring Potting Compound

Here's a typical installation of Sta-Warm compound melting equipment, employing heated hose for dispensing.

From a rectangular tank built to user's own specifications for capacity and proportions, and equipped with variable thermostat control, melted potting compound is dispensed into transformers through a 10 ft. Sta-Warm flexible metallic hose. The hose itself is electrically heated to maintain proper temperature of the compound until it reaches its destination. A separately controlled thermostat on the hose line further guarantees that the compound will neither burn (and carbonize) or freeze (and solidify) before leaving the nozzle.

The tank only, the hose only, or both as a complete working unit may be ordered as required to fit into your compound melting and dispensing set-up to speed up production without adding extra man-hours.

Why not inquire for full details and prices today by writing fully to Dept. D?

STA-WARM ELECTRIC CO.
1000 N. CHESTNUT ST. · RAVENNA, OHIO



SPECIFICATIONS:
Manual counter type M1. Non-electrical but otherwise exactly as described. Complete with lever. Each: $1.75. Electric counter, Non-reset, type NR1, exactly as shown and described. $4.10 each for 115 volts, 60 cycles. Other voltages from 6 to 220 are 75c extra. Convenient mounting bracket, 20c. Reset electric counter, type R1 (not shown), soon available. 5 digits. Heavy duty. Resets with twist of fingers. Torque motor type, suitable also for electronic circuits. Standard voltages 6 to 220. Net each: $14.50.

40,000 TIMES EVERY HOUR!

A G&G HiSpeed ELECTRO-COUNTER, registers up to 40,000 counts an hour . . . it records with consistent accuracy up to 600 times a minute!

Used for Production Controls, Operational Checks, Functional Actions. Increases accuracy; reduces time of record-taking; permits accumulation of new data.

Compact, sturdy, well-engineered. Mechanism entirely enclosed in cadium-plated housing. Easy-to-read figures behind plastic window.

Write for counter sheet I-246
facsimile paper sheet "Electrex"

GORRELL & GORRELL
Originators and Makers of Recording Equipment Since 1925
HAWORTH, NEW JERSEY



SMALL PARTS

Filaments, anodes, supports, springs, etc. for electronic tubes. Small wire and flat metal formed parts to your prints for your assemblies. LUXON fishing tackle accessories, double pointed pins, fine sizes wire straightened. Inquiries will receive prompt attention.

ART WIRE AND STAMPING CO.

227 High St. Newark 2, N. J.

ELECTRONICS ENGINEERING

PRODUCT DEVELOPMENT AND ENGINEERING • RADIO, TELEVISION, ELECTRONIC EQUIPMENT DESIGN

Electrical Controls, Motors, Generators, Power and Sub-Station Equipment. FM, Standard and Short Wave Amplifiers, Transformers, Speakers, Station Equipment. Special Induction and Dielectric Heating Machines. Photo-electric Controls, High Frequency Generators, Measuring Equipment, Etc.

action

When You Need It Fast
Entire Project or Any Phase
Work in Your Shop or Ours

BARNES & REINECKE

INDUSTRIAL DESIGNERS & ENGINEERS
230 E. OHIO ST.
CHICAGO 11

STAFF of 181 12th YEAR

ANOTHER
SPECIAL BY
PROGRESSIVE
QUALITY PROMCO BRAND
BLUE PRINT
ACTUAL SIZE
ENLARGED FOR DETAIL
CATALOG SHOWS DOZENS MORE
Special heads, threads and finishes on any metal or alloy adapted to cold upset. Weekly output: 25,000,000 pieces. Many specials, suggesting production savings for you, illustrated in latest catalog. Includes weights per 1M standard pieces, dec. equivs. of fractions, other purchasing and engineering helps. Write for Catalog 18.
The PROGRESSIVE MFG. CO.
50 NORWOOD ST., TORRINGTON, CONN.



Your profit from the use of any kind of equipment hinges on its quality of performance — and on its *endurance*. Electronic Engineering Company transformers are built ruggedly to give *lasting* service under all conditions. If you have special and difficult transformer problems, feel free to make use of the finest engineering talent and most complete electronic laboratories.
Write or call today.

"SPECIALIZED *Transformer* ENGINEERS"
3223-9 WEST ARMITAGE AVE.
ELECTRONIC *Engineering* COMPANY INC.
CHICAGO 47, ILL.

ganizations the facilities of its Ohmite Laboratory for making precise measurements of electrical and magnetic quantities, approaching in accuracy those of the National Bureau of Standards.

PERSONNEL

ALEXANDER NORDEN, for many years vice-president of L. S. Brach Mfg. Co., has been elected president of Interstate Mfg. Corp., Newark, N. J.

CHARLES JEFFERS has returned to his post as technical director of WOAI, San Antonio, after three years service with OWI where he served as chief of the Engineering Division, Communications Facilities Overseas Branch.

WILLIAM F. FRANKART, formerly assistant chief engineer of Aireon Mfg. Corp., Kansas City, Kansas, takes over as radio department head at Precision Specialties Co., Los Angeles.

ROGER B. COLTON has retired from the Army after 35 years service and is now associated with the firm of

General Henry H. Arnold (left) presenting Distinguished Service Medal and Legion of Merit to Major General Roger B. Colton in recognition of outstanding wartime services that included developments leading to applications of radar to strategic bombing, fire control, and guided missiles

Colton & Foss, Inc., Washington, D. C., electronic consultants specializing in broadcast, public service communications, radio, and radar development.

ARTHUR H. WULFSBERG has joined the Research Division of Collins Radio Co. Previous work involved design and production of radar and loran equipment at Sylvania Electric Products Inc.

C. R. MADUELL, JR., formerly research physicist for Signal Corps

2 VITAL AIDS

TO THE MANUFACTURER OF

Miniature Tube Radios

★ STAR



DOUBLE-CHECK SYSTEM

#JE-10—Miniature socket wiring plug for accurate alignment of miniature socket contacts during wiring. Precision cast of zinc base alloy—Pins of stainless steel.

#JE-12 — (Hardened tool steel insert) or JE-13 (Stainless steel insert) Miniature tube pin straightener to obtain a perfect fit when the tube is placed in the set.

For complete information and prices—write

RADIO ACCESSORY DIVISION

STAR EXPANSION PRODUCTS CO.

147 Cedar St., New York 6, N. Y.

HATHAWAY OSCILLOGRAPHS

S8-B

For Every Purpose

S12-A

TYPE S8-B—General purpose, laboratory and field, 12 to 24 elements. Permanent film or paper record, 6" to 10" wide, to 200' long. Record speeds from 1/3" to 40" per second, instantly selected by quick changing transmission. Simultaneous viewing and recording. Time coordinate device. Bulletin SP-165.

TYPE S8-C—Identical to S8-B—with 24 to 36 elements. Bulletin SP-165.

TYPE S8-D—Similar to Type S8-B in quality and accuracy. Low cost; automatic features are not included. Bulletin SP-175.

TYPE S12-A—Portable general purpose laboratory and field, 12 elements. Record speeds quickly selected by change gears from ½" to 48" per second. Simultaneous viewing and recording. Bulletin SP-167.

TYPE S14-A—NEW STUDENT OSCILLOGRAPH. Accurate and dependable. General purpose laboratory and field. Ideal for colleges and technical schools. Instant magazine loading. Simultaneous viewing and recording. Bulletin SP-182.

HATHAWAY INSTRUMENT CO., Denver 10, Colo.



STRAIN RELIEFS
HEATER PLUG CONTACTS
CUBE TAP CONTACTS

Complete line for all applications. Many sizes ready for shipment. When writing for literature and samples, please state wire size.

HEYCO

HEYMAN MANUFACTURING COMPANY

510 Michigan Ave. Kenilworth, N. J.

A Buy-word for Excellence

40 YEARS

DEPENDABILITY

PUR-A-TONE
Reg. Trade Mark

ANTENNAS

1906 BRACH 1946

ALL TYPES FOR

- **AUTOS**
- **HOMES**
- **MARINE**

A.M. — F.M. — TELEVISION

Make pleased customers and bigger profits . . . ask your distributor for BRACH Puratone ANTENNAS.

Special-purpose transmitting antennas designed for volume production to your own specifications. Collapsible — sectional — direction finding — radar and coaxial type. All sizes, lengths and materials. Consult us on your needs.

L. S. BRACH MFG. CORP.

200 CENTRAL AVENUE NEWARK, N. J.

WORLD'S OLDEST AND LARGEST MANUFACTURERS OF RADIO ANTENNAS AND ACCESSORIES.

CAPACITOR QUESTIONS Answered!

JUST OUT!



"THE ELECTROLYTIC CAPACITOR"

by Alexander M. Georgiev

Probably no Radio-Electronic component is more important than the Electrolytic Capacitor, and this new book by Alexander M. Georgiev who has devoted more than 15 years to Capacitor research and development answers all the many questions engineers, designers, servicemen and others have been asking about this subject. Abundant data are presented as to Electrolytic Capacitor constructional features,—where, when and how to use them to best advantage in preference to non-electrolytic types—in short, everything you need to know in order to utilize, buy, specify, replace or service Capacitors intelligently and efficiently. A comprehensive bibliography and list of patents will prove of far-reaching value. Contains over 200 pages and eighty illustrations including graphs, photomicrographs, oscillograms, etc. Just out in limited edition—the first modern book to be written on this vital component! Order today while the supply lasts.

WHAT TYPE?
WHY?
WHERE?

$3.00 $3.25 foreign

ALL THE FACTS ON A LITTLE KNOWN SUBJECT

Electrolytic Capacitor Construction Characteristics; Advantages; Applications; Operation at low and high voltages and frequencies; a-c or pulsating d-c; ambient conditions; wets versus drys; electrolytics versus non-electrolytics; behavior of various types; choosing the best type for a given application and operating conditions; servicing; testing, replacement and emergency repairs—and dozens of other subjects of foremost interest to all who design, handle, or service equipment incorporating capacitors.

ORDER NOW!

MURRAY HILL BOOKS, Inc.
Dept. E-46, 232 Madison Ave., New York 16, N. Y.

Enclosed find $.....for .....copies of Alexander M. Georgiev's "The ELECTROLYTIC CAPACITOR" (Price $3 each, $3.25 foreign) or ☐ send C.O.D. (in U.S.A. only) for this amount plus postage.

Name .....

Address .....

City & Dist. No.....State.....

Engineering Labs, is now consultant physicist and vice-president of Delta Electronic Equipment Co., New Orleans, La.

ROBERT H. HOLLISTER has been named service department manager at Collins Radio Co.

MATT J. JELEN, after ten years with Sparks-Worthington Co., has joined U. S. Television Mfg. Corp. as senior engineer in the Radio Division.

ALLEN D. PETTEE has been made chief electrical engineer of General Cable Corp., New York, N. Y.

HOMER HOWARD is now chief engineer of Audio Products Co., Burbank, Calif. He was formerly manager of the Pacific Coast radio division of Lear Aircraft.

H. Howard

C. M. Wheeler

CARSON M. WHEELER has joined Amperex Electronic Corp., Brooklyn, N. Y., as chief engineer in charge of tube development. For the last ten years he was with Federal Telephone and Radio Corp., serving during the war as assistant to the director of vacuum tube research.

J. D. SCHANTZ received a promotion to assistant manager of the research department at Farnsworth Television & Radio Corp., Fort Wayne, Indiana, having been with this firm and the predecessor company in Philadelphia since 1936.

J. D. Schantz

H. C. Florance

HERBERT C. FLORANCE has been made chief engineer of WGHF, new f-m

WOLLASTON Process Wire . . . *So Fine it can be seen only under high Magnification*

We can draw wire as small as

1/100,000 of an inch in diameter

. . . available in Platinum and some other Metals

.00001" is less than 1/30 the diameter of the smallest wire die commercially available. Yet our Wollaston Process wire (drawn in a silver jacket) closely meets your specifications for diameter, resistance and other characteristics.

●

This organization specializes in wire and ribbon of smaller than commercial sizes and closer than commercial tolerances. *Write for List of Products.*

SIGMUND COHN & CO.

SINCE 1901

44 GOLD STREET NEW YORK 7

ACTUAL SIZE

Now

Commercial Crystals to 35 Megacycles

35 megacycle crystals now mean fewer doublers, less weight, space and cost in your VHF equipment. Immediate delivery of specified frequency crystals.

- Low Temp. Co-efficient
- .01% Tolerance
- 60 ma. Current Capacity
- Nominal Cost

Territory Open for Factory Representation

RADIO SPECIALTY MFG. CO.
PORTLAND, OREGON

PROBLEMS of weight, space, alignment, obstructions, vibration, and cost—solved by

WALKER-TURNER Flexible Shafting

● In certain applications of control and power transmission, no other form of drive proves as successful as Walker-Turner Flexible Shafting. For mechanical coupling between components; for control of capacitors, potentiometers, tuning circuits; for flexible power drive around obstructions—use Walker-Turner Flexible Shafting. Our wide experience is at your disposal, without any obligation to you or your company.

WALKER-TURNER COMPANY, INC.
PLAINFIELD, NEW JERSEY

walker-Turner COMPANY, INC. PLAINFIELD, N.J. U.S.A.

FLEXIBLE SHAFTING
FOR REMOTE CONTROL AND POWER TRANSMISSION

Bagshaw's NEEDLES

FAMOUS SINCE 1892
for Better Record Performance

Maybe the very first "cutting" was done with the grand-daddy of this famous recording needle . . . for BAGSHAW came in with the talking machine itself! Preferred in sound studios where only the BEST will do . . . perfect cutting mate for our great transcription Needle that you know so well!

H. W. ACTON CO., INC.
SOLE DISTRIBUTOR
370 SEVENTH AVENUE NEW YORK 1, N. Y.

REGULATED POWER SUPPLY

250-450 VOLTS

Wide fields of application have been opened up both in research and industry for this unit. A-C ripple is negligible and extreme care has been taken to eliminate high-frequency noise. Regulated power supply units are invaluable for such applications as amplifiers, television pulse generators, constant frequency oscillators, and measuring equipment.

Other G-E regulated power-supplies are available in the following ranges: **180-300 volts 160-1500 volts Dual Regulated**

Write today: Electronics Department, Specialty Division, General Electric, Syracuse, N. Y.

GENERAL ELECTRIC
184-E2

Electronic Measuring Instruments



PS-1

The FINEST MICROPHONES
for P.A. and RECORDING!
AMPERITE VELOCITY MICROPHONE WITH PATENTED ACOUSTIC COMPENSATOR
New P. G. DYNAMIC WITH NEW SUPERIOR ELIPSOID PICK UP PATTERN!
AMPERITE KONTAK MIKES
IDEAL FOR AMPLIFYING STRINGED INSTRUMENTS
USED WITH ANY AMPLIFIER AND WITH RADIO SETS
ASK YOUR JOBBER WRITE FOR FOLDER
AMPERITE
AMPERITE



• PLASTIC FABRICATING •

PUNCHED AND FABRICATED PARTS, SPEED AND ACCURACY IN
TOOL CONSTRUCTION AND PRODUCTION REQUIREMENTS

• BAKELITE SHEETS, RODS, TUBES •

Over 20 years of fabricating experience

ELECTRICAL INSULATION CO., INC.

12 VESTRY ST., NEW YORK 13, N. Y.

and facsimile broadcasting station in New York City.

FRANK H. R. POUNSETT, formerly chief engineer of the radio division of Research Enterprises Limited, is now chief engineer of Stromberg-Carlson Co. Limited, Toronto.

GEORGE L. HALLER has been named assistant dean of the School of Chemistry and Physics at Pennsylvania State College. Colonel Haller's work during the war dealt with radio and radar countermeasure equipment, submarine detection from aircraft, and radio and radar control of guided missiles.

SAMUEL GUBIN becomes vice-president in charge of engineering for Spectrum Engineers, Inc., newly organized engineering and consulting firm in Philadelphia. He was formerly with RCA in Camden, where he supervised the microwave beacon group.

CHARLES J. ALBA is radio research engineer at Air Associates, Inc., Los Angeles. He was formerly with Air Track Mfg. Co., College Park, Md. in the same capacity.

NEAL TURNER is now quality control chief at Hallicrafters Co., Chicago.

JOHN J. LIVINGOOD has left the faculty of Harvard University to become assistant director of research at Collins Radio Co., Cedar Rapids, Iowa. He directed developmental work on high power at ultrahigh frequencies at Harvard RRL and worked on cyclotron design and operation.

J. J. Livingood

W. R. Jones

WALTER R. JONES was made chief engineer of the Radio Tube Division at Sylvania Electric Products Inc. He has been with Sylvania 17 years. THOMAS C. STEPHENS comes to the Research Division of Collins Radio Co. from the University of Iowa where he was an instructor in radio and electrical engineering.

GWILYM A. PRICE becomes president

ANTICIPATE YOUR REQUIREMENTS!

First Come . . . First Served!

Orders for transformers are pouring in so fast that we will soon be booked to capacity for several months to come. If your product requires heavy duty filter reactors, swinging reactors, or plate transformers, anticipate your requirements and place your order NOW!

DONGAN ELECTRIC MFG. CO.
2977 Franklin Detroit 7, Mich.

DONGAN
TRANSFORMERS
The Dongan Line Since Nineteen-Nine

Preferred

as a source of precision-made WASHERS and STAMPINGS manufactured to your specifications

CUP WASHERS for Binding Screws

WHITEHEAD STAMPING CO.
1691 W. Lafayette Blvd. Detroit 16, Michigan

GASES

ARGON · NEON
HELIUM · KRYPTON
XENON

HYDROGEN
NITROGEN · OXYGEN

COMPLETE GAS PRODUCTION PLANTS INSTALLED FOR LOWEST COST OPERATION . . .

FORMING MIXTURES
CARBON DIOXIDE
ACETYLENE

HIGHEST QUALITIES • ANY QUANTITY DELIVERED ANYWHERE

AMERICAN GAS & CHEMICAL CO.
HARRISON, NEW JERSEY • Contracted Complete Service on All Gases

SP&RI

WE'RE BLUSHING WITH MODESTY

Because of what others are saying about the new

STRONGHOLD SCREW PRODUCTS

NET PRICE CATALOG

"Very interesting, well compiled, and the net prices appealed to us."
— *S.L.H. Co., Salt Lake City, Utah*

"A masterpiece of its own."
— *C.S. Co., St. Louis, Mo.*

"Congratulations because you certainly have done a swell job! We were very much surprised to find that your line was as complete as it is."
— *L.A.B. Co., Baltimore, Md.*

"Truly a work of art."
— *J.E. Co., Staunton, Va.*

"The best we ever laid eyes on."
— *H. Industries, Chicago, Ill.*

"It's a humdinger." — *T.R. Co., Chicago, Ill.*

"A very valuable asset to our file, and you may feel confident that we will use it to good advantage."
— *I.C. Products Corp., South Bend, Ind.*

"Certainly unique. Congratulations to you on stepping away from the customary ways of doing things." — *W.F. Mfg. Co., Cincinnati, Ohio*

"Wish to compliment you on its skilful arrangement." — *J.B.G. Mfg. Co., St. Louis, Mo.*

"Something we have been looking for for some time." — *M. Inc., Savannah, Ga.*

FREE

Let our "Net Price Catalog" be your guide to fasteners and *prices*. An up-to-date encyclopedia and specification chart for every purchasing agent and engineer.

MANUFACTURERS SCREW PRODUCTS
270 W. Hubbard St., Chicago 10, Ill.
It's Faster to Phone — WHitehall 4680
Standardize on STRONGHOLD

PASTE THIS COUPON ON YOUR LETTERHEAD
MANUFACTURERS SCREW PRODUCTS
270 W. Hubbard St., Chicago 10, Ill.
Please send me a copy of the new STRONGHOLD "Net Price Catalog."

Name . . . . . .
Position . . . . . .
Company . . . . . .
Address . . . . . .
City, Zone, State . . . . . .

☐ Please send a few samples of your products.
☐ Please quote prices as per attached request.
☐ Check here if you would also like a free copy of our "Pocket Library of Engineering Data," a handy, finger-tip reference to technical information every user of fastener products should have.



Lightweight Champion

A compact, lightweight time delay relay. Setscrew timing adjustable from a fraction of a second to several minutes. For alternating current or direct current operation. Information and literature on request. No obligation.

AGASTAT

Electro-Pneumatic *TIME DELAY RELAY*

ELIZABETH **A'G'A** NEW JERSEY

AMERICAN GAS ACCUMULATOR COMPANY

MASSIVE WINDING CORE
25% More Capacity

Another exclusive Hardwick-Hindle advantage is this great ceramic core of unusually large cross section for the wattage rating—*more* wire, *more* surface and, *less* temperature rise.

And between this ceramic winding core and the rugged die cast base there is ample space for full ventilation to insure low operating temperature for the mounting panel.

This is only one of several exclusive features. Let us tell you of other Hardwick-Hindle advantages in this and in other rheostats, as well as in our resistors.

Our engineering service is always available for specific problems. Write us today.



HARDWICK, HINDLE, INC.
RHEOSTATS and RESISTORS
Subsidiary of THE NATIONAL LOCK WASHER COMPANY
NEWARK 5, N. J. ESTABLISHED 1886 U. S. A.

and chief executive officer of Westinghouse Electric Corp., succeeding George H. Bucher who resigned and is now vice chairman of the board of directors.

AWARDS

SOSTHENES BEHN, president of International Telephone and Telegraph Corp., was awarded the Medal for Merit, highest civilian decoration for wartime service, for fostering extensive research and development which produced radio and telephone equipment used to great advantage by the Army.

FRANK M. FOLSOM, executive vice-president in charge of the RCA Victor Division, Camden, was awarded the Medal for Merit in recognition of outstanding services as Chief of the Procurement Branch of the Navy's office of Procurement and Material.

ARTHUR F. VAN DYCK, assistant to Dr. C. B. Jolliffe at RCA, received the Legion of Merit award for his contributions to the development and

Rear Admiral Monroe Kelly presenting Legion of Merit medal and citation to A. F. Van Dyck

establishment of loran systems in the U. S. Navy. Commander Van Dyck was Officer-in-Charge of Navigational Aids in the Office of the Chief of Naval Operations.

JOHN F. RIDER was presented with the Legion of Merit medal for "exceptional administrative service to the Signal Corps Publication Agency," from which he retired in 1945 as Lieutenant Colonel.

- SOFT SOLDER RINGS AND PREFORMS
- SILVER SOLDER RINGS
- COPPER BRAZING RINGS



For Use With Flame, Oven or Induction Heating

Large range of wire sizes carried in stock for immediate fabrication into Rings and Preforms.

ELECTRONIC SPECIALTIES MANUFACTURING COMPANY
127 North Main Street, Elkhart, Indiana

For FM AM CW RECEPTION in the VHF SPECTRUM

Your requirements for a general-purpose receiver in the v.h.f. spectrum are met by this, the most advanced development in its field. Continuous frequency coverage is provided from 27.8 to 143 mc. in three bands with convenient controls for selecting bands and for switching to FM, AM, or CW reception. The 3-watt audio system is substantially flat from 40 to 15,000 cycles. With hermetically sealed transformers and reactors, oil-impregnated paper capacitors, and moisture proofed wiring, this receiver is suited to mobile or fixed-station service under all climatic conditions. Furnished complete with 15 tubes, speaker, and built-in power supply for 115/230 volt a-c operation. Net price is $322.00 FOB Boston.

Order today from

Immediate Delivery

The RADIO SHACK
167 WASHINGTON ST., BOSTON MASS., U.S.A.

FREE—108-Page Catalog of Electronic Equipment and Components

DEPENDABLE PORTABLE ELECTRIC POWER



For Your Job!...

. . . BUILT IN FIVE SIZES, ranging from 3 K. W. to 15 K. W., these portable electric power plants are manufactured to give dependable service under the most rugged conditions. Write today for specifications.

Models Range from 3000 to 15000 Watts, A.C. 120 to 440 Volts, 50 and 60 Cycles, Single or Three Phase.

DEALERS WANTED! Some profitable franchises still available. Write or wire

PIONEER ELECTRIC CO. 3700 East Olympic Boulevard Los Angeles 23, California

---

VULCAN



TUBULAR BOTTOM OUTLET

This VULCAN HEATING ELEMENT

has proved efficient and economical in

COFFEE URNS
STEAM TABLES
STERILIZERS
WATER HEATERS
AND SIMILAR ARTICLES

If you have a problem involving Electrical Heating Units, write us.

VULCAN ELECTRIC COMPANY
DANVERS 10, MASS.

Makers of a wide variety of Heating Elements for assembly into manufacturers' own products and of Heating Specialties that use electricity.

DC means SC
—IN ALL
RECTIFIER
APPLICATIONS
DC means SC... Selenium Conversion and Selenium Control. Selenium Rectifiers are available in many different ratings and sizes ...each designed to perform an exact and vital function. Selenium Rectifiers are small in size, light weight, efficient, economical and adaptable to all mechanical arrangements. Selenium Rectifiers have no moving parts and require no maintenance. They are simple ...rugged and provide instantaneous and silent operation. A few of the many reasons why DC means SC... Selenium Conversion and Selenium Control. If you use DC... get the facts on SC.
SEND FOR BULLETINS
SELENIUM CORPORATION of AMERICA
1719 WEST PICO BOULEVARD
LOS ANGELES 15, CALIFORNIA
EXPORT DIVISION: FRAZAR & HANSEN
301 CLAY STREET, SAN FRANCISCO, CALIFORNIA

NEW BOOKS

Fundamental Theory of Servomechanisms

By LEROY A. MACCOLL, *Bell Telephone Laboratories, Inc. D. Van Nostrand Co., Inc., New York, N. Y.*, 1945, 130 *pages*, $2.25.

GENERAL THEORY OF LINEAR, continuously operating servomechanisms is studied by the technique of feedback amplifier design. That is, the characteristics of servomechanisms are analysed by studying their frequency and phase characteristics in the complex frequency plane. Stability is treated in the manner of Nyquist's criterion for feedback amplifiers. As a consequence of this treatment, the approach is more intelligible to communication engineers than that of the purely mathematical analysis of the differentiating and integrating action of the servomechanism so frequently used in studying its transient behavior.

The material, originally circulated within the limits of wartime secrecy, covers simple systems in their steady state, transient behavior of servomechanisms, stability, and accuracy. Based on the equations for servo characteristics, means of stabilizing and controlling accuracy are discussed. The work concludes with treatments of oscillating control, sampling, and on-off servomechanisms. A chapter is devoted to a comparison of the transient analysis and the steady-state approach to servo operation in which the merits of the steady-state method used in this text are demonstrated.—F.R.

• • •

Electronics For Engineers

By JOHN MARKUS AND VIN ZELUFF, *Associate Editors*, ELECTRONICS. *McGraw-Hill Book Company, New York* 18, 1945, 390 *pages*, $6.00.

THIS IS A COLLECTION of articles culled from the pages of ELECTRONICS and written by many different engineering authors. According to the preface the editors of the book ". . . have gone through the complete files of the magazine from the first issue (April, 1930) and from this wealth of technical data have selected 142 articles, reference sheets, charts and graphs that have been in greatest demand for their reference value. All of this material

The Type TEC Time Delay Relay allows an adjustable or fixed time delay between operation of a control circuit and subsequent opening or closing of a load circuit.

Its function is to reduce manual supervision and improve quality of the product by automatically controlling industrial processes or electrically operated machinery. It is used extensively in such operations as plastic molding, heat treating, induction heating, mixing, and purging gas fired ovens.

This type of Relay is available with either Automatic or Controlled Reset. Type TEC automatically starts the cycle over again after power interruption. Type TEC-R resumes the cycle at the point of interruption.

Embodying the sturdy construction of the improved Model E design type TEC Time Delay Relay has many specific "use" advantages:

- Large dial for accurate settings.
- Micrometer adjusting knob.
- Progress indicator showing unexpired time cycle.
- Simple screw mounting.
- Clearly marked electrical connections.

If you use "*TIME* as a factor of *CONTROL*" in any type of equipment or process, it will pay you to CONSULT CRAMER.

THE R. W. CRAMER COMPANY, Inc.
Box No. 3
Centerbrook, Conn.

Cramer
SPECIALISTS IN *TIME* AS A FACTOR OF *CONTROL*
INTERVAL · DELAY · CYCLE · IMPULSE · PERCENTAGE

IMMEDIATE DELIVERY!

WRL Multitester

- Sturdy Steel Case
- 30-60 Degree Angle
- Stand it up or Lay it Down

CAT. NO. 16-491

$18.75

TEST LEADS CAT. NO. 17-459 **$.60**

Ranges: DC Volts—0/5/50/250/500 V, AC Volts—0/10/100/500/1000V, DC Mills—0/10/100 Mills. Ohmmeter—Low Range 0-500 Ohms. High Range—0-100,000—1 Meg. 3" Meter with sturdy D'Aronsval movement. Size 5½ x 8 x 3¼.

Phono Amplifier Kits

Complete with tubes, speaker, stamped chassis, resistors and condensers. Many other kits also available. Cat. No. 7-271. $9.50 ea. Lots of 3, ea.... **$9.15**

WRL LOW PRICED TRANSMITTER KITS
15, 35, 70, and 150 Watt types

On our toes at all times to give you the best in radio and electronic devices of all kinds. Immediate delivery to all parts of the world from the heart of America.

WE INVITE INQUIRIES FROM AGENTS, IMPORTERS, BROKERS |

FREE! 52 Page Catalog Packed with savings in radio, electronic, and general merchandise. Send for your copy today.

Handy Tube Base Calculator 25c
Giant Radio Reference Map 15c
Address Dept. E-4 Council Bluffs, Iowa

World Radio LABORATORIES — Everything in Radio — Incorporated

Formerly Wholesale Radio Laboratories

MOLDED TERMINAL STRIPS

COMPLETELY ASSEMBLED
WITH HARDWARE

Available in lengths from 1 to 20 terminals.
Terminal Sizes: 6-32; 8-32; 10-32

Northern Industrial Chemical Company
7-11 ELKINS ST., SO. BOSTON 27, MASS.
36 YEARS OF PLASTIC MOLDING EXPERIENCE

Solves the Problem of Mailing List Maintenance

Probably no other organization is as well equipped as McGraw-Hill to solve the complicated problem of list maintenance during this period of unparalleled change in industrial personnel.

McGraw-Hill Mailing Lists cover most major industries. They are compiled from exclusive sources, and are based on hundreds of thousands of mail questionnaires and the reports of a nation-wide field staff. All names are guaranteed accurate within 2%.

When planning your direct mail advertising and sales promotion, consider this unique and economical service in relation to your product. Details on request.

McGraw-Hill Publishing Co., Inc.
DIRECT MAIL DIVISION
330 West 42nd St., New York, 18, N. Y.

THERE'S A DRAKE SOLDERING IRON FOR EVERY TYPE OF ELECTRONIC WORK

From that mighty mite

the Drake No. 400 to the high-speed production "honey"

the Drake No. 600-10 there is a high quality Drake Soldering Iron "just right" for the job.

Drake Heat Controls and the Drake "Magic Cup" Stand are important soldering aids.

SEE YOUR RADIO PARTS JOBBER

DRAKE ELECTRIC WORKS, INC.
3656 LINCOLN AVE. CHICAGO, ILL.

Send for

It's new—amazingly effective and surprisingly inexpensive. Vibrashock* triple-action unit mounts really absorb vibration and cushion shock. Compare Vibrashock with any other unit type mount—and see the marked improvement in performance. We believe Vibrashock will solve your vibration problems. *trade mark

ROBINSON AVIATION, INC.
Teterboro Air Terminal, Dept. E. 1.
Teterboro, New Jersey
3757 WILSHIRE BLVD., LOS ANGELES 5 CALIFORNIA

Specially Designed To Meet Your Needs

For years Westfield has specialized in custom-made nuts for leading manufacturers.

Conforming rigidly to specifications, they are more dependable and frequently more economical. Consult us on present or post-war needs. Write or wire.

WMP WESTFIELD METAL PRODUCTS CO. INC.

WESTFIELD, MASS.

ATTENUATORS by TECH LABS



MIDGET TYPE 600

"Midget" model is especially designed for crowded apparatus or portable equipment.



STANDARD TYPE 700

- Solid silver contacts and stainless silver alloy wiper arms.
- Rotor hub pinned to shaft prevents unauthorized tampering and keeps wiper arms in perfect adjustment.
- Can be furnished in any practical impedance and db. loss per step upon request.
- TECH LABS can furnish a unit for every purpose.
- Write for bulletin No. 431.

TECH LABORATORIES

Manufacturers of Precision Electrical Resistance Instruments

337 CENTRAL AVE. • JERSEY CITY 7, N. J.

has been carefully checked, edited and condensed where desirable to put it into the best possible form for presentation in a book."

A need for such a book is almost self-evident, for it is the sad but universal experience of subscribers to monthly technical magazines that the material of the new and oncoming issues tends to bury the previously published material. The reader and user; if he makes any attempt, carries on a losing struggle to retain ready access to the articles which he has specially marked for future reference.

The editors have performed a valuable service by bringing together this collection. Theirs is the responsibility for the selections and omissions of material. In the opinion of the reviewer it is a job well done and does credit to their judgment.

The individual papers are grouped into 27 chapters within a self-explanatory alphabetical index. The typography, arrangement and display are excellent. The material is much too rich and varied to make it possible to indicate more than its general scope as given by the chapter headings, as follows: A-F Impedance-Matching Networks, Antennas, Audio Amplifiers, Audio-Circuit Design, Capacitors, Cathode-Ray Tubes, Coaxial Lines, Electronic Heating, Filters, Industrial Control, Iron-Core Transformers and Chokes, Mathematics, Networks, Oscillators, Permanent Magnets, Pulses, Rectifiers, Relays, R-F Coils and Transformers, R-F Impedance-Matching Networks, R-F Power Amplifiers, Sound, Television, Frequency Modulation and Facsimile, Transmission Lines, Tubes, Tuned Circuits, and Wide-Band Amplifiers.

Here is a volume of practical, useful material, the very stuff out of which the practice of electronic engineering is made. Engineers, designers, teachers, and builders of electronic and communication equipment will find in it suggestions and helps which fellow engineers have through the years devised, constructed and passed on out of their own daily practice and experience.—HENRY E. HARTIG

—◇—

2,000 HEAVY BOMBERS with 900 fighter escorts carried a total of 27,000 sets of signal equipment.

Dimensions

Diameter.....2 5/16"
Housing Length.....2 19/32"
Weight, bare.....21 oz.

Announcing
NEW *Ostermotors*
Synchronous and Induction Capacitor Type Motors and Gearmotors

M-31A

Oster No.	Type	Motor	Power Service	Max. H.P. Output	Shaft R.P.M.
LCY LCYR	Motor Gearmotor	Cap. Synch.	115 V 60 C	.0005	1800-3600 30-60
LC LCR	Motor Gearmotor	Cap. Ind.	115 V 60 C	.001	1675-3350 28-57

New precision Ostermotors designed for timing devices, clock and control mechanisms. Highest quality construction assures unvarying performance. Your choice of bronze or ball bearings in motor. Annealed laminations . . . precision gears . . . compact die cast housings . . . practical mounting arrangements.

These new Ostermotors are built to your order; can be furnished with special shafts, gear ratios, or other mechanical and electrical characteristics. They are now in production. Write for further information. . . . *John Oster Manufacturing Co., 4 Main Street, Racine, Wisconsin.*

Other Special Ostermotors

Oster is now in production or going into production on motors listed here. If you need quality motors in these types or sizes, write us today.

	H. P. Range at rated load	R. P. M.	Type	Dia.	Length
E. S.	1/50 — 1/30	1725	Induction Split Phase	3 21/64"	4½" to 5¼"
E. C.	1/50 — 1/30	1725	Induction Capacitor	3 21/64"	4½" to 5¼"
E. U.	1/25 — 1/10	5-10M	Series	3 21/64"	4½" to 5⅞"
K. S.	1/20 — 1/10	1725	Induction Split Phase	4 13/32"	5½" to 8¼"
K. C.	1/20 — 1/10	1725	Capacitor Start & Run	4 13/32"	5½" to 8¼"



Would a vibration meter locate trouble in your WASHER?

Electrical equipment requires super-precision rigidity — dependability. Make sure with

QUADRIGA *Quality Washers*

Washers to specifications, of any type, purpose or material; which can be fabricated by punch press, Flat, Special Dimensions, Irregular Contour, Tension and Spring, Formed and Drawn, Cupped and Finishing etc. Wire Terminals Send for complete catalog.

Also SMALL METAL STAMPINGS, any design ***Prompt delivery***

THE QUADRIGA MANUFACTURING CO.
Inc. 1894 "Half a Century" 221-AW Grand Ave. Chicago 10, Ill.

The COMPLETE STORY of ELECTRONICS written so you can UNDERSTAND it

An accurate, clearly-worded, non-technical account of the seeming miracles that have been accomplished by the modern science of electronics. By electronic means, television, radar, fluorescent lighting, talking pictures, radio, atom - smashing, plastic molding, sound recording, radiography, and other marvels of twentieth-century science are accomplished. This readable and authoritative survey by a member of the staff of the General Electric Research Laboratory is designed to acquaint the interested layman with the fundamental principles, special characteristics, and practical applications of electronics in science, industry and public health.

Just Published

ELECTRONS IN ACTION

By JAMES STOKLEY

320 pages, 5½x8, 91 Illustrations, $3.00

In addition to excellent explanations of such developments as frequency modulation, network television, and the electron microscope, the book presents a clear-cut summary of the sensational advances in the field of atomic energy, including a survey of pioneer work in this field and a factual account of the atomic bomb, based on the authentic Smyth report. The significance of radar and loran for peacetime applications is also thoroughly discussed, and a full chapter is devoted to some of the newest knowledge about the effect of the sun and the moon on radio on the earth.

Seventeen fascinating chapters give you an easy-to-understand picture of the whole field of electronics:

1. Modern Miracles
2. They're Called Electrons
3. Electrons Made Free
4. Putting Them to Work
5. Talking Around the World
6. Seeing Beyond the Horizon
7. Cosmic Electronics
8. Light from Electrons
9. Sounds for the Future
10. Electrons in Overalls
11. Measurement
12. Looking Through Matter
13. Smaller and Smaller
14. Electrons in Medicine
15. Faster and Faster
16. Where It Leads
17. Atomic Energy

Appendix: Radar

What are electrons and where do they come from? How does television work? What is the secret of radar, of loran, of BTO? What is a diode? an ignitron? a klystron? a precipitron? How are pictures and facsimile newspapers transmitted over wires or through the ether? How is sound recorded on motion-picture film and on phonograph records? What is the outlook for postwar developments in electronics?

—These and a great number of related questions are discussed and answered on the basis of current knowledge, for the benefit of the layman interested in electronics—as well as for the specialist in allied fields of engineering, industry, and research.

Send this McGRAW-HILL coupon!

McGraw-Hill Book Co., 330 W. 42 St., New York City 18

Send me Stokley's ELECTRONS IN ACTION for 10 days' examination on approval. In 10 days I will send $3.00, plus few cents postage, or return book postpaid. (Postage paid on cash orders.)

Name .....

Address .....

City and State .....

Company .....

Position .....L. 4-46

For Canadian Prices Write Embassy Book Co., 12 Richmond St. E., Toronto, 1

LOGARITHMIC AC VOLTMETER

WIDE BAND AMPLIFIER



RANGE:
.0005 to 500 volts
—65 VU to +57 VU
Direct Reading
without external
Multipliers

FREQUENCY RESP.
4 C/S to 2 MC/S
±2%

INPUT IMPEDANCE
2 MEGOHMS
15 mmfds.

STABILITY
±1%
105 to 125 volts

INSTRUMENT ELECTRONICS

LITTLE NECK, L. I., N. Y.

253-21 NORTHERN BOULEVARD — BAYSIDE 9-5225

Front or Rear Surface

MIRRORS AND REFLECTORS



FOR TELEVISION, ELECTRONIC, OPTICAL, and SCIENTIFIC APPARATUS

Front or Rear Surface Mirrors and Reflectors made to your specifications.

Closest optical and dimensional tolerances observed.

- EXCEPTIONAL REFLECTIVITY
- WILL NOT TARNISH
- OPAQUE OR SEMI-TRANSPARENT
- HEAT RESISTANT
- PROMPT SERVICE

We invite your inquiries. Samples and quotations will be submitted promptly.

Let Zenith help solve your Mirror and Reflector problems!

ZENITH OPTICAL LABORATORY

SPECIALISTS IN VACUUM DEPOSITION

123 WEST 64th STREET
NEW YORK 23, N. Y.

Backtalk

This department is operated as an open forum where our readers may discuss problems of the electronics industry or comment upon articles which ELECTRONICS has published.

Spoof

FOR A NUMBER of years now work has been proceeding in order to bring perfection to the crudely conceived idea of a machine that would not only supply inverse reactive current for use in unilateral phase detractors, but would also be capable of automatically synchronizing cardinal grammeters. Such a machine is the "Turbo-Encabulator." Basically, the only new principle involved is that instead of power being generated by the relative motion of conductors and fluxes, it is produced by the modial interaction of magneto-reluctance and capacitive directance.

The original machine had a baseplate of prefabulated amulite, surmounted by a malleable logarithmic casing in such a way that the two spurving bearings were in a direct line with the pentametric fan. The latter consisted simply of six hydrocoptic marzelvanes, so fitted to the ambifacient lunar waneshaft that side fumbling was effectively prevented. The main winding was of the normal lotus-o-delta type placed in panendermic semi-boloid slots in the stator, every seventh conductor being connected by a non-reversible tremie pipe to the differential girdlespring on the "up" end of the grammeters.

Forty-one manestically spaced grouting brushes were arranged to feed into the rotor slip-stream a mixture of high S-value phenylhydrobenzamine and five per cent reminative tetryliodohexamine. Both of these liquids have specific pericosities given by $P = 2.5_n^{a \cdot 7}$ where n is the diathetical evolute of retrograde temperature phase disposition and C is Cholmondeley's annular grillage coefficient. Initially, n was measured with the aid of a metapolar refractive pilfrometer (for a description of this ingenious instrument, see L. E. Rum-

CONTACTS

FOR THE FIELD OF ELECTRONICS

Electron Tube Machinery

of every type, — standard, and special design

Specialists in Equipment for the manufacture of Radio Tubes, Cathode Ray Tubes, Fluorescent Lamps, Incandescent Lamps, Neon Tubes, Photo Cells, X-ray Tubes and other glass or electronic products, on production or laboratory basis.

Kahle ENGINEERING COMPANY

1307-1309 Seventh St., North Bergen, N. J.

Strip Insulated Wires

QUICKER... BETTER

with "Speedex"

AUTOMATIC WIRE STRIPPER

...Speeds Production

Strips insulation from all types of wire — instantly, easily, perfectly. Just press the handles and the job is done. Cuts wire too. Strips 800 to 1000 wires per hour. Available for all size solid or stranded wires —No. 8 to No. 30. List Price $6.00.

Write Dept. E for Full Particulars

GENERAL CEMENT MFG. CO.

Rockford, Illinois, U.S.A.

FINE RIBBONS OF TUNGSTEN and MOLYBDENUM

Quality and accuracy in our fabrication of Tungsten & Molybdenum Ribbons have characterized our service to the Electronic industry.

A development of

H. CROSS Co.

15 Beekman St., New York 7, N.Y.

MICROMETER FREQUENCY METER

for checking Transmitters from 1.5 to 56 mc., within 0.01 per cent

LAMPKIN LABORATORIES

Bradenton, Fla., U. S. A.

We manufacture a complete line of equipment

SPOT WELDERS, electric from ¼ to 50 KVA
TRANSFORMERS, special and standard types
INCANDESCENT LAMP manufacturing equipment
FLUORESCENT TUBE MAKING EQUIPMENT
ELECTRONIC EQUIPMENT, vacuum pumps, etc.
WET GLASS SLICING and cutting machines for laboratory use
GENERAL GLASS working machines and burners
COLLEGE GLASS working units for students and laboratory

AC ARC WELDERS from 100 to 400 Amps

EISLER ENGINEERING CO.

731 So. 13th St. (near Avon Ave). Newark, New Jersey

REPAIR YOUR ELECTRIC APPLIANCES WITH NEW AMAZING NICHROCITE

Burned or Broken Electric Heating Elements Repaired Instantly . .

Handy for Home or Industrial Use

Simply overlap ends, apply Nichrocite paste and turn on the current — a perfect weld results. Used by big utility companies and repair shops. Just the thing for that broken or burned out heating element in your electric iron, stove, toaster or heater. Does the job in a jiffy. Trial order, $1; 4 ozs. $2.50; 1 lb. $8.00.

Armstrong Electric Co., Box 861-EM, Minneapolis

MORE RF KILOWATT HOURS PER DOLLAR WITH

F & O TRANSMITTING TUBES

Inquiries Invited—Let us explain how Savings are effected and the F & O greater guarantee.

FREELAND & OLSCHNER PRODUCTS Inc.

611 Baronne St., New Orleans 13, La.

Raymond 4756

High Power Tube Specialists Exclusively (5 KW to 100 KW)

HETERODYNE ELIMINATORS

If you are troubled by heterodyne interference consult

J. L. A. McLaughlin

P. O. Box 529, La Jolla, Calif.

Your Inquiry Will Have Special Value

if you mention that it is in response to advertising in this publication. Advertisers value such acknowledgments highly; so does the publisher. You benefit—as a reader—in the enlarged future service such acknowledgments help to make possible.

REX RHEOSTAT COMPANY, BALDWIN, L. I., N. Y.

PROTECTED & UNPROTECTED
RHEOSTATS
WITH LUBRICATED CONTACTS
ROTARY DRIVE RHEOSTATS
WITHOUT BACK LASH
PROTECTED & UNPROTECTED
ADJUSTABLE RESISTORS
UP TO 1000 WATT
PROMPT SHIPMENTS

18 YEARS IN RADIO

GET THIS *New* CATALOG By This Old Firm

Latest developments in radio and electronic parts and devices, newest ham gear, gadgets for experimenters, bargains in war surplus items.

FREE TO YOU

Mail the coupon below and get this new catalog FREE.

BURSTEIN-APPLEBEE CO.,
1012 McGee, Kansas City 6, Mo.

Send me FREE catalog advertised in Electronics.

I AM_____
STATE CONNECTION IN INDUSTRY

NAME_____

ADDRESS_____

TOWN_____ STATE_____

PROFESSIONAL SERVICES

ASSOCIATED ELECTRONICS COMPANY *INDUSTRIAL ENGINEERING SPECIALISTS*
Engineering Research & Development
Product Design — Market Research
Sales Brochures — Technical Manuals
Field Surveys — Laboratory Analysis
Complete Engineering Service For All Industries
132 Nassau Street, New York 7, N. Y.

F. T. FISHER'S SONS LIMITED
Consulting Engineers
Broadcast Transmitters, Antenna Systems, Studio Equipment, Mobile and Fixed Communication Systems.
1425 Dorchester St. West, Montreal

MICHAEL BOZOIAN
Consulting Service In Electronics
Instrumentation & Controls Design—Development—Models Literature & Patent Survey Recommendations For New Laboratories.
Telephone 8521
702 Fifth Street *Ann Arbor, Mich.*

PAUL E. GERST & CO.
CONSULTING ENGINEERS
Specialists in
Electrical Product Design
El. Machinery, Apparatus & Applications
El. Appliances, Hi-Frequency Apparatus
Electronics, Radio Communication
205 W. Wacker Dr. Chicago 6, Ill.

H. RUSSELL BROWNELL
Consulting Engineer
Specializing in Measurements & Testing Instruments & Techniques - Electrical - Electronic - Magnetic.
188 West 4th St. New York 14, N. Y.

HODGSON & ASSOCIATES
Physics, Mathematics, Research, Development & Patent Consultants.
Satisfaction guaranteed. Submit your problem for a preliminary survey without cost.
Sherman Oaks, California

COOPER & FLEMING
Consulting Electronic Engineers
AM & FM BROADCASTING.
Industial & Medical Electronics
420 Market St. Sutter 8854 San Francisco, Calif.

J. L. A. McLAUGHLIN
Designer of
Communications Receivers
Specializing in the elimination of heterodyne interference.
P. O. Box 529, La Jolla, Calif.

E. STUART DAVIS
Consulting Engineer
Research—Design—Development
Radio - Carrier Current - Supersonics - Radiant Energy - Control and Measurement - Methods and Devices, Communication - Transportation & Industrial applications.
Marine Laboratory facilities aboard the yacht "ELECTRON"
422 N. E. River Drive Ft. Lauderdale, Florida

NATIONAL DESIGN SERVICE
Designers and Developers of
FACTORY TEST EQUIPMENT
TELEVISION R.F. SWEEP GENERATORS
F.M. SIGNAL GENERATORS
COMPLETE CENTRALIZED MODULATED SYSTEMS
96 Liberty St. New York 6, N. Y.

STANLEY D. EILENBERGER
Consulting Engineer
INDUSTRIAL ELECTRONICS
Design—Development—Models
Complete Laboratory and Shop Facilities
6309-13—27th Ave.
Kenosha, Wis. Telephone 2-4213

ALBERT PREISMAN
Consulting Engineer
Specializing in Television and Pulse Techniques, Video Amplifiers, Industrial Applications.
616 St. Andrews Lane, Silver Spring, Md.

ELECTRONIC ENGINEERS
Designers and Consultants
Radio and Electronic Product Design
Radio Equipment to Order
Industrial Electronic Devices to Order
Broadcast Station Allocation
Complete Research and Constructional Facilities
Phone Citrus 1-6884
611 E. Garfield Ave. Glendale 5, California

JOSEPH RAZEK, Ph.D.
Consulting Physicist
Electrical and Mechanical Engineering Problems
Instruments and Control Devices Electronics
Specialists in Colorimetry, Spectrophotometry and Industrial Color Control
Laboratory and Shop Facilities
202 Darby Road Lianerch, Pa.
Phone Hilltop 6910

ELECTRONIC RESEARCH ASSOCIATES
ERA will apply progressive, war-proven development in electronic research . . . *counting . . . timing . . . measuring . . . industrial controls* . . . to your manufacturing advantage.
Box 333, 305 Linden Av., San Francisco, Cal.

G. W. RHEIN
Engineering Consultant
Radio Communication Electronics
Complete Development and design for manufacture with engineering models.
St. Paris Pike Springfield, Ohio

ELM LABORATORIES
Research and Design
RADIO TRANSMITTERS AND RECEIVERS
Designs for Home Radios, Electro-Mechanical Devices and Components.
20 South Broadway Dobbs Ferry, New York
Phone—Dobbs Ferry 4068

PAUL D. ZOTTU
Consulting Engineer
INDUSTRIAL ELECTRONICS
High Frequency Dielectric and Induction Heating Applications, Equipment Selection, Equipment and Component Design, Development, Models.
314 Washington St. Newton, Mass.
BIG-0240

pelverstein in "Zeitschrift für Elektrotechnistatischs-Donnerblitze" vol. vii), but up to the present date nothing has been found to equal the transcendental hopper dadoscope. (See "Proceedings of the Peruvian Academy of Skatological Sciences" June, 1914.)

Electrical engineers will appreciate the difficulty of nubing together a regurgitative purwell and a supramitive wennel-sprocket. Indeed, this proved to be a stumbling block to further development until, in 1942, it was found that the use of anhydrous nangling pins enabled a kryptonastic bolling shim to the tankered.

The early attempts to construct a sufficiently robust spiral decommutator failed largely because of a lack of appreciation of the large quasipiestic stresses in the gremlin studs; the latter were specially designed to hold the roffit bars to the spamshaft. When, however, it was discovered that wending could be prevented by a simple addition to the living sockets, almost perfect running was secured.

The operating point is maintained as near as possible to the h.f. rem peak by constantly fromaging the bitumogenous spandrels. This is a distinct advance on the standard nivel-sheave in that no dramcock oil is required after the phase detractors have remissed.

Undoubtedly, the turbo-encabulator has now reached a very high level of technical development. It has been successfully used for operating nofer trunnions. In addition, whenever a barescent skor motion is required, it may be employed in conjunction with a drawn reciprocating dingle arm to reduce sinusoidal depleneration.

EDITOR'S NOTE. The above description of the turbo-encabulator is taken from the *Industrial Bulletin* of Arthur D. Little Company, Cambridge, Mass. Unfortunately no photographs of the device are available at the moment. It is hoped that when military restrictions are loosened a bit and Arthur D. Little engineers are not so busy more data will be published on what seems to be a most important industrial instrument. Despite the lucid description quoted above more information is definitely needed.

JOHN AMBROSE FLEMING, discoverer of the diode, wrote more than 90 important scientific treatises between 1892 and 1934. His 1,700 page book on electromagnetic waves is considered one of the classics of radio literature.



A McGRAW-HILL PUBLICATION

FOR HIPERM ALLOY TRANSFORMERS

The UTC Hiperm alloy audio transformers are specifically designed for portable and compact service. While light in weight and small in dimensions, neither dependability nor fidelity has been sacrificed. The frequency characteristic of the Hiperm alloy audio units is uniform from 30 to 20,000 cycles. These units are similar in general design and characteristics to the famous Linear Standard audio Series.

UTC Hiperm Alloy Transformers Feature

- True Hum Balancing Coil Structure
- Balanced Variable Impedance Line
- Reversible Mounting
- Alloy Shields
- Multiple Coil, Semi-Toroidal Coil Structure
- High Fidelity

FOR IMMEDIATE DELIVER

From Your Distributor

Type No.	Application	Primary Impedance	Secondary Impedance	± 1 db from	Max. Level	Max Unbal. DC in primary	List Price
HA-100	Low impedance mike, pickup, or multiple line to grid.	50, 125, 200, 250, 333, 500 ohms	60,000 ohms in two sections	30–20,000	+22 DB	5 MA	16.25
HA-100X	Same as above but with tri-alloy internal shield to effect very low hum pickup.						20.90
HA-101	Low impedance mike, pickup, or multiple line to push-pull grids.	50, 125, 200, 250, 333, 500 ohms	120,000 ohms overall, in two sections	30–20,000	+22 DB	5 MA	18.55
HA-101X	Same as above but with tri-alloy internal shield to effect very low hum pickup.						23.20
HA-108	Mixing, low impedance mike, pickup or multiple line.	50, 125, 200, 250, 333, 500 ohms	50, 125, 200, 250, 333, 500 ohms	30–20,000	+22 DB	0	16.25
HA-106	Single plate to push-pull grids	8,000 to 15,000 ohms	135,000 ohms 1.5:1 ratio, each side	30–20,000	+22 DB	1 MA	13.90
HA-113	Single plate to multiple line.	8,000 to 15,000 ohms	50, 125, 200, 250, 333, 500 ohms	30–20,000	+22 DB	5 MA	15.65
HA-134	Push-pull 89's or 2A3's to line.	5,000 to 10,000 ohms	50, 125, 200, 250, 300, 500 ohms	30–20,000	+32 DB	5 MA	17.40
HA-135	Push-pull 2A3's to voice coil.	3,000 to 5,000 ohms	30, 20, 15, 10, 7.5, 5, 2.5, 1.2	30–20,000	+32 DB	5 MA	16.25

The above listing includes only a few of the many Hiperm Alloy Transformers available . . . write for catalog.

United Transformer Corp.

150 VARICK STREET NEW YORK 13, N. Y.

EXPORT DIVISION: 13 EAST 40th STREET, NEW YORK 16, N. Y., CABLES: "ARLAB"

electronics

A McGRAW-HILL PUBLICATION

MAY • 1946

UHF COLOR TELEVISION.....Cover
Driver and final r-f amplifier of the CBS color television transmitter developed by the laboratories of Federal Telephone and Radio Corporation

PATENT PUZZLE, by Donald K. Lippincott... 92
Over 6,000 microwave patent applications were filed during the war, and few were issued

MEASUREMENT OF OCEAN WAVES GENERATED BY ATOMIC BOMBS, by Norman J. Holter.....94
Bikini Atoll test plans, instruments and methods

ENGINEERING APPROACH TO WAVE GUIDES, by Theodore Moreno 99
Advantages of guides at microwaves and the factors determining a proper choice of their dimensions

WHERE COLOR TELEVISION STANDS, by Donald G. Fink.....104
Suggestions for needed research, intended to clarify the technical factors behind an important controversy

ELECTRONIC HEATING IN THE FURNITURE INDUSTRY, by E. S. Winlund 108
Fundamentals of applying high-frequency power to set bonding-glues in joints, core lumber and plywood

JAPANESE MAGNETRONS, by Marvin Hobbs.....114
Status of progress at war's end, with technical details of both experimental and production models for radar

RECORDING CAA TRAFFIC CONTROL INSTRUCTIONS, by K. M. MacIlvain.....116
Flight instructions are automatically recorded on flexible belts suitable for permanent filing

RADIOSONDE TELEMETERING SYSTEMS, by V. D. Hauck, J. R. Cosby and A. B. Dember.....120
Details of latest transmitter circuits using temperature and humidity-responsive elements and dry-pack battery

PULSE-MODULATED RADIO RELAY EQUIPMENT, by John J. Kelleher.....124
Pulse-modulated eight-channel multiplex radio communication equipment for links up to 200 miles long

DESIGN DATA FOR BEADED COAXIAL LINES, by C. R. Cox 130
Procedures for finding characteristic impedance, optimum insulator spacing, attenuation, and maximum power

TWO-TERMINAL OSCILLATOR, by Murray G. Crosby.....136
Feedback in a two-stage amplifier provides a convenient oscillator for various applications

RADAR FOR BLIND BOMBING—PART I, by J. V. Holdam, S. McGrath and A. D. Cole.....138
Technical details of H2X airborne microwave radar, including new phanastron circuit for precise time-delays

GATE CIRCUIT FOR CHRONOGRAPHS, by L. B. Tooley.....144
Two thyratrons provide a simple switching system controlling a succeeding amplifier

2-MC SKY-WAVE TRANSMISSION, by J. A. Pierce.....146
Timing accuracy to within a few miscroseconds over long distances is possible with the nocturnal *E* layer

CIRCUITS FOR SUBMINIATURE TUBE.....154
Circuits for very small triode suitable for lightweight, compact applications

PHASE-SHIFTER NOMOGRAPH, by Raymond E. Lafferty.....158
Simplifies design calculations for bridge-type phase-shifting network covering range from 0 to 180 degrees

CROSSTALK 91	TUBES AT WORK..... 190	NEW BOOKS..... 320
REFERENCE SHEET..... 158	ELECTRON ART..... 208	BACKTALK 328
INDUSTRIAL CONTROL..... 160	NEW PRODUCTS..... 236	INDEX TO ADVERTISERS..... 337
	NEWS OF THE INDUSTRY..... 284	

KEITH HENNEY, *Editor;* **DONALD G. FINK,** *Executive Editor;* W. W. MacDonald, *Managing Editor;* John Markus, Vin Zeluff, *Associate Editors;* Frank Rockett, A. A. McKenzie, *Assistant Editors;* J. A. Myers, *Chicago Editor;* Frank Haylock, *Los Angeles Editor;* Gladys T. Montgomery, *Washington Editor;* Jeanne M. Heron, *Make-up Editor;* Jeanne E. Grolimund, *Editorial Assistant;* Harry Phillips, *Art Director;* Eleanore Luke, *Art Assistant*

H. W. MATEER, *Publisher;* J. E. Blackburn, Jr., *Director of Circulation, Electronics;* Stacy May, *Director of Economic Staff;* Wallace B. Blood, *Manager*

D. H. Miller, H. R. Denmead, Jr., *New York;* Ralph H. Flynn, H. D. Randall, Jr., *New England;* F. P. Coyle, R. E. Miller, *Philadelphia;* C. D. Wardner, A. F. Tischer, *Chicago;* E. J. Smith, *Cleveland;* J. W. Otterson, *San Francisco;* Roy N. Phelan, *Los Angeles;* Ralph C. Maultsby, *Atlanta*

Contents Copyright, 1946, by McGraw-Hill Publishing Company, Inc., All Rights Reserved

McGRAW-HILL PUBLISHING COMPANY, INCORPORATED
JAMES H. McGRAW, Founder and Honorary Chairman

PUBLICATION OFFICE 99-129 North Broadway, Albany 1, N. Y., U. S. A.
EDITORIAL AND EXECUTIVE OFFICES 330 West 42nd St., New York 18, N. Y., U. S. A.

James H. McGraw, Jr., President; Curtis W. McGraw, Senior Vice-President and Treasurer; Howard Ehrlich, Vice-President and General Business Manager; Eugene Duffield, Editorial Assistant to the President; Joseph A. Gerardi, Secretary; and J. E. Blackburn, Jr., Vice-President (for circulation operations).
ELECTRONICS, May, 1946, Vol. 19; No. 5. Published monthly, price 50c a copy. Directory issue $1.00. Allow at least ten days for change of address. All communications about subscriptions should be addressed to the Director of Circulation.
Subscription rates—United States and possessions, Mexico, Central and South American countries, $5.00 a year, $8.00 for two years, $10 for three years. Canada (Canadian funds accepted) $5.50 a year, $9.00 for two years, $11.00 for three years. All other countries $7.00 for one year, $14.00 for three years. Please indicate position and company connection on all subscription orders. Entered as Second Class matter August 29, 1936, at Post Office, Albany, New York, under the Act of March 3, 1879. BRANCH OFFICES: 520 North Michigan Avenue, Chicago 11, Ill.; 68 Post Street, San Francisco 4; Aldwych House, Aldwych, London, W.C. 2; Washington, D. C. 4; Philadelphia 2; Cleveland 15; Detroit 26; St. Louis 8; Boston 16; Atlanta 3, Ga.; 621 So. Hope St., Los Angeles 14; 738-9 Oliver Building, Pittsburgh 22.

HERE ARE 2 Ways to Stop Radio Noise



The Old Way

9 separate parts
16 soldered connections
14 mounting fastenings
5 sources of supply

UNCERTAIN RESULTS

The Tobe Way

1 compact unit
4 simple connections
1 convenient mounting
1 responsible supplier

GUARANTEED PERFORMANCE

Each of these two methods eliminates radio noise . . . but one makes needless work for engineering, purchasing, and assembly departments, while the other relieves them of the entire burden of interference elimination. Tobe FILTERIZING makes your product radio-silent . . . simply, economically, dependably. And the "FILTERIZED" label, furnished free to Filterette users, helps build sales by telling the public that your product makes no radio noise. Ask us for details of this trouble-saving, sales-building service: we'll tell you all about it at no obligation.

SUPPRESS MAN-MADE RADIO STATIC
TOBE
FILTERIZED

TOBE DEUTSCHMANN CORPORATION - CANTON, MASSACHUSETTS

ORIGINATORS OF FILTERETTES • • • THE ACCEPTED CURE FOR RADIO NOISE